



10 INDUSTRIAL AVE,
SUITE 3
MAHWAH NJ 07430

PHONE: 201.684.0055
FAX: 201.684.0066

June 5, 2017

Melanie A. Bachman
Executive Director
Connecticut Siting Council
10 Franklin Square
New Britain, CT 06051

Kyle Richers
10 Industrial Ave
Mahwah, NJ 07430
908-447-4716
krichers@transcendwireless.com

Notice of Exempt Modification
130 Vernon Road, Bolton, CT 06043
Latitude- 41.802648
Longitude- -72.441213

Dear Ms. Bachman,

T-Mobile currently maintains (4) existing antennas at the 130' level of the existing 150' guyed tower located at 130 Vernon Road in Bolton, CT. The tower and property is owned by Mountaintop Enterprises, Inc. T-Mobile intends to maintain the same antenna configuration as existing, but install (2) new Tower Mounted Amplifiers and (4) 1-5/8" coax cables.

This facility was approved by the Town of Bolton on September 4, 2001. A copy of this approval is attached. This approval did not come with conditions.

Please accept this letter as notification pursuant to Regulations of Connecticut State Agencies 16-50j-73, for construction that constitutes an exempt modification pursuant to R.C.S.A. 16-50j-72(b)(2). In accordance with R.C.S.A. 16-50j-73, a copy of this letter is being sent to Robert Morra, First Selectman of the Town of Bolton, as well as the tower and property owner.

The planned modifications to the facility fall squarely within those activities explicitly provided for in R.C.S.A. 16-50j-72(b)(2).

1. The proposed modifications will not result in an increase in the height of the existing structure.
2. The proposed modifications will not require the extension of the site boundary.
3. The proposed modifications will not increase noise levels at the facility by six decibels or more, or to levels that exceed state and local criteria.
4. The operation of the replacement antennas will not increase radio frequency emissions at the facility to a level at or above the Federal Communications Commission safety standard,
5. The proposed modifications will not cause a change or alteration in the physical or environmental characteristics of the site.

6. The existing structure and its foundation can support the proposed loading with certain modifications.

For the foregoing reason, T-Mobile respectfully submits that the proposed modifications to the above-referenced telecommunications facility constitute an exempt modification under R.C.S.A. 16-50j-72(b)(2).

Sincerely,

Kyle Richers

Kyle Richers

10 Industrial Ave, Suite 3

Mahwah, New Jersey 07430

908-447-4716

krichers@transcendwireless.com

Attachments:

CC: The Honorable Robert R. Morra, First Selectman, Town of Bolton

Jim Rupert, Zoning Enforcement Officer, Town of Bolton

Mountaintop Enterprises, Inc. – as property and tower owner



TOWN OF BOLTON

222 Bolton Center Rd, Bolton, CT 06043

LAND USE DEPARTMENT PERMIT APPLICATION

15-21-9

PLEASE CONTACT THE LAND USE DEPARTMENT AT 649-8066 TO SCHEDULE INSPECTIONS OR FOR FINAL INSPECTION UPON COMPLETION TO ISSUE CERTIFICATE

- 1. PERMIT TYPE -- BUILDING ELECTRICAL _____ PLUMBING _____ HEATING _____
- 2. ADDRESS OF WORK 130 Vernon Road ZONE _____
- 3. PROPERTY OWNER Mountaintop Enterprises Inc.
ADDRESS PO Box 9219, Bolton, CT 06043 TELEPHONE # 860 647 7772
- 4. APPLICANT Milton R. Hathaway
ADDRESS PO Box 9219, Bolton, CT 06043 TELEPHONE # 860 647 7772

I hereby agree to conform to all the requirements of the Laws of the State of CT, the Ordinances of the Town of Bolton, all stipulations of this application, and to notify the Building Official of any alteration in the plans or specifications of the building for which this permit is asked. And agree that this building is to be located the proper distance from all street lines, side yard lines and required distances from all other zones and is located in a zone in which this building and its use is allowed. This permit expires one (1) year from date of approval.

Milton R. Hathaway
APPLICANT

9-31-01
DATE

Proof of Workers Compensation Coverage

I as owner or sole proprietor claim exemption and intend to not act as a general contractor or principal employer.

Ronald Bostrom 9/4/01
PERMIT APPROVED - DATE
BUILDING OFFICIAL

n/a
PLAN APPROVED - DATE
HEALTH DISTRICT/SANITARIAN

5. OTHER REQUIRED PERMIT APPLICATION(S) - TYPE Town of Bolton Zoning Permit

6. FLOODPLAIN: N Y _____ DESCRIPTION _____

7. FEE SCHEDULE

ESTIMATED VALUE OF ALL WORK \$ 90,000

| | | |
|------------------------|------------|-----------------|
| <u>Estimated Value</u> | <u>Fee</u> | |
| \$ 1 - 1000 | \$20 | |
| each additional \$1000 | \$12 | (standard fees) |
| or fraction thereof | | |



----- DRIVEWAY PERMIT FEE: \$30
----- RETURNABLE DRIVEWAY PERMIT BOND: \$1,000.00

TOTAL PERMIT FEE \$ 1,088.00

SEP - 4 2001

150'

map



Property Information

Property ID 09013012-02-3
Location 130 VERNON RD
Owner MOUNTAINTOP ENTERPRISES INC



**MAP FOR REFERENCE ONLY
 NOT A LEGAL DOCUMENT**

CRCOG makes no claims and no warranties, expressed or implied, concerning the validity or accuracy of the GIS data presented on this map.

130 VERNON RD

Location 130 VERNON RD

Assessment \$391,370

Mblu 02/ / 3/ /

Appraisal \$739,300

Owner MOUNTAIN TOP ENTERPRISES INC

PID 1982

Building Count 1

Current Value

| Appraisal | |
|----------------|-----------|
| Valuation Year | Total |
| 2013 | \$739,300 |

| Assessment | |
|----------------|-----------|
| Valuation Year | Total |
| 2013 | \$391,370 |

Owner of Record

Owner MOUNTAIN TOP ENTERPRISES INC

Sale Price \$0

Co-Owner

Certificate

Address PO BOX 9219
BOLTON, CT 06043

Book & Page 166/656
Sale Date 10/01/2014

Instrument 24

Ownership History

| Ownership History | | | | | |
|------------------------------|------------|-------------|-------------|------------|------------|
| Owner | Sale Price | Certificate | Book & Page | Instrument | Sale Date |
| MOUNTAIN TOP ENTERPRISES INC | | | 166/656 | 24 | 10/01/2014 |

Building Information

Building 1 : Section 1

Year Built: 1980

Living Area: 2032

Building Percent 76

Good:

| Building Attributes | |
|---------------------|------------------|
| Field | Description |
| STYLE | Equipment Garage |
| Stories: | 1.5 |
| Occupancy | 1.00 |


| | |
|------------------|----------------|
| Exterior Wall 1 | Board & Batten |
| Exterior Wall 2 | |
| Roof Structure | Gable |
| Roof Cover | Asphalt |
| Interior Wall 1 | Minimum |
| Interior Wall 2 | |
| Interior Floor 1 | Minimum |
| Interior Floor 2 | |
| Heating Fuel | None |
| Heating Type | None |
| % Central Air | 0 |
| Frame Type | WOOD FRAME |
| Fin. Bsmt. Area | |

Building Photo



(PhotoHandler.ashx?pid=1982&bid=1982)

Building Layout



| Building Sub-Areas | | | Legend |
|--------------------|-----------------------|------------|-------------|
| Code | Description | Gross Area | Living Area |
| BAS | First Floor | 2032 | 2032 |
| BSM | Basement | 1696 | 0 |
| UHS | Unfinished Half Story | 1696 | 0 |
| | | 5424 | 2032 |

Extra Features

| Extra Features | Legend |
|----------------------------|--------|
| No Data for Extra Features | |

Land

Land Use

Land Line Valuation

Zone R-3

Size (Acres) 30.3

Depth

Assessed Value \$343,470

Appraised Value \$670,800

Outbuildings

| Outbuildings | | | | | Legend |
|---------------------|--------------------|-----------------|------------------------|--------------|---------------|
| Code | Description | Sub Code | Sub Description | Size | Bldg # |
| SHD1 | Shed | FR | Frame | 192.00 S.F. | 1 |
| SHD1 | Shed | FR | Frame | 200.00 S.F. | 1 |
| BRN1 | 1 Story Barn | FR | Frame | 4000.00 S.F. | 1 |
| CELL | Cell Tower | | | 150.00 FEET | 1 |
| CELL | Cell Tower | | | 200.00 FEET | 1 |
| SHD1 | Shed | FR | Frame | 400.00 S.F. | 1 |

Valuation History

| Appraisal | |
|-----------------------|--------------|
| Valuation Year | Total |
| 2014 | \$739,300 |
| 2013 | \$692,200 |

| Assessment | |
|-----------------------|--------------|
| Valuation Year | Total |
| 2014 | \$391,370 |
| 2013 | \$385,790 |

(c) 2014 Vision Government Solutions, Inc. All rights reserved.

RADIO FREQUENCY EMISSIONS ANALYSIS REPORT
EVALUATION OF HUMAN EXPOSURE POTENTIAL
TO NON-IONIZING EMISSIONS

T-Mobile Existing Facility

Site ID: CT11180C

Bolton Ct.._1
130 Vernon Road
Bolton, CT 06043

September 30, 2016

EBI Project Number: 6216004445

| Site Compliance Summary | |
|--|------------------|
| Compliance Status: | COMPLIANT |
| Site total MPE% of FCC general public allowable limit: | 13.52 % |

September 30, 2016

T-Mobile USA
Attn: Jason Overbey, RF Manager
35 Griffin Road South
Bloomfield, CT 06002

Emissions Analysis for Site: **CT11180C – Bolton Ct.,_1**

EBI Consulting was directed to analyze the proposed T-Mobile facility located at **130 Vernon Road, Bolton, CT**, for the purpose of determining whether the emissions from the Proposed T-Mobile Antenna Installation located on this property are within specified federal limits.

All information used in this report was analyzed as a percentage of current Maximum Permissible Exposure (% MPE) as listed in the FCC OET Bulletin 65 Edition 97-01 and ANSI/IEEE Std C95.1. The FCC regulates Maximum Permissible Exposure in units of microwatts per square centimeter ($\mu\text{W}/\text{cm}^2$). The number of $\mu\text{W}/\text{cm}^2$ calculated at each sample point is called the power density. The exposure limit for power density varies depending upon the frequencies being utilized. Wireless Carriers and Paging Services use different frequency bands each with different exposure limits, therefore it is necessary to report results and limits in terms of percent MPE rather than power density.

All results were compared to the FCC (Federal Communications Commission) radio frequency exposure rules, 47 CFR 1.1307(b)(1) – (b)(3), to determine compliance with the Maximum Permissible Exposure (MPE) limits for General Population/Uncontrolled environments as defined below.

General population/uncontrolled exposure limits apply to situations in which the general public may be exposed or in which persons who are exposed as a consequence of their employment may not be made fully aware of the potential for exposure or cannot exercise control over their exposure. Therefore, members of the general public would always be considered under this category when exposure is not employment related, for example, in the case of a telecommunications tower that exposes persons in a nearby residential area.

Public exposure to radio frequencies is regulated and enforced in units of microwatts per square centimeter ($\mu\text{W}/\text{cm}^2$). The general population exposure limit for the 700 MHz Band is approximately 467 $\mu\text{W}/\text{cm}^2$, and the general population exposure limit for the 1900 MHz (PCS) and 2100 MHz (AWS) bands is 1000 $\mu\text{W}/\text{cm}^2$. Because each carrier will be using different frequency bands, and each frequency band has different exposure limits, it is necessary to report percent of MPE rather than power density.

Occupational/controlled exposure limits apply to situations in which persons are exposed as a consequence of their employment and in which those persons who are exposed have been made fully aware of the potential for exposure and can exercise control over their exposure. Occupational/controlled exposure limits also apply where exposure is of a transient nature as a result of incidental passage through a location where exposure levels may be above general population/uncontrolled limits (see below), as long as the exposed person has been made fully aware of the potential for exposure and can exercise control over his or her exposure by leaving the area or by some other appropriate means.

Additional details can be found in FCC OET 65.

CALCULATIONS

Calculations were done for the proposed T-Mobile Wireless antenna facility located at **130 Vernon Road, Bolton, CT**, using the equipment information listed below. All calculations were performed per the specifications under FCC OET 65. Since T-Mobile is proposing highly focused directional panel antennas, which project most of the emitted energy out toward the horizon, all calculations were performed assuming a lobe representing the maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was focused at the base of the tower. For this report the sample point is the top of a 6-foot person standing at the base of the tower.

For all calculations, all equipment was calculated using the following assumptions:

- 1) 2 UMTS channels (PCS Band - 1900 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 30 Watts per Channel.
- 2) 2 LTE channels (AWS Band – 2100 MHz) were considered for each sector of the proposed installation. These Channels have a transmit power of 60 Watts per Channel
- 3) 1 LTE channel (700 MHz Band) was considered for each sector of the proposed installation. This channel has a transmit power of 30 Watts.
- 4) All radios at the proposed installation were considered to be running at full power and were uncombined in their RF transmissions paths per carrier prescribed configuration. Per FCC OET Bulletin No. 65 - Edition 97-01 recommendations to achieve the maximum anticipated value at each sample point, all power levels emitting from the proposed antenna installation are increased by a factor of 2.56 to account for possible in-phase reflections from the surrounding environment. This is rarely the case, and if so, is never continuous.

- 5) For the following calculations the sample point was the top of a 6-foot person standing at the base of the tower. The maximum gain of the antenna per the antenna manufactures supplied specifications minus 10 dB was used in this direction. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 6) The antennas used in this modeling are the **Ericsson AIR21 B4A/B2P** 1900 MHz (PCS) and 2100 MHz (AWS) channels and the **Commscope SBNH-1D65C** for 700 MHz and 2100 MHz (AWS) channels. This is based on feedback from the carrier with regards to anticipated antenna selection. The **Ericsson AIR21 B4A/B2P** has a maximum gain of **15.9 dBd** at its main lobe at 1900 MHz and 2100 MHz. The **Commscope SBNH-1D65C** has a maximum gain of **15.1 dBd** at its main lobe at 1900 MHz and a maximum gain of **13.6 dBd** at its main lobe at 700 MHz. The maximum gain of the antenna per the antenna manufactures supplied specifications, minus 10 dB, was used for all calculations. This value is a very conservative estimate as gain reductions for these particular antennas are typically much higher in this direction.
- 7) The antenna mounting height centerline of the proposed antennas is **130 feet** above ground level (AGL).
- 8) Emissions values for additional carriers were taken from the Connecticut Siting Council active database. Values in this database are provided by the individual carriers themselves.
- 9) All calculations were done with respect to uncontrolled / general public threshold limits.

T-Mobile Site Inventory and Power Data

| Sector: | A | Sector: | B |
|--------------------|--------------------------------|--------------------|--------------------------------|
| Antenna #: | 1 | Antenna #: | 1 |
| Make / Model: | Ericsson AIR21 B4A/B2P | Make / Model: | Ericsson AIR21 B4A/B2P |
| Gain: | 15.9 dBd | Gain: | 15.9 dBd |
| Height (AGL): | 130 | Height (AGL): | 130 |
| Frequency Bands | 1900 MHz(PCS) / 2100 MHz (AWS) | Frequency Bands | 1900 MHz(PCS) / 2100 MHz (AWS) |
| Channel Count | 4 | Channel Count | 4 |
| Total TX Power(W): | 180 | Total TX Power(W): | 180 |
| ERP (W): | 7,002.81 | ERP (W): | 7,002.81 |
| Antenna A1 MPE% | 1.64 | Antenna B1 MPE% | 1.64 |
| Antenna #: | 2 | Antenna #: | 2 |
| Make / Model: | Commscope SBNH-1D65C | Make / Model: | Commscope SBNH-1D65C |
| Gain: | 13.6 dBd | Gain: | 13.6 dBd |
| Height (AGL): | 130 | Height (AGL): | 130 |
| Frequency Bands | 700 MHz | Frequency Bands | 700 MHz |
| Channel Count | 1 | Channel Count | 1 |
| Total TX Power(W): | 30 | Total TX Power(W): | 30 |
| ERP (W): | 687.26 | ERP (W): | 687.26 |
| Antenna A2 MPE% | 0.34 | Antenna B2 MPE% | 0.34 |

| Site Composite MPE% | |
|---------------------------|----------------|
| Carrier | MPE% |
| T-Mobile (Per Sector Max) | 1.98 % |
| AT&T | 1.31 % |
| Verizon Wireless | 2.71 % |
| Sprint | 0.74 % |
| Nextel | 0.32 % |
| Bolton Radio Station | 0.00 % |
| Commsite Internat'l | 0.04 % |
| Metrocall | 0.12 % |
| Pagemart | 2.30 % |
| AirTouch | 0.63 |
| Conn. Radio | 0.23 |
| Eversource | 3.14 |
| Site Total MPE %: | 13.52 % |

| | |
|--------------------------|----------------|
| T-Mobile Sector A Total: | 1.98 % |
| T-Mobile Sector B Total: | 1.98 % |
| T-Mobile Sector C Total: | 1.98 % |
| Site Total: | 13.52 % |

| T-Mobile _per sector | # Channels | Watts ERP (Per Channel) | Height (feet) | Total Power Density ($\mu\text{W}/\text{cm}^2$) | Frequency (MHz) | Allowable MPE ($\mu\text{W}/\text{cm}^2$) | Calculated % MPE |
|------------------------------|------------|-------------------------|---------------|---|-----------------|---|------------------|
| T-Mobile AWS - 2100 MHz LTE | 2 | 2,334.27 | 130 | 10.92 | AWS - 2100 MHz | 1000 | 1.09% |
| T-Mobile PCS - 1950 MHz UMTS | 2 | 1,167.14 | 130 | 5.46 | PCS - 1950 MHz | 1000 | 0.55% |
| T-Mobile 700 MHz LTE | 1 | 687.26 | 130 | 1.61 | 700 MHz | 467 | 0.34% |
| | | | | | | Total: | 1.98% |

Summary

All calculations performed for this analysis yielded results that were **within** the allowable limits for general public exposure to RF Emissions.

The anticipated maximum composite contributions from the T-Mobile facility as well as the site composite emissions value with regards to compliance with FCC's allowable limits for general public exposure to RF Emissions are shown here:

| T-Mobile Sector | Power Density Value (%) |
|------------------------------|-------------------------|
| Sector A: | 1.98 % |
| Sector B: | 1.98 % |
| T-Mobile Per Sector Maximum: | 1.98 % |
| | |
| Site Total: | 13.52 % |
| | |
| Site Compliance Status: | COMPLIANT |

The anticipated composite MPE value for this site assuming all carriers present is **13.52%** of the allowable FCC established general public limit sampled at the ground level. This is based upon values listed in the Connecticut Siting Council database for existing carrier emissions.

FCC guidelines state that if a site is found to be out of compliance (over allowable thresholds), that carriers over a 5% contribution to the composite value will require measures to bring the site into compliance. For this facility, the composite values calculated were well within the allowable 100% threshold standard per the federal government.

Structural Analysis Report

150' Existing Guyed Lattice Tower


*Proposed T-Mobile
Antenna Upgrade*

T-Mobile Site Ref: CT11180C

*130 Vernon Road
Bolton, CT 06043*

Centek Project No. 17012.45

Date: April 20, 2017



Prepared for:
T-Mobile USA
35 Griffin Road
Bloomfield, CT 06002

Table of Contents

SECTION 1 – REPORT

- INTRODUCTION
- ANTENNA AND APPURTENANCE SUMMARY
- PRIMARY ASSUMPTIONS USED IN THE ANALYSIS
- ANALYSIS
- TOWER LOADING
- TOWER CAPACITY
- CONCLUSION AND RECOMMENDATIONS

SECTION 2 – CONDITIONS & SOFTWARE

- STANDARD ENGINEERING CONDITIONS
- GENERAL DESCRIPTION OF STRUCTURAL ANALYSIS PROGRAM

SECTION 3 – CALCULATIONS

- tnxTower INPUT/OUTPUT SUMMARY
- tnxTower FEED LINE PLAN
- tnxTower FEED LINE DISTRIBUTION
- tnxTower LEG COMPRESSION DIAGRAM
- tnxTower GLOBAL MAST SHEAR AND MOMENT DIAGRAMS
- tnxTower DEFLECTION DIAGRAMS
- tnxTower STRESS DISTRIBUTION
- tnxTower WIND PRESSURE AND ICE THICKNESS
- tnxTower DETAILED OUTPUT
- TOWER BASE FOUNDATION ANALYSIS
- GUY ANCHOR FOUNDATION ANALYSIS

SECTION 4 – REFERENCE MATERIALS

- RF DATA SHEET

I n t r o d u c t i o n

The purpose of this report is to summarize the results of the non-linear, P- Δ structural analysis of the antenna upgrade proposed by T-Mobile on the existing guyed lattice tower located in Bolton, CT.

The host tower is a 150-ft, three legged, guyed lattice tower. The original tower design documents were unavailable for use in this report. The tower geometry, structure member sizes and foundation information were obtained from a previous structural report prepared by AECOM job no. TWM-007 dated September 20, 2016.

Antenna and appurtenance information were obtained from the aforementioned structural report and a T-Mobile RF data sheet.

The tower consists of eight (8) straight and one (1) tapered base vertical sections consisting of solid round legs steel grade of ASTM A572-50. Diagonal and horizontal lateral support bracing consists of solid round steel grade of ASTM A572-50. The vertical tower sections are connected by bolted sleeves with the diagonal and horizontal bracing to legs consisting of welded connections. The width of the tower face is 3.75-ft throughout its length.

A n t e n n a a n d A p p u r t e n a n c e S u m m a r y

The existing and proposed loads considered in the analysis consist of the following:

- **SPRINT (EXISTING/RESERVED):**
Antennas: Three (3) RFS APXVSP18 panel antennas, three (3) RFS APXVTM14 panel antennas, three (3) 800MHz RRHs, three (3) 1900MHz RRHs and three (3) TD-RRH8x20-25 remote radio heads mounted on three (3) 12-ft T-frames with a RAD center elevation of 148-ft above grade.
Cables: Three (3) 1-1/4" \varnothing fiber cables running on a leg/face of the existing tower as specified in Section 3 of this report.
- **T-MOBILE (EXISTING TO REMAIN):**
Antennas: Two (2) Ericsson AIR21 panel antennas, two (2) Andrew SBNH-1D65C and two (2) Ericsson RRUS-11 remote radio units mounted on two (2) 12-ft T-frames with a RAD center elevation of 130-ft above grade.
Cables: Two (2) 1-1/4" \varnothing fiber cables running on a leg/face of the existing tower as specified in Section 3 of this report
- **T-MOBILE (PROPOSED):**
Antennas: Two (2) Twin AWS TMAs mounted on two (2) 12-ft T-frames with a RAD center elevation of 130-ft above grade.
Cables: Four (4) 1-5/8" \varnothing coax cables running on a leg/face of the existing tower as specified in Section 3 of this report

Primary Assumptions Used in the Analysis

- The tower structure's theoretical capacity not including any assessment of the condition of the tower.
- The tower carries the horizontal and vertical loads due to the weight of antennas, ice load and wind.
- Tower is properly installed and maintained.
- Tower is in plumb condition.
- Tower loading for antennas and mounts as listed in this report.
- All bolts are appropriately tightened providing the necessary connection continuity.
- All welds are fabricated with ER-70S-6 electrodes.
- All members are assumed to be as specified in the original tower design documents.
- All members are "hot dipped" galvanized in accordance with ASTM A123 and ASTM A153 Standards.
- All member protective coatings are in good condition.
- All tower members were properly designed, detailed, fabricated, installed and have been properly maintained since erection.
- Any deviation from the analyzed antenna loading will require a new analysis for verification of structural adequacy.
- All coax cables routed as specified in Section 3 of this report.

A n a l y s i s

The existing tower was analyzed using a comprehensive computer program entitled tnxTower. The program analyzes the tower, considering the worst case loading condition. The tower is considered as loaded by concentric forces along the tower, and the model assumes that the tower members are subjected to bending, axial, and shear forces.

The existing tower was analyzed for the controlling basic wind speed (3-second gust) with no ice and the applicable wind and ice combination to determine stresses in members as per guidelines of TIA-222-G-2005 entitled "Structural Standard for Antenna Support Structures and Antennas", the American Institute of Steel Construction (AISC) and the Manual of Steel Construction; Load and Resistance Factor Design (LRFD).

The controlling wind speed is determined by evaluating the local available wind speed data as provided in Appendix N of the CSBC¹ and the wind speed data available in the TIA-222-G-2005 Standard.

T o w e r L o a d i n g

Tower loading was determined by the basic wind speed as applied to projected surface areas with modification factors per TIA-222-G-2005, gravity loads of the tower structure and its components, and the application of 1.00" radial ice on the tower structure and its components.

| | | |
|-------------------|--|---|
| Basic Wind Speed: | Tolland County; v = 95-105 mph (3-second gust) | [Annex B of TIA-222-G-2005] |
| | Bolton; v = 97 mph (3 second gust) | [Appendix N of the 2016 CT Building Code] |
| Load Cases: | <u>Load Case 1</u> ; 97 mph wind speed w/ no ice plus gravity load – used in calculation of tower stresses and rotation. | [Appendix N of the 2016 CT Building Code] |
| | <u>Load Case 2</u> ; 50 mph wind speed w/ 1.00" radial ice plus gravity load – used in calculation of tower stresses. | [Annex B of TIA-222-G-2005] |

¹ The 2012 International Building Code as amended by the 2016 Connecticut State Building Code (CSBC).

Tower Capacity

- Calculated stresses were found to be within allowable limits. In Load Case 2, per tnxTower "Section Capacity Table", this tower was found to be at **57.1%** of its total capacity.

| Tower Section | Elevation | Stress Ratio (percentage of capacity) | Result |
|----------------------------|-----------------|--|-------------|
| Leg (T3) | 100'-0"-120'-0" | 27.6% | PASS |
| Diagonal (T9) | 0'-0"-5'-0" | 38.1% | PASS |
| Bottom Girt (T8) | 5'-0"-20'-0" | 40.1% | PASS |
| Guy C @ 210-ft radius (T2) | 138-ft | 57.1% | PASS |

Foundations and Anchorage

The existing tower base foundation consists of a 2.5-ft diameter x 2.25-ft long reinforced concrete pier on a 7-ft square x 1.25-ft thick reinforced concrete pad bearing directly on the existing sub grade. Additionally, guy wire loading is transferred to three (3) concrete support blocks anchored to rock with (2) 1-3/8" diameter rock anchors per block. The sub-grade conditions used as the basis for the foundation analysis were derived from the aforementioned structural report.

- The worst case tower base and guy anchor reactions developed from the governing Load Case 1 were used in the verification of the anchorage foundations:

| Tower Guy Reactions | |
|------------------------------------|-------------------|
| Vector | Inner |
| Horizontal (In Plane of GW) | 29 kips |
| Horizontal (Out of Plane of GW) | 1 kips |
| Vertical | 18 kips |
| Resultant Force at end of Guy Wire | 34 kips |
| Tower Base Reactions | |
| Vector | Proposed Reaction |
| Horizontal Shear | 1.0 kips |
| Axial Compression | 114.0 kips |

CEN TEK Engineering, Inc.
 Structural Analysis - 150-ft Guyed Lattice Tower
 T-Mobile Antenna Upgrade ~ CT11180C
 Bolton, CT
 April 20, 2017

| Foundation | Design Limit | TIA-222-G Section 9.4 FS ⁽¹⁾ | Proposed Loading (FS) ⁽¹⁾ | Result |
|---|----------------|---|--------------------------------------|-------------|
| Reinf. Conc. Anchor Block w/ Rock Anchors | Steel Strength | 1.0 | 3.9 | PASS |
| | Bond Strength | 1.0 | 10.9 | PASS |
| | | Ultimate Bearing | Proposed | |
| Base Foundation | Bearing | 8.0 ksf | 2.55 ksf | PASS |

| Note 1: FS denotes 'Factor of Safety'.

Conclusion

This analysis shows that the subject tower **is adequate** to support the proposed modified antenna configuration with the below recommendations.


The analysis is based, in part, on the information provided to this office by T-Mobile. If the existing conditions are different than the information in this report, Centek Engineering, Inc. must be contacted for resolution of any potential issues.

Please feel free to call with any questions or comments.

Respectfully Submitted by:



Timothy J. Lynn, PE
 Structural Engineer



*Standard Conditions for Furnishing of
Professional Engineering Services on
Existing Structures*

All engineering services are performed on the basis that the information used is current and correct. This information may consist of, but is not necessarily limited to:

- Information supplied by the client regarding the structure itself, its foundations, the soil conditions, the antenna and feed line loading on the structure and its components, or other relevant information.
- Information from the field and/or drawings in the possession of Centek Engineering, Inc. or generated by field inspections or measurements of the structure.
- It is the responsibility of the client to ensure that the information provided to Centek Engineering, Inc. and used in the performance of our engineering services is correct and complete. In the absence of information to the contrary, we assume that all structures were constructed in accordance with the drawings and specifications and are in an un-corroded condition and have not deteriorated. It is therefore assumed that its capacity has not significantly changed from the “as new” condition.
- All services will be performed to the codes specified by the client, and we do not imply to meet any other codes or requirements unless explicitly agreed in writing. If wind and ice loads or other relevant parameters are to be different from the minimum values recommended by the codes, the client shall specify the exact requirement. In the absence of information to the contrary, all work will be performed in accordance with the latest revision of ANSI/ASCE10 & ANSI/EIA-222
- All services performed, results obtained, and recommendations made are in accordance with generally accepted engineering principles and practices. Centek Engineering, Inc. is not responsible for the conclusions, opinions and recommendations made by others based on the information we supply.


GENERAL DESCRIPTION OF STRUCTURAL ANALYSIS PROGRAM

tnxTower, is an integrated structural analysis and design software package for Designed specifically for the telecommunications industry, tnxTower, formerly ERITower, automates much of the tower analysis and design required by the TIA/EIA 222 Standard.

tnxTower Features:

- tnxTower can analyze and design 3- and 4-sided guyed towers, 3- and 4-sided self-supporting towers and either round or tapered ground mounted poles with or without guys.
- The program analyzes towers using the TIA-222-G (2005) standard or any of the previous TIA/EIA standards back to RS-222 (1959). Steel design is checked using the AISC ASD 9th Edition or the AISC LRFD specifications.
- Linear and non-linear (P-delta) analyses can be used in determining displacements and forces in the structure. Wind pressures and forces are automatically calculated.
- Extensive graphics plots include material take-off, shear-moment, leg compression, displacement, twist, feed line, guy anchor and stress plots.
- tnxTower contains unique features such as True Cable behavior, hog rod take-up, foundation stiffness and much more.

| | | | | | | | | | | | |
|-------------------|----------|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|
| Section | T9 | T10 | T11 | T12 | T13 | T14 | T15 | T16 | T17 | T18 | T19 |
| Legs | SR 2 1/2 | | | | | | | | | | |
| Leg Grade | A572-50 | | | | | | | | | | |
| Diagonals | SR 3/4 | | | | | | | | | | |
| Diagonal Grade | A572-50 | | | | | | | | | | |
| Top Girts | SR 3/4 | | | | | | | | | | |
| Bottom Girts | SR 3/4 | | | | | | | | | | |
| Horizontal | N.A. | | | | | | | | | | |
| Top Guy Pull-Offs | 4x1/2 | | | | | | | | | | |
| Horizontal | N.A. | | | | | | | | | | |
| Face Width (ft) | SR 1 1/4 | | | | | | | | | | |
| # Panels @ (ft) | 3.75 | | | | | | | | | | |
| Weight (K) | 4 @ 2.25 | | | | | | | | | | |
| | 0.6 | | | | | | | | | | |



DESIGNED APPURTENANCE LOADING

| TYPE | ELEVATION | TYPE | ELEVATION |
|---------------------------|-----------|-------------------------------------|-----------|
| APXVSP18-C-A20 (Sprint) | 148 | TD-RRH8x20-25 (Sprint) | 148 |
| APXVSP18-C-A20 (Sprint) | 148 | PIROD 12' T-Frame (Sprint) | 148 |
| APXVSP18-C-A20 (Sprint) | 148 | PIROD 12' T-Frame (Sprint) | 148 |
| APXVTM14 (Sprint) | 148 | PIROD 12' T-Frame (Sprint) | 148 |
| APXVTM14 (Sprint) | 148 | AIR21 B4A/B2P (T-Mobile) | 130 |
| APXVTM14 (Sprint) | 148 | AIR21 B4A/B2P (T-Mobile) | 130 |
| FD-RRH 2x50 800 (Sprint) | 148 | SBNH-1D65C (T-Mobile) | 130 |
| FD-RRH 2x50 800 (Sprint) | 148 | SBNH-1D65C (T-Mobile) | 130 |
| FD-RRH 2x50 800 (Sprint) | 148 | RRUS-11 (T-Mobile) | 130 |
| FD-RRH 4x45 1900 (Sprint) | 148 | RRUS-11 (T-Mobile) | 130 |
| FD-RRH 4x45 1900 (Sprint) | 148 | TMA 12"x6"x4" (T-Mobile - Proposed) | 130 |
| FD-RRH 4x45 1900 (Sprint) | 148 | TMA 12"x6"x4" (T-Mobile - Proposed) | 130 |
| FD-RRH 4x45 1900 (Sprint) | 148 | TMA 12"x6"x4" (T-Mobile - Proposed) | 130 |
| TD-RRH8x20-25 (Sprint) | 148 | PIROD 12' T-Frame (T-Mobile) | 130 |
| TD-RRH8x20-25 (Sprint) | 148 | PIROD 12' T-Frame (T-Mobile) | 130 |

SYMBOL LIST


| MARK | SIZE | MARK | SIZE |
|------|----------|------|------|
| A | 2 @ 2.25 | | |

MATERIAL STRENGTH

| GRADE | Fy | Fu | GRADE | Fy | Fu |
|---------|--------|--------|-------|----|----|
| A572-50 | 50 ksi | 65 ksi | | | |

TOWER DESIGN NOTES

1. Tower designed for Exposure C to the TIA-222-G Standard.
2. Tower designed for a 97 mph basic wind in accordance with the TIA-222-G Standard.
3. Tower is also designed for a 50 mph basic wind with 1.00 in ice. Ice is considered to increase in thickness with height.
4. Deflections are based upon a 60 mph wind.
5. Tower Structure Class II.
6. Topographic Category 1 with Crest Height of 0.00 ft
7. TOWER RATING: 57.1%




ALL REACTIONS ARE FACTORED

| | | | |
|---|---|----------------|------------|
| Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587 | Job: 17012.45 - CT11180C | | |
| | Project: 150' Guyed Tower - 130 Vernon Road Bolton, CT | | |
| | Client: T-Mobile | Drawn by: T.JL | App'd: |
| | Code: TIA-222-G | Date: 04/20/17 | Scale: NTS |
| | Path: | Dwg No. E-1 | |

Feed Line Plan

— Round
 — Flat
 — App In Face
 — App Out Face




| | | | |
|---|----------------|---|--|
| Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587 | | Job: 17012.45 - CT11180C | |
| | | Project: 150' Guyed Tower - 130 Vernon Road Bolton, CT | |
| Client: T-Mobile | Drawn by: T.JL | App'd: | |
| Code: TIA-222-G | Date: 04/20/17 | Scale: NTS | |
| Path: | | Dwg No. E-7 | |

J:\Jobs\1701200\W45_C11180205_Structural\Backup Documentation\Civil\ER\150' Guyed Tower - Bolton, CT.dwg

Feed Line Distribution Chart

5' - 150'

— Round
 — Flat
 — App In Face
 — App Out Face
 — Truss Leg




| | | | | | |
|---|----------------|--------|---|----------------|-------------|
| Centek Engineering Inc. | | | Job: 17012.45 - CT11180C | | |
| 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587 | | | Project: 150' Guyed Tower - 130 Vernon Road Bolton, CT | | |
| Client: T-Mobile | Drawn by: T.JL | App'd: | Code: TIA-222-G | Date: 04/20/17 | Scale: NTS |
| Path: | | | | | Dwg No. E-7 |

J:\Jobs\170120\W45_C11180205_Structural\Backup Documentation\Civil\150' Guyed Tower - Bolton, CT.dwg

TIA-222-G - 97 mph/50 mph 1.0000 in Ice Exposure C

Leg Capacity ———



Leg Compression (K)



| | | |
|---|---|------------|
| Centek Engineering Inc. | | |
| 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587 | | |
| Job: 17012.45 - CT11180C | Project: 150' Guyed Tower - 130 Vernon Road Bolton, CT | |
| Client: T-Mobile | Drawn by: T.JL | App'd: |
| Code: TIA-222-G | Date: 04/20/17 | Scale: NTS |
| Path: | Dwg No. E-3 | |




Vx Vz

Mx Mz



| | | | |
|---|----------------|---|--|
| Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587 | | Job: 17012.45 - CT11180C | |
| | | Project: 150' Guyed Tower - 130 Vernon Road Bolton, CT | |
| Client: T-Mobile | Drawn by: T.JL | App'd: | |
| Code: TIA-222-G | Date: 04/20/17 | Scale: NTS | |
| Path: | Dwg No. E-4 | | |

J:\Jobs\170120\W45_C\11180205_Structural\Backup_Documentation\Civil\ER\150' Guyed Tower - Bolton, CT.dwg




| | | |
|---|---|------------|
| Centek Engineering Inc. | | |
| 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587 | | |
| Job: 17012.45 - CT11180C | Project: 150' Guyed Tower - 130 Vernon Road Bolton, CT | |
| Client: T-Mobile | Drawn by: T.JL | App'd: |
| Code: TIA-222-G | Date: 04/20/17 | Scale: NTS |
| Path: | Dwg No. E-5 | |

Stress Distribution Chart




0' - 150'

■ > 100%
 ■ 90%-100%
 ■ 75%-90%
 ■ 50%-75%
 ■ < 50% Overstress



| | | | | | |
|---|--|------------------|---|--|--|
| Centek Engineering Inc. | | | Job: 17012.45 - CT11180C | | |
| 63-2 North Branford Rd. Branford, CT 06405 | | | Project: 150' Guyed Tower - 130 Vernon Road Bolton, CT | | |
| Phone: (203) 488-0580 | | Client: T-Mobile | Drawn by: T.JL | | App'd: |
| FAX: (203) 488-8587 | | Code: TIA-222-G | Date: 04/20/17 | | Scale: NTS |
| Path: | | | Dwg No. E-8 | | <small>J:\Jobs\1701200\W45 - CT11180205 - Structural\Backup Documents\Structural\150' Guyed Tower - Bolton, CT.dwg</small> |

Wind Pressures and Ice Thickness
TIA-222-G - 97 mph/50 mph 1.0000 in Ice Exposure C



| | | | | | |
|---|----------------|--------|---|----------------|------------|
| Centek Engineering Inc. | | | Job: 17012.45 - CT11180C | | |
| 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587 | | | Project: 150' Guyed Tower - 130 Vernon Road Bolton, CT | | |
| Client: T-Mobile | Drawn by: T.JL | App'd: | Code: TIA-222-G | Date: 04/20/17 | Scale: NTS |
| Path: J:\job\170120\W45_C11180205_Structural\Backup\Documentation\Civil\150' Guyed Tower - Bolton, CT.dwg | | | Dwg No. E-9 | | |

| | | |
|--|---|----------------------------------|
| tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587 | Job 17012.45 - CT11180C | Page 1 of 44 |
| | Project 150' Guyed Tower - 130 Vernon Road Bolton, CT | Date 13:20:26 04/20/17 |
| | Client T-Mobile | Designed by TJL |

Tower Input Data

The main tower is a 3x guyed tower with an overall height of 150.00 ft above the ground line.

The base of the tower is set at an elevation of 0.00 ft above the ground line.

The face width of the tower is 3.75 ft at the top and tapered at the base.

This tower is designed using the TIA-222-G standard.

The following design criteria apply:

Basic wind speed of 97 mph.

Structure Class II.

Exposure Category C.

Topographic Category 1.

Crest Height 0.00 ft.

Nominal ice thickness of 1.0000 in.

Ice thickness is considered to increase with height.

Ice density of 56 pcf.

A wind speed of 50 mph is used in combination with ice.

Temperature drop of 50 °F.

Deflections calculated using a wind speed of 60 mph.

Pressures are calculated at each section.

Safety factor used in guy design is 1.


Stress ratio used in tower member design is 1.

Local bending stresses due to climbing loads, feed line supports, and appurtenance mounts are not considered.

Options


| | | |
|-------------------------------------|--------------------------------------|---|
| Consider Moments - Legs | Distribute Leg Loads As Uniform | Use ASCE 10 X-Brace Ly Rules |
| Consider Moments - Horizontals | Assume Legs Pinned | Calculate Redundant Bracing Forces |
| Consider Moments - Diagonals | √ Assume Rigid Index Plate | Ignore Redundant Members in FEA |
| Use Moment Magnification | √ Use Clear Spans For Wind Area | √ SR Leg Bolts Resist Compression |
| √ Use Code Stress Ratios | √ Use Clear Spans For KL/r | √ All Leg Panels Have Same Allowable |
| √ Use Code Safety Factors - Guys | √ Retension Guys To Initial Tension | Offset Girt At Foundation |
| Escalate Ice | Bypass Mast Stability Checks | √ Consider Feed Line Torque |
| Always Use Max Kz | √ Use Azimuth Dish Coefficients | Include Angle Block Shear Check |
| Use Special Wind Profile | √ Project Wind Area of Appurt. | Use TIA-222-G Bracing Resist. Exemption |
| √ Include Bolts In Member Capacity | √ Autocalc Torque Arm Areas | Use TIA-222-G Tension Splice Exemption |
| √ Leg Bolts Are At Top Of Section | Add IBC .6D+W Combination | Poles |
| Secondary Horizontal Braces Leg | √ Sort Capacity Reports By Component | Include Shear-Torsion Interaction |
| Use Diamond Inner Bracing (4 Sided) | Triangulate Diamond Inner Bracing | Always Use Sub-Critical Flow |
| √ SR Members Have Cut Ends | Treat Feed Line Bundles As Cylinder | Use Top Mounted Sockets |
| SR Members Are Concentric | | |

| | | | |
|----------------|---|--------------------|-------------------|
| Job | 17012.45 - CT11180C | Page | 2 of 44 |
| Project | 150' Guyed Tower - 130 Vernon Road Bolton, CT | Date | 13:20:26 04/20/17 |
| Client | T-Mobile | Designed by | TJL |



Corner & Starmount Guyed Tower

| | | |
|--|---|----------------------------------|
| tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587 | Job 17012.45 - CT11180C | Page 3 of 44 |
| | Project 150' Guyed Tower - 130 Vernon Road Bolton, CT | Date 13:20:26 04/20/17 |
| | Client T-Mobile | Designed by TJJ |



Face Guyed

Tower Section Geometry

| <i>Tower Section</i> | <i>Tower Elevation</i> | <i>Assembly Database</i> | <i>Description</i> | <i>Section Width</i> | <i>Number of Sections</i> | <i>Section Length</i> |
|----------------------|------------------------|--------------------------|--------------------|----------------------|---------------------------|-----------------------|
| | <i>ft</i> | | | <i>ft</i> | | <i>ft</i> |
| T1 | 150.00-140.00 | | | 3.75 | 1 | 10.00 |
| T2 | 140.00-120.00 | | | 3.75 | 1 | 20.00 |
| T3 | 120.00-100.00 | | | 3.75 | 1 | 20.00 |
| T4 | 100.00-80.00 | | | 3.75 | 1 | 20.00 |
| T5 | 80.00-60.00 | | | 3.75 | 1 | 20.00 |
| T6 | 60.00-40.00 | | | 3.75 | 1 | 20.00 |
| T7 | 40.00-20.00 | | | 3.75 | 1 | 20.00 |
| T8 | 20.00-5.00 | | | 3.75 | 1 | 15.00 |
| T9 | 5.00-0.00 | | | 3.75 | 1 | 5.00 |

Tower Section Geometry (cont'd)

| | | |
|--|---|----------------------------------|
| tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587 | Job 17012.45 - CT11180C | Page 4 of 44 |
| | Project 150' Guyed Tower - 130 Vernon Road Bolton, CT | Date 13:20:26 04/20/17 |
| | Client T-Mobile | Designed by TJL |

| Tower Section | Tower Elevation ft | Diagonal Spacing ft | Bracing Type | Has K Brace End Panels | Has Horizontals | Top Girt Offset in | Bottom Girt Offset in |
|---------------|-----------------------|------------------------|--------------|------------------------|-----------------|-----------------------|--------------------------|
| T1 | 150.00-140.00 | 2.25 | X Brace | No | Steps | 6.0000 | 6.0000 |
| T2 | 140.00-120.00 | 2.38 | X Brace | No | Steps | 6.0000 | 6.0000 |
| T3 | 120.00-100.00 | 2.38 | X Brace | No | Steps | 6.0000 | 6.0000 |
| T4 | 100.00-80.00 | 2.38 | X Brace | No | Steps | 6.0000 | 6.0000 |
| T5 | 80.00-60.00 | 2.38 | X Brace | No | Steps | 6.0000 | 6.0000 |
| T6 | 60.00-40.00 | 2.38 | X Brace | No | Steps | 6.0000 | 6.0000 |
| T7 | 40.00-20.00 | 2.38 | X Brace | No | Steps | 6.0000 | 6.0000 |
| T8 | 20.00-5.00 | 2.42 | X Brace | No | Steps | 6.0000 | 0.0000 |
| T9 | 5.00-0.00 | 2.25 | X Brace | No | Yes | 0.0000 | 6.0000 |

Tower Section Geometry (cont'd)

| Tower Elevation ft | Leg Type | Leg Size | Leg Grade | Diagonal Type | Diagonal Size | Diagonal Grade |
|-----------------------|-------------|----------|---------------------|---------------|---------------|---------------------|
| T1 150.00-140.00 | Solid Round | 2 | A572-50 (50 ksi) | Solid Round | 3/4 | A572-50 (50 ksi) |
| T2 140.00-120.00 | Solid Round | 2 | A572-50 (50 ksi) | Solid Round | 3/4 | A572-50 (50 ksi) |
| T3 120.00-100.00 | Solid Round | 2 | A572-50 (50 ksi) | Solid Round | 3/4 | A572-50 (50 ksi) |
| T4 100.00-80.00 | Solid Round | 2 1/4 | A572-50 (50 ksi) | Solid Round | 3/4 | A572-50 (50 ksi) |
| T5 80.00-60.00 | Solid Round | 2 1/4 | A572-50 (50 ksi) | Solid Round | 3/4 | A572-50 (50 ksi) |
| T6 60.00-40.00 | Solid Round | 2 1/4 | A572-50 (50 ksi) | Solid Round | 3/4 | A572-50 (50 ksi) |
| T7 40.00-20.00 | Solid Round | 2 1/4 | A572-50 (50 ksi) | Solid Round | 3/4 | A572-50 (50 ksi) |
| T8 20.00-5.00 | Solid Round | 2 1/2 | A572-50 (50 ksi) | Solid Round | 3/4 | A572-50 (50 ksi) |
| T9 5.00-0.00 | Solid Round | 2 1/2 | A572-50 (50 ksi) | Solid Round | 3/4 | A572-50 (50 ksi) |

Tower Section Geometry (cont'd)

| Tower Elevation ft | Top Girt Type | Top Girt Size | Top Girt Grade | Bottom Girt Type | Bottom Girt Size | Bottom Girt Grade |
|-----------------------|---------------|---------------|---------------------|------------------|------------------|---------------------|
| T1 150.00-140.00 | Solid Round | 3/4 | A572-50 (50 ksi) | Solid Round | 3/4 | A572-50 (50 ksi) |
| T2 140.00-120.00 | Solid Round | 3/4 | A572-50 (50 ksi) | Solid Round | 3/4 | A572-50 (50 ksi) |
| T3 120.00-100.00 | Solid Round | 3/4 | A572-50 (50 ksi) | Solid Round | 3/4 | A572-50 (50 ksi) |
| T4 100.00-80.00 | Solid Round | 3/4 | A572-50 (50 ksi) | Solid Round | 3/4 | A572-50 (50 ksi) |
| T5 80.00-60.00 | Solid Round | 3/4 | A572-50 (50 ksi) | Solid Round | 3/4 | A572-50 (50 ksi) |
| T6 60.00-40.00 | Solid Round | 3/4 | A572-50 (50 ksi) | Solid Round | 3/4 | A572-50 (50 ksi) |
| T7 40.00-20.00 | Solid Round | 3/4 | A572-50 (50 ksi) | Solid Round | 3/4 | A572-50 (50 ksi) |

| | | |
|--|---|----------------------------------|
| tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587 | Job 17012.45 - CT11180C | Page 5 of 44 |
| | Project 150' Guyed Tower - 130 Vernon Road Bolton, CT | Date 13:20:26 04/20/17 |
| | Client T-Mobile | Designed by TJJ |

| Tower Elevation ft | Top Girt Type | Top Girt Size | Top Girt Grade | Bottom Girt Type | Bottom Girt Size | Bottom Girt Grade |
|-----------------------|---------------|---------------|---------------------|------------------|------------------|---------------------|
| T8 20.00-5.00 | Solid Round | 3/4 | (50 ksi) A572-50 | Solid Round | 3/4 | (50 ksi) A572-50 |
| T9 5.00-0.00 | Solid Round | | (50 ksi) A572-50 | Solid Round | 3/4 | (50 ksi) A572-50 |

Tower Section Geometry (cont'd)

| Tower Elevation ft | No. of Mid Girts | Mid Girt Type | Mid Girt Size | Mid Girt Grade | Horizontal Type | Horizontal Size | Horizontal Grade |
|-----------------------|------------------|---------------|---------------|---------------------|-----------------|-----------------|------------------|
| T9 5.00-0.00 | None | Solid Round | | A572-50 (50 ksi) | Flat Bar | 4x1/2 | A36 (36 ksi) |

Tower Section Geometry (cont'd)

| Tower Elevation ft | Gusset Area (per face) ft ² | Gusset Thickness in | Gusset Grade | Adjust. Factor <i>A_f</i> | Adjust. Factor <i>A_r</i> | Weight Mult. | Double Angle Stitch Bolt Spacing Diagonals in | Double Angle Stitch Bolt Spacing Horizontals in | Double Angle Stitch Bolt Spacing Redundants in |
|-----------------------|--|------------------------|-----------------|--|--|--------------|---|---|--|
| T1 150.00-140.00 | 0.00 | 0.0000 | A36 (36 ksi) | 1 | 1 | 1 | 36.0000 | 36.0000 | 36.0000 |
| T2 140.00-120.00 | 0.00 | 0.0000 | A36 (36 ksi) | 1 | 1 | 1 | 36.0000 | 36.0000 | 36.0000 |
| T3 120.00-100.00 | 0.00 | 0.0000 | A36 (36 ksi) | 1 | 1 | 1 | 36.0000 | 36.0000 | 36.0000 |
| T4 100.00-80.00 | 0.00 | 0.0000 | A36 (36 ksi) | 1 | 1 | 1 | 36.0000 | 36.0000 | 36.0000 |
| T5 80.00-60.00 | 0.00 | 0.0000 | A36 (36 ksi) | 1 | 1 | 1 | 36.0000 | 36.0000 | 36.0000 |
| T6 60.00-40.00 | 0.00 | 0.0000 | A36 (36 ksi) | 1 | 1 | 1 | 36.0000 | 36.0000 | 36.0000 |
| T7 40.00-20.00 | 0.00 | 0.0000 | A36 (36 ksi) | 1 | 1 | 1 | 36.0000 | 36.0000 | 36.0000 |
| T8 20.00-5.00 | 0.00 | 0.0000 | A36 (36 ksi) | 1 | 1 | 1 | 36.0000 | 36.0000 | 36.0000 |
| T9 5.00-0.00 | 0.00 | 0.0000 | A36 (36 ksi) | 1 | 1 | 1 | 36.0000 | 36.0000 | 36.0000 |

Tower Section Geometry (cont'd)

| | | | | |
|--|----------------|---|--------------------|-------------------|
| tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587 | Job | 17012.45 - CT11180C | Page | 6 of 44 |
| | Project | 150' Guyed Tower - 130 Vernon Road Bolton, CT | Date | 13:20:26 04/20/17 |
| | Client | T-Mobile | Designed by | TJL |

| Tower Elevation | Calc K Single Angles | Calc K Solid Rounds | Legs | X Brace Diags X Y | K Brace Diags X Y | Single Diags X Y | Girts X Y | Horiz. X Y | Sec. Horiz. X Y | Inner Brace X Y |
|---------------------|----------------------|---------------------|------|-------------------------|-------------------------|------------------------|-----------------|------------------|-----------------------|-----------------------|
| T1 150.00-140.00 | Yes | Yes | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 |
| T2 140.00-120.00 | Yes | Yes | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 |
| T3 120.00-100.00 | Yes | Yes | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 |
| T4 100.00-80.00 | Yes | Yes | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 |
| T5 80.00-60.00 | Yes | Yes | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 |
| T6 60.00-40.00 | Yes | Yes | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 |
| T7 40.00-20.00 | Yes | Yes | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 |
| T8 20.00-5.00 | Yes | Yes | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 |
| T9 5.00-0.00 | Yes | Yes | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 |

¹Note: K factors are applied to member segment lengths. K-braces without inner supporting members will have the K factor in the out-of-plane direction applied to the overall length.

Tower Section Geometry (cont'd)

| Tower Elevation ft | Leg | | Diagonal | | Top Girt | | Bottom Girt | | Mid Girt | | Long Horizontal | | Short Horizontal | |
|-----------------------|---------------------------|------|---------------------------|------|---------------------------|------|---------------------------|------|---------------------------|------|---------------------------|------|---------------------------|------|
| | Net Width Deduct in | U | Net Width Deduct in | U | Net Width Deduct in | U | Net Width Deduct in | U | Net Width Deduct in | U | Net Width Deduct in | U | Net Width Deduct in | U |
| T1 150.00-140.00 | 0.0000 | 0.75 | 0.0000 | 0.75 | 0.0000 | 0.75 | 0.0000 | 0.75 | 0.0000 | 0.75 | 0.0000 | 0.75 | 0.0000 | 0.75 |
| T2 140.00-120.00 | 0.0000 | 0.75 | 0.0000 | 0.75 | 0.0000 | 0.75 | 0.0000 | 0.75 | 0.0000 | 0.75 | 0.0000 | 0.75 | 0.0000 | 0.75 |
| T3 120.00-100.00 | 0.0000 | 0.75 | 0.0000 | 0.75 | 0.0000 | 0.75 | 0.0000 | 0.75 | 0.0000 | 0.75 | 0.0000 | 0.75 | 0.0000 | 0.75 |
| T4 100.00-80.00 | 0.0000 | 0.75 | 0.0000 | 0.75 | 0.0000 | 0.75 | 0.0000 | 0.75 | 0.0000 | 0.75 | 0.0000 | 0.75 | 0.0000 | 0.75 |
| T5 80.00-60.00 | 0.0000 | 0.75 | 0.0000 | 0.75 | 0.0000 | 0.75 | 0.0000 | 0.75 | 0.0000 | 0.75 | 0.0000 | 0.75 | 0.0000 | 0.75 |
| T6 60.00-40.00 | 0.0000 | 0.75 | 0.0000 | 0.75 | 0.0000 | 0.75 | 0.0000 | 0.75 | 0.0000 | 0.75 | 0.0000 | 0.75 | 0.0000 | 0.75 |
| T7 40.00-20.00 | 0.0000 | 0.75 | 0.0000 | 0.75 | 0.0000 | 0.75 | 0.0000 | 0.75 | 0.0000 | 0.75 | 0.0000 | 0.75 | 0.0000 | 0.75 |
| T8 20.00-5.00 | 0.0000 | 0.75 | 0.0000 | 0.75 | 0.0000 | 0.75 | 0.0000 | 0.75 | 0.0000 | 0.75 | 0.0000 | 0.75 | 0.0000 | 0.75 |
| T9 5.00-0.00 | 0.0000 | 0.75 | 0.0000 | 0.75 | 0.0000 | 0.75 | 0.0000 | 0.75 | 0.0000 | 0.75 | 0.0000 | 0.75 | 0.0000 | 0.75 |

Tower Section Geometry (cont'd)

| | | |
|--|---|----------------------------------|
| tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587 | Job 17012.45 - CT11180C | Page 7 of 44 |
| | Project 150' Guyed Tower - 130 Vernon Road Bolton, CT | Date 13:20:26 04/20/17 |
| | Client T-Mobile | Designed by TJL |

| Tower Elevation ft | Leg Connection Type | Leg | | Diagonal | | Top Girt | | Bottom Girt | | Mid Girt | | Long Horizontal | | Short Horizontal | |
|-----------------------|---------------------|-----------------|-----|-----------------|-----|-----------------|-----|-----------------|-----|-----------------|-----|-----------------|-----|------------------|-----|
| | | Bolt Size in | No. | Bolt Size in | No. | Bolt Size in | No. | Bolt Size in | No. | Bolt Size in | No. | Bolt Size in | No. | Bolt Size in | No. |
| T1 150.00-140.00 | Sleeve SS | 0.0000 | 0 | 0.5000 | 0 | 0.5000 | 0 | 0.5000 | 0 | 0.6250 | 0 | 0.5000 | 0 | 0.6250 | 0 |
| | | A325N | | A325N | | A325N | | A325N | | A325X | | A325N | | A325X | |
| T2 140.00-120.00 | Sleeve SS | 0.6250 | 5 | 0.5000 | 0 | 0.5000 | 0 | 0.5000 | 0 | 0.6250 | 0 | 0.5000 | 0 | 0.6250 | 0 |
| | | A325N | | A325N | | A325N | | A325N | | A325X | | A325N | | A325X | |
| T3 120.00-100.00 | Sleeve SS | 0.6250 | 5 | 0.5000 | 0 | 0.5000 | 0 | 0.5000 | 0 | 0.6250 | 0 | 0.5000 | 0 | 0.6250 | 0 |
| | | A325N | | A325N | | A325N | | A325N | | A325X | | A325N | | A325X | |
| T4 100.00-80.00 | Sleeve SS | 0.7500 | 5 | 0.5000 | 0 | 0.5000 | 0 | 0.5000 | 0 | 0.6250 | 0 | 0.5000 | 0 | 0.6250 | 0 |
| | | A325N | | A325N | | A325N | | A325N | | A325X | | A325N | | A325X | |
| T5 80.00-60.00 | Sleeve SS | 0.7500 | 5 | 0.5000 | 0 | 0.5000 | 0 | 0.5000 | 0 | 0.6250 | 0 | 0.5000 | 0 | 0.6250 | 0 |
| | | A325N | | A325N | | A325N | | A325N | | A325X | | A325N | | A325X | |
| T6 60.00-40.00 | Sleeve SS | 0.7500 | 5 | 0.5000 | 0 | 0.5000 | 0 | 0.5000 | 0 | 0.6250 | 0 | 0.5000 | 0 | 0.6250 | 0 |
| | | A325N | | A325N | | A325N | | A325N | | A325X | | A325N | | A325X | |
| T7 40.00-20.00 | Sleeve SS | 0.7500 | 5 | 0.5000 | 0 | 0.5000 | 0 | 0.5000 | 0 | 0.6250 | 0 | 0.5000 | 0 | 0.6250 | 0 |
| | | A325N | | A325N | | A325N | | A325N | | A325X | | A325N | | A325X | |
| T8 20.00-5.00 | Sleeve SS | 0.7500 | 5 | 0.5000 | 0 | 0.5000 | 0 | 0.5000 | 0 | 0.6250 | 0 | 0.5000 | 0 | 0.6250 | 0 |
| | | A325N | | A325N | | A325N | | A325N | | A325X | | A325N | | A325X | |
| T9 5.00-0.00 | Sleeve SS | 0.0000 | 0 | 0.5000 | 0 | 0.5000 | 0 | 0.5000 | 0 | 0.6250 | 0 | 0.5000 | 0 | 0.6250 | 0 |
| | | A325N | | A325N | | A325N | | A325N | | A325X | | A325N | | A325X | |

Guy Data

| Guy Elevation ft | Guy Grade | Guy Size | Initial Tension K | % | Guy Modulus ksi | Guy Weight plf | L _u ft | Anchor Radius ft | Anchor Azimuth Adj. ° | Anchor Elevation ft | End Fitting Efficiency % |
|---------------------|-----------|----------|----------------------|-----|--------------------|-------------------|----------------------|---------------------|-----------------------------|------------------------|--------------------------------|
| 138 | EHS | A 9/16 | 3.50 | 10% | 21000 | 0.671 | 256.30 | 210.00 | 0.0000 | -14.00 | 100% |
| | | B 9/16 | 3.50 | 10% | 21000 | 0.671 | 268.63 | 210.00 | 0.0000 | -34.00 | 100% |
| | | C 9/16 | 3.50 | 10% | 21000 | 0.671 | 271.20 | 210.00 | 0.0000 | -38.00 | 100% |
| 70 | EHS | A 11/16" | 5.00 | 10% | 19000 | 1.000 | 223.97 | 210.00 | 0.0000 | -14.00 | 100% |
| | | B 11/16" | 5.00 | 10% | 19000 | 1.000 | 232.20 | 210.00 | 0.0000 | -34.00 | 100% |
| | | C 11/16" | 5.00 | 10% | 19000 | 1.000 | 234.02 | 210.00 | 0.0000 | -38.00 | 100% |

Guy Data(cont'd)

| Guy Elevation ft | Mount Type | Torque-Arm Spread ft | Torque-Arm Leg Angle ° | Torque-Arm Style | Torque-Arm Grade | Torque-Arm Type | Torque-Arm Size |
|---------------------|------------|-------------------------|---------------------------|------------------|------------------|-----------------|-----------------|
| 138 | Torque Arm | 12.00 | 30.0000 | Wing | A36 (36 ksi) | Double Angle | 2L3x3x5/16 |
| 70 | Corner | | | | | | |

Guy Data (cont'd)

| | | |
|--|---|----------------------------------|
| tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587 | Job 17012.45 - CT11180C | Page 8 of 44 |
| | Project 150' Guyed Tower - 130 Vernon Road Bolton, CT | Date 13:20:26 04/20/17 |
| | Client T-Mobile | Designed by TJJ |

| Guy Elevation ft | Diagonal Grade | Diagonal Type | Upper Diagonal Size | Lower Diagonal Size | Is Strap. | Pull-Off Grade | Pull-Off Type | Pull-Off Size |
|---------------------|---------------------|---------------|---------------------|---------------------|-----------|---------------------|---------------|---------------|
| 138.00 | A572-50 (50 ksi) | Solid Round | | | No | A572-50 (50 ksi) | Solid Round | 1 1/4 |
| 70.00 | A572-50 (50 ksi) | Solid Round | | | Yes | A572-50 (50 ksi) | Solid Round | 1 1/4 |

Guy Data (cont'd)

| Guy Elevation ft | Cable Weight A | Cable Weight B | Cable Weight C | Cable Weight D | Tower Intercept A | Tower Intercept B | Tower Intercept C | Tower Intercept D |
|---------------------|-------------------|-------------------|-------------------|-------------------|----------------------|----------------------|----------------------|----------------------|
| | K | K | K | K | ft | ft | ft | ft |
| 138 | 0.17 | 0.18 | 0.18 | | 6.21 | 6.81 | 6.94 | |
| | | | | | 4.3 sec/pulse | 4.5 sec/pulse | 4.5 sec/pulse | |
| 70 | 0.22 | 0.23 | 0.23 | | 4.98 | 5.34 | 5.42 | |
| | | | | | 3.9 sec/pulse | 4.0 sec/pulse | 4.0 sec/pulse | |

Guy Data (cont'd)

| Guy Elevation ft | Calc K Single Angles | Calc K Solid Rounds | Torque Arm | | Pull Off | | Diagonal | |
|---------------------|-------------------------|------------------------|----------------|----------------|----------------|----------------|----------------|----------------|
| | | | K _x | K _y | K _x | K _y | K _x | K _y |
| 138 | No | No | 1 | 1 | 1 | 1 | 1 | 1 |
| 70 | No | No | | | 1 | 1 | 1 | 1 |

Guy Data (cont'd)

| Guy Elevation ft | Torque-Arm | | | | Pull Off | | | | Diagonal | | | |
|---------------------|-----------------|--------|---------------------------|---|-----------------|--------|---------------------------|------|-----------------|--------|---------------------------|------|
| | Bolt Size in | Number | Net Width Deduct in | U | Bolt Size in | Number | Net Width Deduct in | U | Bolt Size in | Number | Net Width Deduct in | U |
| 138 | 0.0000 | 0 | 0.0000 | 1 | 0.6250 | 0 | 0.0000 | 0.75 | 0.6250 | 0 | 0.0000 | 0.75 |
| | A325N | | | | A325N | | | | A325N | | | |
| 70 | 0.0000 | 0 | 0.0000 | 1 | 0.6250 | 0 | 0.0000 | 0.75 | 0.6250 | 0 | 0.0000 | 0.75 |
| | A325N | | | | A325N | | | | A325N | | | |

Guy Pressures

| Guy Elevation ft | Guy Location | z ft | q _z psf | q _z Ice psf | Ice Thickness in |
|---------------------|--------------|---------|-----------------------|------------------------------|---------------------|
| 138 | A | 62.00 | 23 | 6 | 2.1302 |
| | B | 52.00 | 23 | 6 | 2.0930 |
| | C | 50.00 | 22 | 6 | 2.0849 |

| | | |
|--|---|----------------------------------|
| tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587 | Job 17012.45 - CT11180C | Page 9 of 44 |
| | Project 150' Guyed Tower - 130 Vernon Road Bolton, CT | Date 13:20:26 04/20/17 |
| | Client T-Mobile | Designed by TJL |

| Guy Elevation ft | Guy Location | z ft | qz psf | qz Ice psf | Ice Thickness in |
|---------------------|--------------|---------|-----------|---------------|---------------------|
| 70 | A | 28.00 | 20 | 5 | 1.9674 |
| | B | 18.00 | 18 | 5 | 1.8824 |
| | C | 16.00 | 18 | 5 | 1.8603 |

Guy-Tensioning Information

| Temperature At Time Of Tensioning | | | | | | | | | | | | | | | | | |
|-----------------------------------|---------|---------|----------------------|-----------------|----------------------|-----------------|----------------------|-----------------|----------------------|-----------------|----------------------|-----------------|----------------------|-----------------|----------------------|-----------------|-------|
| Guy Elevation ft | H ft | V ft | 0 F | | 20 F | | 40 F | | 60 F | | 80 F | | 100 F | | 120 F | | |
| | | | Initial Tension K | Intercept ft | Initial Tension K | Intercept ft | Initial Tension K | Intercept ft | Initial Tension K | Intercept ft | Initial Tension K | Intercept ft | Initial Tension K | Intercept ft | Initial Tension K | Intercept ft | |
| | | | 138 | A | 206.62 | 152.00 | 4.437 | 4.91 | 4.118 | 5.29 | 3.805 | 5.72 | 3.500 | 6.21 | 3.205 | 6.78 | 2.922 |
| | B | 206.62 | 172.00 | 4.351 | 5.49 | 4.062 | 5.88 | 3.778 | 6.32 | 3.500 | 6.81 | 3.231 | 7.37 | 2.971 | 8.00 | 2.724 | 8.72 |
| | C | 206.62 | 176.00 | 4.335 | 5.62 | 4.051 | 6.01 | 3.772 | 6.45 | 3.500 | 6.94 | 3.235 | 7.50 | 2.981 | 8.13 | 2.737 | 8.84 |
| 70 | A | 207.83 | 84.00 | 6.644 | 3.75 | 6.083 | 4.10 | 5.533 | 4.50 | 5.000 | 4.98 | 4.488 | 5.54 | 4.005 | 6.21 | 3.559 | 6.98 |
| | B | 207.83 | 104.00 | 6.527 | 4.10 | 6.006 | 4.45 | 5.496 | 4.86 | 5.000 | 5.34 | 4.523 | 5.90 | 4.070 | 6.55 | 3.647 | 7.30 |
| | C | 207.83 | 108.00 | 6.503 | 4.18 | 5.990 | 4.53 | 5.488 | 4.95 | 5.000 | 5.42 | 4.530 | 5.98 | 4.083 | 6.63 | 3.666 | 7.37 |

Feed Line/Linear Appurtenances - Entered As Round Or Flat

| Description | Face or Leg | Allow Shield | Component Type | Placement ft | Face Offset in | Lateral Offset (Frac FW) | # | # Per Row | Clear Spacing in | Width or Diameter in | Perimeter in | Weight plf |
|-----------------------------------|-------------|--------------|----------------|-----------------|-------------------|-----------------------------|---|-----------|---------------------|-------------------------|-----------------|---------------|
| HYBRIFLEX 1-1/4" (Sprint) | B | No | Ar (CaAa) | 148.00 - 0.00 | 0.0000 | -0.3 | 3 | 3 | 1.5400 | 1.5400 | | 1.30 |
| HYBRIFLEX 1-1/4" (T-Mobile) | C | No | Ar (CaAa) | 148.00 - 0.00 | 0.0000 | -0.35 | 2 | 2 | 1.5400 | 1.5400 | | 1.30 |
| 1 5/8 (T-Mobile - Proposed) | C | No | Ar (CaAa) | 148.00 - 0.00 | 0.0000 | -0.1 | 4 | 4 | 1.9800 | 1.9800 | | 1.04 |

Feed Line/Linear Appurtenances Section Areas

| Tower Section | Tower Elevation ft | Face | A _R ft ² | A _F ft ² | C _{A_A} In Face ft ² | C _{A_A} Out Face ft ² | Weight K |
|---------------|-----------------------|------|-----------------------------------|-----------------------------------|--|---|-------------|
| T1 | 150.00-140.00 | A | 0.000 | 0.000 | 0.000 | 0.000 | 0.00 |
| | | B | 0.000 | 0.000 | 3.696 | 0.000 | 0.03 |
| | | C | 0.000 | 0.000 | 8.800 | 0.000 | 0.05 |
| T2 | 140.00-120.00 | A | 0.000 | 0.000 | 0.000 | 0.000 | 0.00 |
| | | B | 0.000 | 0.000 | 9.240 | 0.000 | 0.08 |
| | | C | 0.000 | 0.000 | 22.000 | 0.000 | 0.14 |
| T3 | 120.00-100.00 | A | 0.000 | 0.000 | 0.000 | 0.000 | 0.00 |
| | | B | 0.000 | 0.000 | 9.240 | 0.000 | 0.08 |
| | | C | 0.000 | 0.000 | 22.000 | 0.000 | 0.14 |
| T4 | 100.00-80.00 | A | 0.000 | 0.000 | 0.000 | 0.000 | 0.00 |
| | | B | 0.000 | 0.000 | 9.240 | 0.000 | 0.08 |
| | | C | 0.000 | 0.000 | 22.000 | 0.000 | 0.14 |
| T5 | 80.00-60.00 | A | 0.000 | 0.000 | 0.000 | 0.000 | 0.00 |

| | | |
|--|---|----------------------------------|
| tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587 | Job 17012.45 - CT11180C | Page 10 of 44 |
| | Project 150' Guyed Tower - 130 Vernon Road Bolton, CT | Date 13:20:26 04/20/17 |
| | Client T-Mobile | Designed by TJL |

| Tower Section | Tower Elevation ft | Face | A_R ft ² | A_F ft ² | C_{AA} In Face ft ² | C_{AA} Out Face ft ² | Weight K |
|---------------|-----------------------|------|--------------------------|--------------------------|--|---|-------------|
| T6 | 60.00-40.00 | B | 0.000 | 0.000 | 9.240 | 0.000 | 0.08 |
| | | C | 0.000 | 0.000 | 22.000 | 0.000 | 0.14 |
| | | A | 0.000 | 0.000 | 0.000 | 0.000 | 0.00 |
| T7 | 40.00-20.00 | B | 0.000 | 0.000 | 9.240 | 0.000 | 0.08 |
| | | C | 0.000 | 0.000 | 22.000 | 0.000 | 0.14 |
| | | A | 0.000 | 0.000 | 0.000 | 0.000 | 0.00 |
| T8 | 20.00-5.00 | B | 0.000 | 0.000 | 9.240 | 0.000 | 0.08 |
| | | C | 0.000 | 0.000 | 22.000 | 0.000 | 0.14 |
| | | A | 0.000 | 0.000 | 0.000 | 0.000 | 0.00 |
| T9 | 5.00-0.00 | B | 0.000 | 0.000 | 6.930 | 0.000 | 0.06 |
| | | C | 0.000 | 0.000 | 16.500 | 0.000 | 0.10 |
| | | A | 0.000 | 0.000 | 0.000 | 0.000 | 0.00 |
| | | B | 0.000 | 0.000 | 2.310 | 0.000 | 0.02 |
| | | C | 0.000 | 0.000 | 5.500 | 0.000 | 0.03 |

Feed Line/Linear Appurtenances Section Areas - With Ice

| Tower Section | Tower Elevation ft | Face or Leg | Ice Thickness in | A_R ft ² | A_F ft ² | C_{AA} In Face ft ² | C_{AA} Out Face ft ² | Weight K |
|---------------|-----------------------|-------------|---------------------|--------------------------|--------------------------|--|---|-------------|
| T1 | 150.00-140.00 | A | 2.319 | 0.000 | 0.000 | 0.000 | 0.000 | 0.00 |
| | | B | | 0.000 | 0.000 | 13.799 | 0.000 | 0.23 |
| | | C | | 0.000 | 0.000 | 30.777 | 0.000 | 0.51 |
| T2 | 140.00-120.00 | A | 2.294 | 0.000 | 0.000 | 0.000 | 0.000 | 0.00 |
| | | B | | 0.000 | 0.000 | 34.327 | 0.000 | 0.56 |
| | | C | | 0.000 | 0.000 | 76.606 | 0.000 | 1.26 |
| T3 | 120.00-100.00 | A | 2.256 | 0.000 | 0.000 | 0.000 | 0.000 | 0.00 |
| | | B | | 0.000 | 0.000 | 34.073 | 0.000 | 0.55 |
| | | C | | 0.000 | 0.000 | 76.100 | 0.000 | 1.24 |
| T4 | 100.00-80.00 | A | 2.211 | 0.000 | 0.000 | 0.000 | 0.000 | 0.00 |
| | | B | | 0.000 | 0.000 | 33.773 | 0.000 | 0.54 |
| | | C | | 0.000 | 0.000 | 75.504 | 0.000 | 1.21 |
| T5 | 80.00-60.00 | A | 2.156 | 0.000 | 0.000 | 0.000 | 0.000 | 0.00 |
| | | B | | 0.000 | 0.000 | 33.405 | 0.000 | 0.52 |
| | | C | | 0.000 | 0.000 | 74.775 | 0.000 | 1.18 |
| T6 | 60.00-40.00 | A | 2.085 | 0.000 | 0.000 | 0.000 | 0.000 | 0.00 |
| | | B | | 0.000 | 0.000 | 32.929 | 0.000 | 0.51 |
| | | C | | 0.000 | 0.000 | 73.828 | 0.000 | 1.15 |
| T7 | 40.00-20.00 | A | 1.981 | 0.000 | 0.000 | 0.000 | 0.000 | 0.00 |
| | | B | | 0.000 | 0.000 | 32.237 | 0.000 | 0.48 |
| | | C | | 0.000 | 0.000 | 72.452 | 0.000 | 1.09 |
| T8 | 20.00-5.00 | A | 1.815 | 0.000 | 0.000 | 0.000 | 0.000 | 0.00 |
| | | B | | 0.000 | 0.000 | 23.351 | 0.000 | 0.33 |
| | | C | | 0.000 | 0.000 | 52.694 | 0.000 | 0.76 |
| T9 | 5.00-0.00 | A | 1.545 | 0.000 | 0.000 | 0.000 | 0.000 | 0.00 |
| | | B | | 0.000 | 0.000 | 7.339 | 0.000 | 0.10 |
| | | C | | 0.000 | 0.000 | 16.679 | 0.000 | 0.22 |

Feed Line Center of Pressure

| Section | Elevation ft | CP_X in | CP_Z in | CP_X Ice in | CP_Z Ice in |
|---------|-----------------|--------------|--------------|---------------------|---------------------|
| T1 | 150.00-140.00 | 1.0642 | 0.6631 | 0.2703 | 0.1901 |

| | | |
|--|---|----------------------------------|
| tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587 | Job 17012.45 - CT11180C | Page 11 of 44 |
| | Project 150' Guyed Tower - 130 Vernon Road Bolton, CT | Date 13:20:26 04/20/17 |
| | Client T-Mobile | Designed by TJL |

| Section | Elevation | CP _X | CP _Z | CP _X | CP _Z |
|---------|---------------|-----------------|-----------------|-----------------|-----------------|
| | <i>ft</i> | <i>in</i> | <i>in</i> | <i>Ice</i> | <i>Ice</i> |
| | | | | <i>in</i> | <i>in</i> |
| T2 | 140.00-120.00 | 1.1887 | 0.7407 | 0.3866 | 0.2718 |
| T3 | 120.00-100.00 | 1.1887 | 0.7407 | 0.3948 | 0.2776 |
| T4 | 100.00-80.00 | 1.1629 | 0.7246 | 0.3995 | 0.2808 |
| T5 | 80.00-60.00 | 1.1514 | 0.7174 | 0.3938 | 0.2769 |
| T6 | 60.00-40.00 | 1.1629 | 0.7246 | 0.4271 | 0.3003 |
| T7 | 40.00-20.00 | 1.1629 | 0.7246 | 0.4503 | 0.3166 |
| T8 | 20.00-5.00 | 1.1332 | 0.7061 | 0.4723 | 0.3321 |
| T9 | 5.00-0.00 | 0.8277 | 0.9574 | 0.2480 | 0.3114 |

Shielding Factor Ka

| Tower Section | Feed Line Record No. | Description | Feed Line Segment Elev. | K _a No Ice | K _a Ice |
|---------------|----------------------|------------------|-------------------------|-----------------------|--------------------|
| T1 | 1 | HYBRIFLEX 1-1/4" | 140.00 - 148.00 | 0.6000 | 0.2784 |
| T1 | 2 | HYBRIFLEX 1-1/4" | 140.00 - 148.00 | 0.6000 | 0.2784 |
| T1 | 3 | 1 5/8 | 140.00 - 148.00 | 0.6000 | 0.2784 |
| T2 | 1 | HYBRIFLEX 1-1/4" | 120.00 - 140.00 | 0.6000 | 0.3564 |
| T2 | 2 | HYBRIFLEX 1-1/4" | 120.00 - 140.00 | 0.6000 | 0.3564 |
| T2 | 3 | 1 5/8 | 120.00 - 140.00 | 0.6000 | 0.3564 |
| T3 | 1 | HYBRIFLEX 1-1/4" | 100.00 - 120.00 | 0.6000 | 0.3640 |
| T3 | 2 | HYBRIFLEX 1-1/4" | 100.00 - 120.00 | 0.6000 | 0.3640 |
| T3 | 3 | 1 5/8 | 100.00 - 120.00 | 0.6000 | 0.3640 |
| T4 | 1 | HYBRIFLEX 1-1/4" | 80.00 - 100.00 | 0.6000 | 0.3684 |
| T4 | 2 | HYBRIFLEX 1-1/4" | 80.00 - 100.00 | 0.6000 | 0.3684 |
| T4 | 3 | 1 5/8 | 80.00 - 100.00 | 0.6000 | 0.3684 |
| T5 | 1 | HYBRIFLEX 1-1/4" | 60.00 - 80.00 | 0.6000 | 0.3601 |
| T5 | 2 | HYBRIFLEX 1-1/4" | 60.00 - 80.00 | 0.6000 | 0.3601 |
| T5 | 3 | 1 5/8 | 60.00 - 80.00 | 0.6000 | 0.3601 |
| T6 | 1 | HYBRIFLEX 1-1/4" | 40.00 - 60.00 | 0.6000 | 0.3934 |
| T6 | 2 | HYBRIFLEX 1-1/4" | 40.00 - 60.00 | 0.6000 | 0.3934 |
| T6 | 3 | 1 5/8 | 40.00 - 60.00 | 0.6000 | 0.3934 |
| T7 | 1 | HYBRIFLEX 1-1/4" | 20.00 - 40.00 | 0.6000 | 0.4142 |
| T7 | 2 | HYBRIFLEX 1-1/4" | 20.00 - 40.00 | 0.6000 | 0.4142 |
| T7 | 3 | 1 5/8 | 20.00 - 40.00 | 0.6000 | 0.4142 |
| T8 | 1 | HYBRIFLEX 1-1/4" | 5.00 - 20.00 | 0.6000 | 0.4310 |
| T8 | 2 | HYBRIFLEX 1-1/4" | 5.00 - 20.00 | 0.6000 | 0.4310 |
| T8 | 3 | 1 5/8 | 5.00 - 20.00 | 0.6000 | 0.4310 |
| T9 | 1 | HYBRIFLEX 1-1/4" | 0.00 - 5.00 | 0.6000 | 0.1711 |
| T9 | 2 | HYBRIFLEX 1-1/4" | 0.00 - 5.00 | 0.6000 | 0.1711 |
| T9 | 3 | 1 5/8 | 0.00 - 5.00 | 0.6000 | 0.1711 |

| | | |
|--|---|----------------------------------|
| tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587 | Job 17012.45 - CT11180C | Page 12 of 44 |
| | Project 150' Guyed Tower - 130 Vernon Road Bolton, CT | Date 13:20:26 04/20/17 |
| | Client T-Mobile | Designed by TJL |

Discrete Tower Loads

| Description | Face or Leg | Offset Type | Offsets: | | Azimuth Adjustment | Placement | C _{AA} Front | C _{AA} Side | Weight |
|----------------------------|-------------|-------------|--------------|--------|--------------------|-----------|-----------------------|----------------------|--------|
| | | | Horz Lateral | Vert | | | | | |
| | | | ft | ft | ° | ft | ft ² | ft ² | K |
| APXVSP18-C-A20 (Sprint) | A | From Leg | 3.00 | 0.0000 | 148.00 | No Ice | 8.02 | 5.28 | 0.06 |
| | | | 3.00 | | | 1/2" Ice | 8.48 | 5.74 | 0.11 |
| | | | 0.00 | | | 1" Ice | 8.94 | 6.20 | 0.16 |
| APXVSP18-C-A20 (Sprint) | B | From Leg | 3.00 | 0.0000 | 148.00 | No Ice | 8.02 | 5.28 | 0.06 |
| | | | 3.00 | | | 1/2" Ice | 8.48 | 5.74 | 0.11 |
| | | | 0.00 | | | 1" Ice | 8.94 | 6.20 | 0.16 |
| APXVSP18-C-A20 (Sprint) | C | From Leg | 3.00 | 0.0000 | 148.00 | No Ice | 8.02 | 5.28 | 0.06 |
| | | | 3.00 | | | 1/2" Ice | 8.48 | 5.74 | 0.11 |
| | | | 0.00 | | | 1" Ice | 8.94 | 6.20 | 0.16 |
| APXVTM14 (Sprint) | A | From Leg | 3.00 | 0.0000 | 148.00 | No Ice | 6.34 | 3.61 | 0.06 |
| | | | -3.00 | | | 1/2" Ice | 6.72 | 3.97 | 0.10 |
| | | | 0.00 | | | 1" Ice | 7.10 | 4.33 | 0.14 |
| APXVTM14 (Sprint) | B | From Leg | 3.00 | 0.0000 | 148.00 | No Ice | 6.34 | 3.61 | 0.06 |
| | | | -3.00 | | | 1/2" Ice | 6.72 | 3.97 | 0.10 |
| | | | 0.00 | | | 1" Ice | 7.10 | 4.33 | 0.14 |
| APXVTM14 (Sprint) | C | From Leg | 3.00 | 0.0000 | 148.00 | No Ice | 6.34 | 3.61 | 0.06 |
| | | | -3.00 | | | 1/2" Ice | 6.72 | 3.97 | 0.10 |
| | | | 0.00 | | | 1" Ice | 7.10 | 4.33 | 0.14 |
| FD-RRH 2x50 800 (Sprint) | A | From Leg | 3.00 | 0.0000 | 148.00 | No Ice | 2.06 | 1.93 | 0.06 |
| | | | 3.00 | | | 1/2" Ice | 2.24 | 2.11 | 0.09 |
| | | | 0.00 | | | 1" Ice | 2.43 | 2.29 | 0.11 |
| FD-RRH 2x50 800 (Sprint) | B | From Leg | 3.00 | 0.0000 | 148.00 | No Ice | 2.06 | 1.93 | 0.06 |
| | | | 3.00 | | | 1/2" Ice | 2.24 | 2.11 | 0.09 |
| | | | 0.00 | | | 1" Ice | 2.43 | 2.29 | 0.11 |
| FD-RRH 2x50 800 (Sprint) | C | From Leg | 3.00 | 0.0000 | 148.00 | No Ice | 2.06 | 1.93 | 0.06 |
| | | | 3.00 | | | 1/2" Ice | 2.24 | 2.11 | 0.09 |
| | | | 0.00 | | | 1" Ice | 2.43 | 2.29 | 0.11 |
| FD-RRH 4x45 1900 (Sprint) | A | From Leg | 3.00 | 0.0000 | 148.00 | No Ice | 2.32 | 2.38 | 0.06 |
| | | | 3.00 | | | 1/2" Ice | 2.52 | 2.59 | 0.08 |
| | | | 0.00 | | | 1" Ice | 2.74 | 2.80 | 0.11 |
| FD-RRH 4x45 1900 (Sprint) | B | From Leg | 3.00 | 0.0000 | 148.00 | No Ice | 2.32 | 2.38 | 0.06 |
| | | | 3.00 | | | 1/2" Ice | 2.52 | 2.59 | 0.08 |
| | | | 0.00 | | | 1" Ice | 2.74 | 2.80 | 0.11 |
| FD-RRH 4x45 1900 (Sprint) | C | From Leg | 3.00 | 0.0000 | 148.00 | No Ice | 2.32 | 2.38 | 0.06 |
| | | | 3.00 | | | 1/2" Ice | 2.52 | 2.59 | 0.08 |
| | | | 0.00 | | | 1" Ice | 2.74 | 2.80 | 0.11 |
| TD-RRH8x20-25 (Sprint) | A | From Leg | 3.00 | 0.0000 | 148.00 | No Ice | 4.05 | 1.53 | 0.07 |
| | | | 3.00 | | | 1/2" Ice | 4.30 | 1.71 | 0.10 |
| | | | 0.00 | | | 1" Ice | 4.56 | 1.90 | 0.13 |
| TD-RRH8x20-25 (Sprint) | B | From Leg | 3.00 | 0.0000 | 148.00 | No Ice | 4.05 | 1.53 | 0.07 |
| | | | 3.00 | | | 1/2" Ice | 4.30 | 1.71 | 0.10 |
| | | | 0.00 | | | 1" Ice | 4.56 | 1.90 | 0.13 |
| TD-RRH8x20-25 (Sprint) | C | From Leg | 3.00 | 0.0000 | 148.00 | No Ice | 4.05 | 1.53 | 0.07 |
| | | | 3.00 | | | 1/2" Ice | 4.30 | 1.71 | 0.10 |
| | | | 0.00 | | | 1" Ice | 4.56 | 1.90 | 0.13 |
| PiROD 12' T-Frame (Sprint) | A | None | | 0.0000 | 148.00 | No Ice | 12.20 | 12.20 | 0.36 |
| | | | | | | 1/2" Ice | 17.60 | 17.60 | 0.49 |
| | | | | | | 1" Ice | 23.00 | 23.00 | 0.62 |
| PiROD 12' T-Frame (Sprint) | B | None | | 0.0000 | 148.00 | No Ice | 12.20 | 12.20 | 0.36 |
| | | | | | | 1/2" Ice | 17.60 | 17.60 | 0.49 |
| | | | | | | 1" Ice | 23.00 | 23.00 | 0.62 |
| PiROD 12' T-Frame (Sprint) | C | None | | 0.0000 | 148.00 | No Ice | 12.20 | 12.20 | 0.36 |
| | | | | | | 1/2" Ice | 17.60 | 17.60 | 0.49 |
| | | | | | | 1" Ice | 23.00 | 23.00 | 0.62 |

| | | | | |
|--|----------------|---|--------------------|-------------------|
| tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587 | Job | 17012.45 - CT11180C | Page | 13 of 44 |
| | Project | 150' Guyed Tower - 130 Vernon Road Bolton, CT | Date | 13:20:26 04/20/17 |
| | Client | T-Mobile | Designed by | TJL |

| Description | Face or Leg | Offset Type | Offsets: | | Azimuth Adjustment | Placement | C _{AA} Front | C _{AA} Side | Weight |
|--|-------------|-------------|----------|--------|--------------------|-----------|-----------------------|----------------------|--------|
| | | | Horz | Vert | | | | | |
| | | | ft | ft | ° | ft | ft ² | ft ² | K |
| AIR21 B4A/B2P (T-Mobile) | A | From Leg | 3.00 | 0.0000 | 130.00 | No Ice | 6.05 | 4.36 | 0.08 |
| | | | 3.00 | | | 1/2" Ice | 6.42 | 4.70 | 0.12 |
| | | | 0.00 | | | 1" Ice | 6.80 | 5.06 | 0.17 |
| AIR21 B4A/B2P (T-Mobile) | C | From Leg | 3.00 | 0.0000 | 130.00 | No Ice | 6.05 | 4.36 | 0.08 |
| | | | 3.00 | | | 1/2" Ice | 6.42 | 4.70 | 0.12 |
| | | | 0.00 | | | 1" Ice | 6.80 | 5.06 | 0.17 |
| SBNH-1D65C (T-Mobile) | A | From Leg | 3.00 | 0.0000 | 130.00 | No Ice | 11.46 | 7.71 | 0.05 |
| | | | -3.00 | | | 1/2" Ice | 12.08 | 8.30 | 0.12 |
| | | | 0.00 | | | 1" Ice | 12.70 | 8.90 | 0.19 |
| SBNH-1D65C (T-Mobile) | C | From Leg | 3.00 | 0.0000 | 130.00 | No Ice | 11.46 | 7.71 | 0.05 |
| | | | -3.00 | | | 1/2" Ice | 12.08 | 8.30 | 0.12 |
| | | | 0.00 | | | 1" Ice | 12.70 | 8.90 | 0.19 |
| RRUS-11 (T-Mobile) | A | From Leg | 3.00 | 0.0000 | 130.00 | No Ice | 2.57 | 1.07 | 0.05 |
| | | | -3.00 | | | 1/2" Ice | 2.76 | 1.21 | 0.07 |
| | | | 0.00 | | | 1" Ice | 2.97 | 1.36 | 0.09 |
| RRUS-11 (T-Mobile) | C | From Leg | 3.00 | 0.0000 | 130.00 | No Ice | 2.57 | 1.07 | 0.05 |
| | | | -3.00 | | | 1/2" Ice | 2.76 | 1.21 | 0.07 |
| | | | 0.00 | | | 1" Ice | 2.97 | 1.36 | 0.09 |
| TMA 12"x6"x4" (T-Mobile - Proposed) | A | From Leg | 3.00 | 0.0000 | 130.00 | No Ice | 0.60 | 0.41 | 0.02 |
| | | | 3.00 | | | 1/2" Ice | 0.70 | 0.50 | 0.02 |
| | | | 0.00 | | | 1" Ice | 0.81 | 0.59 | 0.03 |
| TMA 12"x6"x4" (T-Mobile - Proposed) | C | From Leg | 3.00 | 0.0000 | 130.00 | No Ice | 0.60 | 0.41 | 0.02 |
| | | | 3.00 | | | 1/2" Ice | 0.70 | 0.50 | 0.02 |
| | | | 0.00 | | | 1" Ice | 0.81 | 0.59 | 0.03 |
| PiROD 12' T-Frame (T-Mobile) | A | None | | 0.0000 | 130.00 | No Ice | 12.20 | 12.20 | 0.36 |
| | | | | | | 1/2" Ice | 17.60 | 17.60 | 0.49 |
| | | | | | | 1" Ice | 23.00 | 23.00 | 0.62 |
| PiROD 12' T-Frame (T-Mobile) | C | None | | 0.0000 | 130.00 | No Ice | 12.20 | 12.20 | 0.36 |
| | | | | | | 1/2" Ice | 17.60 | 17.60 | 0.49 |
| | | | | | | 1" Ice | 23.00 | 23.00 | 0.62 |

Tower Pressures - No Ice

$$G_H = 0.850$$

| Section Elevation | z | K _Z | q _z | A _G | F _a | A _F | A _R | A _{leg} | Leg % | C _{AA} In Face | C _{AA} Out Face |
|---------------------|--------|----------------|----------------|-----------------|----------------|-----------------|-----------------|------------------|-------|-------------------------|--------------------------|
| ft | ft | | psf | ft ² | e | ft ² | ft ² | ft ² | | ft ² | ft ² |
| T1 150.00-140.00 | 145.00 | 1.369 | 28 | 39.167 | A | 0.000 | 6.244 | 3.333 | 53.39 | 0.000 | 0.000 |
| | | | | | B | 0.000 | 6.244 | | | 3.696 | 0.000 |
| | | | | | C | 0.000 | 6.244 | | | 8.800 | 0.000 |
| T2 140.00-120.00 | 130.00 | 1.337 | 27 | 78.333 | A | 0.000 | 11.356 | 6.667 | 58.71 | 0.000 | 0.000 |
| | | | | | B | 0.000 | 11.356 | | | 9.240 | 0.000 |
| | | | | | C | 0.000 | 11.356 | | | 22.000 | 0.000 |
| T3 120.00-100.00 | 110.00 | 1.291 | 26 | 78.333 | A | 0.000 | 11.356 | 6.667 | 58.71 | 0.000 | 0.000 |
| | | | | | B | 0.000 | 11.356 | | | 9.240 | 0.000 |
| | | | | | C | 0.000 | 11.356 | | | 22.000 | 0.000 |
| T4 100.00-80.00 | 90.00 | 1.238 | 25 | 78.750 | A | 0.000 | 12.162 | 7.500 | 61.67 | 0.000 | 0.000 |
| | | | | | B | 0.000 | 12.162 | | | 9.240 | 0.000 |

| | | |
|--|---|----------------------------------|
| tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587 | Job 17012.45 - CT11180C | Page 14 of 44 |
| | Project 150' Guyed Tower - 130 Vernon Road Bolton, CT | Date 13:20:26 04/20/17 |
| | Client T-Mobile | Designed by TJL |

| Section Elevation ft | z ft | K _Z | q _z psf | A _G ft ² | F a c e | A _F ft ² | A _R ft ² | A _{leg} ft ² | Leg % | C _{AA} In Face ft ² | C _{AA} Out Face ft ² |
|-------------------------|---------|----------------|-----------------------|-----------------------------------|------------------|-----------------------------------|-----------------------------------|-------------------------------------|----------|--|---|
| T5 80.00-60.00 | 70.00 | 1.174 | 24 | 78.750 | C | 0.000 | 12.162 | 7.500 | 61.67 | 22.000 | 0.000 |
| | | | | | A | 0.000 | 12.533 | | | 0.000 | 0.000 |
| | | | | | B | 0.000 | 12.533 | | | 9.240 | 0.000 |
| T6 60.00-40.00 | 50.00 | 1.094 | 22 | 78.750 | C | 0.000 | 12.533 | 7.500 | 61.67 | 22.000 | 0.000 |
| | | | | | A | 0.000 | 12.162 | | | 0.000 | 0.000 |
| | | | | | B | 0.000 | 12.162 | | | 9.240 | 0.000 |
| T7 40.00-20.00 | 30.00 | 0.982 | 20 | 78.750 | C | 0.000 | 12.162 | 7.500 | 61.67 | 22.000 | 0.000 |
| | | | | | A | 0.000 | 12.162 | | | 0.000 | 0.000 |
| | | | | | B | 0.000 | 12.162 | | | 9.240 | 0.000 |
| T8 20.00-5.00 | 12.50 | 0.85 | 17 | 59.375 | C | 0.000 | 12.162 | 6.250 | 61.67 | 22.000 | 0.000 |
| | | | | | A | 0.000 | 9.853 | | | 0.000 | 0.000 |
| | | | | | B | 0.000 | 9.853 | | | 6.930 | 0.000 |
| T9 5.00-0.00 | 2.50 | 0.85 | 17 | 10.488 | C | 0.000 | 9.853 | 2.270 | 63.43 | 16.500 | 0.000 |
| | | | | | A | 0.618 | 2.985 | | | 63.00 | 0.000 |
| | | | | | B | 0.618 | 2.985 | | | 63.00 | 2.310 |
| | | | | | C | 0.618 | 2.985 | | 63.00 | 5.500 | 0.000 |

Tower Pressure - With Ice

$$G_H = 0.850$$

| Section Elevation ft | z ft | K _Z | q _z psf | t _z in | A _G ft ² | F a c e | A _F ft ² | A _R ft ² | A _{leg} ft ² | Leg % | C _{AA} In Face ft ² | C _{AA} Out Face ft ² |
|-------------------------|---------|----------------|-----------------------|----------------------|-----------------------------------|------------------|-----------------------------------|-----------------------------------|-------------------------------------|----------|--|---|
| T1 150.00-140.00 | 145.00 | 1.369 | 7 | 2.3191 | 43.032 | A | 0.000 | 31.051 | 11.064 | 35.63 | 0.000 | 0.000 |
| | | | | | | B | 0.000 | 31.051 | | | 13.799 | 0.000 |
| | | | | | | C | 0.000 | 31.051 | | | 30.777 | 0.000 |
| T2 140.00-120.00 | 130.00 | 1.337 | 7 | 2.2939 | 85.980 | A | 0.000 | 55.334 | 21.959 | 39.68 | 0.000 | 0.000 |
| | | | | | | B | 0.000 | 55.334 | | | 34.327 | 0.000 |
| | | | | | | C | 0.000 | 55.334 | | | 76.606 | 0.000 |
| T3 120.00-100.00 | 110.00 | 1.291 | 7 | 2.2559 | 85.853 | A | 0.000 | 54.606 | 21.706 | 39.75 | 0.000 | 0.000 |
| | | | | | | B | 0.000 | 54.606 | | | 34.073 | 0.000 |
| | | | | | | C | 0.000 | 54.606 | | | 76.100 | 0.000 |
| T4 100.00-80.00 | 90.00 | 1.238 | 7 | 2.2111 | 86.120 | A | 0.000 | 54.392 | 22.240 | 40.89 | 0.000 | 0.000 |
| | | | | | | B | 0.000 | 54.392 | | | 33.773 | 0.000 |
| | | | | | | C | 0.000 | 54.392 | | | 75.504 | 0.000 |
| T5 80.00-60.00 | 70.00 | 1.174 | 6 | 2.1562 | 85.937 | A | 0.000 | 54.995 | 21.875 | 39.78 | 0.000 | 0.000 |
| | | | | | | B | 0.000 | 54.995 | | | 33.405 | 0.000 |
| | | | | | | C | 0.000 | 54.995 | | | 74.775 | 0.000 |
| T6 60.00-40.00 | 50.00 | 1.094 | 6 | 2.0849 | 85.700 | A | 0.000 | 51.981 | 21.399 | 41.17 | 0.000 | 0.000 |
| | | | | | | B | 0.000 | 51.981 | | | 32.929 | 0.000 |
| | | | | | | C | 0.000 | 51.981 | | | 73.828 | 0.000 |
| T7 40.00-20.00 | 30.00 | 0.982 | 5 | 1.9810 | 85.353 | A | 0.000 | 49.998 | 20.707 | 41.42 | 0.000 | 0.000 |
| | | | | | | B | 0.000 | 49.998 | | | 32.237 | 0.000 |
| | | | | | | C | 0.000 | 49.998 | | | 72.452 | 0.000 |
| T8 20.00-5.00 | 12.50 | 0.85 | 5 | 1.8150 | 63.912 | A | 0.000 | 36.365 | 15.325 | 42.14 | 0.000 | 0.000 |
| | | | | | | B | 0.000 | 36.365 | | | 23.351 | 0.000 |
| | | | | | | C | 0.000 | 36.365 | | | 52.694 | 0.000 |
| T9 5.00-0.00 | 2.50 | 0.85 | 5 | 1.5452 | 11.863 | A | 0.618 | 9.215 | 5.077 | 51.63 | 0.000 | 0.000 |
| | | | | | | B | 0.618 | 9.215 | | | 7.339 | 0.000 |
| | | | | | | C | 0.618 | 9.215 | | | 16.679 | 0.000 |

| | | |
|--|---|----------------------------------|
| tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587 | Job 17012.45 - CT11180C | Page 15 of 44 |
| | Project 150' Guyed Tower - 130 Vernon Road Bolton, CT | Date 13:20:26 04/20/17 |
| | Client T-Mobile | Designed by TJL |

Tower Pressure - Service

$G_H = 0.850$

| Section Elevation | z | K _Z | q _z | A _G | F a c e | A _F | A _R | A _{leg} | Leg % | C _A A _A In Face | C _A A _A Out Face |
|---------------------|--------|----------------|----------------|-----------------|---------|-----------------|-----------------|------------------|-------|---------------------------------------|--|
| ft | ft | | psf | ft ² | e | ft ² | ft ² | ft ² | | ft ² | ft ² |
| T1 150.00-140.00 | 145.00 | 1.369 | 11 | 39.167 | A | 0.000 | 6.244 | 3.333 | 53.39 | 0.000 | 0.000 |
| | | | | | B | 0.000 | 6.244 | | 53.39 | 3.696 | 0.000 |
| | | | | | C | 0.000 | 6.244 | | 53.39 | 8.800 | 0.000 |
| T2 140.00-120.00 | 130.00 | 1.337 | 10 | 78.333 | A | 0.000 | 11.356 | 6.667 | 58.71 | 0.000 | 0.000 |
| | | | | | B | 0.000 | 11.356 | | 58.71 | 9.240 | 0.000 |
| | | | | | C | 0.000 | 11.356 | | 58.71 | 22.000 | 0.000 |
| T3 120.00-100.00 | 110.00 | 1.291 | 10 | 78.333 | A | 0.000 | 11.356 | 6.667 | 58.71 | 0.000 | 0.000 |
| | | | | | B | 0.000 | 11.356 | | 58.71 | 9.240 | 0.000 |
| | | | | | C | 0.000 | 11.356 | | 58.71 | 22.000 | 0.000 |
| T4 100.00-80.00 | 90.00 | 1.238 | 10 | 78.750 | A | 0.000 | 12.162 | 7.500 | 61.67 | 0.000 | 0.000 |
| | | | | | B | 0.000 | 12.162 | | 61.67 | 9.240 | 0.000 |
| | | | | | C | 0.000 | 12.162 | | 61.67 | 22.000 | 0.000 |
| T5 80.00-60.00 | 70.00 | 1.174 | 9 | 78.750 | A | 0.000 | 12.533 | 7.500 | 59.84 | 0.000 | 0.000 |
| | | | | | B | 0.000 | 12.533 | | 59.84 | 9.240 | 0.000 |
| | | | | | C | 0.000 | 12.533 | | 59.84 | 22.000 | 0.000 |
| T6 60.00-40.00 | 50.00 | 1.094 | 9 | 78.750 | A | 0.000 | 12.162 | 7.500 | 61.67 | 0.000 | 0.000 |
| | | | | | B | 0.000 | 12.162 | | 61.67 | 9.240 | 0.000 |
| | | | | | C | 0.000 | 12.162 | | 61.67 | 22.000 | 0.000 |
| T7 40.00-20.00 | 30.00 | 0.982 | 8 | 78.750 | A | 0.000 | 12.162 | 7.500 | 61.67 | 0.000 | 0.000 |
| | | | | | B | 0.000 | 12.162 | | 61.67 | 9.240 | 0.000 |
| | | | | | C | 0.000 | 12.162 | | 61.67 | 22.000 | 0.000 |
| T8 20.00-5.00 | 12.50 | 0.85 | 7 | 59.375 | A | 0.000 | 9.853 | 6.250 | 63.43 | 0.000 | 0.000 |
| | | | | | B | 0.000 | 9.853 | | 63.43 | 6.930 | 0.000 |
| | | | | | C | 0.000 | 9.853 | | 63.43 | 16.500 | 0.000 |
| T9 5.00-0.00 | 2.50 | 0.85 | 7 | 10.488 | A | 0.618 | 2.985 | 2.270 | 63.00 | 0.000 | 0.000 |
| | | | | | B | 0.618 | 2.985 | | 63.00 | 2.310 | 0.000 |
| | | | | | C | 0.618 | 2.985 | | 63.00 | 5.500 | 0.000 |

Tower Forces - No Ice - Wind Normal To Face

| Section Elevation | Add Weight | Self Weight | F a c e | e | C _F | q _z | D _F | D _R | A _E | F | w | Ctrl. Face |
|---------------------|------------|-------------|---------|-------|----------------|----------------|----------------|----------------|-----------------|------|-------|------------|
| ft | K | K | e | | | psf | | | ft ² | K | plf | |
| T1 150.00-140.00 | 0.09 | 0.56 | A | 0.159 | 2.737 | 28 | 1 | 1 | 3.550 | 0.41 | 41.00 | C |
| | | | B | 0.159 | 2.737 | | 1 | 1 | 3.550 | | | |
| | | | C | 0.159 | 2.737 | | 1 | 1 | 3.550 | | | |
| T2 140.00-120.00 | 0.21 | 1.00 | A | 0.145 | 2.79 | 27 | 1 | 1 | 6.439 | 0.85 | 42.72 | C |
| | | TA 1.07 | B | 0.145 | 2.79 | | 1 | 1 | 6.439 | | | |
| | | | C | 0.145 | 2.79 | | 1 | 1 | 6.439 | | | |
| T3 120.00-100.00 | 0.21 | 1.00 | A | 0.145 | 2.79 | 26 | 1 | 1 | 6.439 | 0.82 | 41.25 | C |
| | | | B | 0.145 | 2.79 | | 1 | 1 | 6.439 | | | |
| | | | C | 0.145 | 2.79 | | 1 | 1 | 6.439 | | | |
| T4 100.00-80.00 | 0.21 | 1.17 | A | 0.154 | 2.755 | 25 | 1 | 1 | 6.908 | 0.81 | 40.69 | C |
| | | | B | 0.154 | 2.755 | | 1 | 1 | 6.908 | | | |
| | | | C | 0.154 | 2.755 | | 1 | 1 | 6.908 | | | |
| T5 80.00-60.00 | 0.21 | 1.21 | A | 0.159 | 2.738 | 24 | 1 | 1 | 7.126 | 0.78 | 39.08 | C |
| | | | B | 0.159 | 2.738 | | 1 | 1 | 7.126 | | | |
| | | | C | 0.159 | 2.738 | | 1 | 1 | 7.126 | | | |
| T6 60.00-40.00 | 0.21 | 1.17 | A | 0.154 | 2.755 | 22 | 1 | 1 | 6.908 | 0.72 | 35.95 | C |
| | | | B | 0.154 | 2.755 | | 1 | 1 | 6.908 | | | |

| | | |
|--|---|----------------------------------|
| tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587 | Job 17012.45 - CT11180C | Page 16 of 44 |
| | Project 150' Guyed Tower - 130 Vernon Road Bolton, CT | Date 13:20:26 04/20/17 |
| | Client T-Mobile | Designed by TJL |

| Section Elevation ft | Add Weight K | Self Weight K | F a c e | e | C _F | q _z psf | D _F | D _R | A _E ft ² | F K | w plf | Ctrl. Face |
|-------------------------|-----------------|------------------|---------|-------|----------------|-----------------------|----------------|----------------|-----------------------------------|--------|----------|------------|
| T7 40.00-20.00 | 0.21 | 1.17 | C | 0.154 | 2.755 | 20 | 1 | 1 | 6.908 | 0.65 | 32.29 | C |
| | | | A | 0.154 | 2.755 | | 1 | 1 | 6.908 | | | |
| | | | B | 0.154 | 2.755 | | 1 | 1 | 6.908 | | | |
| T8 20.00-5.00 | 0.16 | 1.03 | C | 0.154 | 2.755 | 17 | 1 | 1 | 6.908 | 0.43 | 28.88 | C |
| | | | A | 0.166 | 2.714 | | 1 | 1 | 5.610 | | | |
| | | | B | 0.166 | 2.714 | | 1 | 1 | 5.610 | | | |
| T9 5.00-0.00 | 0.05 | 0.37 | C | 0.166 | 2.714 | 17 | 1 | 1 | 5.610 | 0.15 | 29.71 | C |
| | | | A | 0.344 | 2.187 | | 1 | 1 | 2.450 | | | |
| | | | B | 0.344 | 2.187 | | 1 | 1 | 2.450 | | | |
| Sum Weight: | 1.58 | 9.73 | C | 0.344 | 2.187 | | 1 | 1 | 2.450 | 5.63 | | |

Tower Forces - No Ice - Wind 45 To Face

| Section Elevation ft | Add Weight K | Self Weight K | F a c e | e | C _F | q _z psf | D _F | D _R | A _E ft ² | F K | w plf | Ctrl. Face |
|-------------------------|-----------------|------------------|---------|-------|----------------|-----------------------|----------------|----------------|-----------------------------------|--------|----------|------------|
| T1 150.00-140.00 | 0.09 | 0.56 | A | 0.159 | 2.737 | 28 | 0.825 | 1 | 3.550 | 0.41 | 41.00 | C |
| | | | B | 0.159 | 2.737 | | 0.825 | 1 | 3.550 | | | |
| | | | C | 0.159 | 2.737 | | 0.825 | 1 | 3.550 | | | |
| T2 140.00-120.00 | 0.21 | 1.00 | A | 0.145 | 2.79 | 27 | 0.825 | 1 | 6.439 | 0.85 | 42.72 | C |
| | | TA | B | 0.145 | 2.79 | | 0.825 | 1 | 6.439 | | | |
| | | C | 0.145 | 2.79 | 0.825 | | 1 | 6.439 | | | | |
| T3 120.00-100.00 | 0.21 | 1.00 | A | 0.145 | 2.79 | 26 | 0.825 | 1 | 6.439 | 0.82 | 41.25 | C |
| | | B | 0.145 | 2.79 | 0.825 | | 1 | 6.439 | | | | |
| | | C | 0.145 | 2.79 | 0.825 | | 1 | 6.439 | | | | |
| T4 100.00-80.00 | 0.21 | 1.17 | A | 0.154 | 2.755 | 25 | 0.825 | 1 | 6.908 | 0.81 | 40.69 | C |
| | | B | 0.154 | 2.755 | 0.825 | | 1 | 6.908 | | | | |
| | | C | 0.154 | 2.755 | 0.825 | | 1 | 6.908 | | | | |
| T5 80.00-60.00 | 0.21 | 1.21 | A | 0.159 | 2.738 | 24 | 0.825 | 1 | 7.126 | 0.78 | 39.08 | C |
| | | B | 0.159 | 2.738 | 0.825 | | 1 | 7.126 | | | | |
| | | C | 0.159 | 2.738 | 0.825 | | 1 | 7.126 | | | | |
| T6 60.00-40.00 | 0.21 | 1.17 | A | 0.154 | 2.755 | 22 | 0.825 | 1 | 6.908 | 0.72 | 35.95 | C |
| | | B | 0.154 | 2.755 | 0.825 | | 1 | 6.908 | | | | |
| | | C | 0.154 | 2.755 | 0.825 | | 1 | 6.908 | | | | |
| T7 40.00-20.00 | 0.21 | 1.17 | A | 0.154 | 2.755 | 20 | 0.825 | 1 | 6.908 | 0.65 | 32.29 | C |
| | | B | 0.154 | 2.755 | 0.825 | | 1 | 6.908 | | | | |
| | | C | 0.154 | 2.755 | 0.825 | | 1 | 6.908 | | | | |
| T8 20.00-5.00 | 0.16 | 1.03 | A | 0.166 | 2.714 | 17 | 0.825 | 1 | 5.610 | 0.43 | 28.88 | C |
| | | B | 0.166 | 2.714 | 0.825 | | 1 | 5.610 | | | | |
| | | C | 0.166 | 2.714 | 0.825 | | 1 | 5.610 | | | | |
| T9 5.00-0.00 | 0.05 | 0.37 | A | 0.344 | 2.187 | 17 | 0.825 | 1 | 2.342 | 0.15 | 29.01 | C |
| | | B | 0.344 | 2.187 | 0.825 | | 1 | 2.342 | | | | |
| | | C | 0.344 | 2.187 | 0.825 | | 1 | 2.342 | | | | |
| Sum Weight: | 1.58 | 9.73 | C | 0.344 | 2.187 | | 0.825 | 1 | 2.342 | 5.63 | | |

Tower Forces - No Ice - Wind 60 To Face

| | | |
|--|---|----------------------------------|
| tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587 | Job 17012.45 - CT11180C | Page 17 of 44 |
| | Project 150' Guyed Tower - 130 Vernon Road Bolton, CT | Date 13:20:26 04/20/17 |
| | Client T-Mobile | Designed by TJL |

| Section Elevation ft | Add Weight K | Self Weight K | F a c e | e | C _F | q _z psf | D _F | D _R | A _E ft ² | F K | w plf | Ctrl. Face |
|-------------------------|-----------------|------------------|---------|-------|----------------|-----------------------|----------------|----------------|-----------------------------------|--------|----------|------------|
| T1 150.00-140.00 | 0.09 | 0.56 | A | 0.159 | 2.737 | 28 | 0.8 | 1 | 3.550 | 0.41 | 41.00 | C |
| | | | B | 0.159 | 2.737 | | 0.8 | 1 | 3.550 | | | |
| | | | C | 0.159 | 2.737 | | 0.8 | 1 | 3.550 | | | |
| T2 140.00-120.00 | 0.21 | 1.00 TA 1.07 | A | 0.145 | 2.79 | 27 | 0.8 | 1 | 6.439 | 0.85 | 42.72 | C |
| | | | B | 0.145 | 2.79 | | 0.8 | 1 | 6.439 | | | |
| | | | C | 0.145 | 2.79 | | 0.8 | 1 | 6.439 | | | |
| T3 120.00-100.00 | 0.21 | 1.00 | A | 0.145 | 2.79 | 26 | 0.8 | 1 | 6.439 | 0.82 | 41.25 | C |
| | | | B | 0.145 | 2.79 | | 0.8 | 1 | 6.439 | | | |
| | | | C | 0.145 | 2.79 | | 0.8 | 1 | 6.439 | | | |
| T4 100.00-80.00 | 0.21 | 1.17 | A | 0.154 | 2.755 | 25 | 0.8 | 1 | 6.908 | 0.81 | 40.69 | C |
| | | | B | 0.154 | 2.755 | | 0.8 | 1 | 6.908 | | | |
| | | | C | 0.154 | 2.755 | | 0.8 | 1 | 6.908 | | | |
| T5 80.00-60.00 | 0.21 | 1.21 | A | 0.159 | 2.738 | 24 | 0.8 | 1 | 7.126 | 0.78 | 39.08 | C |
| | | | B | 0.159 | 2.738 | | 0.8 | 1 | 7.126 | | | |
| | | | C | 0.159 | 2.738 | | 0.8 | 1 | 7.126 | | | |
| T6 60.00-40.00 | 0.21 | 1.17 | A | 0.154 | 2.755 | 22 | 0.8 | 1 | 6.908 | 0.72 | 35.95 | C |
| | | | B | 0.154 | 2.755 | | 0.8 | 1 | 6.908 | | | |
| | | | C | 0.154 | 2.755 | | 0.8 | 1 | 6.908 | | | |
| T7 40.00-20.00 | 0.21 | 1.17 | A | 0.154 | 2.755 | 20 | 0.8 | 1 | 6.908 | 0.65 | 32.29 | C |
| | | | B | 0.154 | 2.755 | | 0.8 | 1 | 6.908 | | | |
| | | | C | 0.154 | 2.755 | | 0.8 | 1 | 6.908 | | | |
| T8 20.00-5.00 | 0.16 | 1.03 | A | 0.166 | 2.714 | 17 | 0.8 | 1 | 5.610 | 0.43 | 28.88 | C |
| | | | B | 0.166 | 2.714 | | 0.8 | 1 | 5.610 | | | |
| | | | C | 0.166 | 2.714 | | 0.8 | 1 | 5.610 | | | |
| T9 5.00-0.00 | 0.05 | 0.37 | A | 0.344 | 2.187 | 17 | 0.8 | 1 | 2.326 | 0.14 | 28.91 | C |
| | | | B | 0.344 | 2.187 | | 0.8 | 1 | 2.326 | | | |
| | | | C | 0.344 | 2.187 | | 0.8 | 1 | 2.326 | | | |
| Sum Weight: | 1.58 | 9.73 | | | | | | | | 5.63 | | |

Tower Forces - No Ice - Wind 90 To Face

| Section Elevation ft | Add Weight K | Self Weight K | F a c e | e | C _F | q _z psf | D _F | D _R | A _E ft ² | F K | w plf | Ctrl. Face |
|-------------------------|-----------------|------------------|---------|-------|----------------|-----------------------|----------------|----------------|-----------------------------------|--------|----------|------------|
| T1 150.00-140.00 | 0.09 | 0.56 | A | 0.159 | 2.737 | 28 | 0.85 | 1 | 3.550 | 0.41 | 41.00 | C |
| | | | B | 0.159 | 2.737 | | 0.85 | 1 | 3.550 | | | |
| | | | C | 0.159 | 2.737 | | 0.85 | 1 | 3.550 | | | |
| T2 140.00-120.00 | 0.21 | 1.00 TA 1.07 | A | 0.145 | 2.79 | 27 | 0.85 | 1 | 6.439 | 0.85 | 42.72 | C |
| | | | B | 0.145 | 2.79 | | 0.85 | 1 | 6.439 | | | |
| | | | C | 0.145 | 2.79 | | 0.85 | 1 | 6.439 | | | |
| T3 120.00-100.00 | 0.21 | 1.00 | A | 0.145 | 2.79 | 26 | 0.85 | 1 | 6.439 | 0.82 | 41.25 | C |
| | | | B | 0.145 | 2.79 | | 0.85 | 1 | 6.439 | | | |
| | | | C | 0.145 | 2.79 | | 0.85 | 1 | 6.439 | | | |
| T4 100.00-80.00 | 0.21 | 1.17 | A | 0.154 | 2.755 | 25 | 0.85 | 1 | 6.908 | 0.81 | 40.69 | C |
| | | | B | 0.154 | 2.755 | | 0.85 | 1 | 6.908 | | | |
| | | | C | 0.154 | 2.755 | | 0.85 | 1 | 6.908 | | | |
| T5 80.00-60.00 | 0.21 | 1.21 | A | 0.159 | 2.738 | 24 | 0.85 | 1 | 7.126 | 0.78 | 39.08 | C |
| | | | B | 0.159 | 2.738 | | 0.85 | 1 | 7.126 | | | |
| | | | C | 0.159 | 2.738 | | 0.85 | 1 | 7.126 | | | |
| T6 60.00-40.00 | 0.21 | 1.17 | A | 0.154 | 2.755 | 22 | 0.85 | 1 | 6.908 | 0.72 | 35.95 | C |
| | | | B | 0.154 | 2.755 | | 0.85 | 1 | 6.908 | | | |
| | | | C | 0.154 | 2.755 | | 0.85 | 1 | 6.908 | | | |
| T7 40.00-20.00 | 0.21 | 1.17 | A | 0.154 | 2.755 | 20 | 0.85 | 1 | 6.908 | 0.65 | 32.29 | C |

| | | | | |
|--|----------------|---|--------------------|-------------------|
| tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587 | Job | 17012.45 - CT11180C | Page | 18 of 44 |
| | Project | 150' Guyed Tower - 130 Vernon Road Bolton, CT | Date | 13:20:26 04/20/17 |
| | Client | T-Mobile | Designed by | TJL |

| Section Elevation ft | Add Weight K | Self Weight K | F a c e | e | C _F | q _z psf | D _F | D _R | A _E ft ² | F K | w plf | Ctrl. Face |
|-------------------------|-----------------|------------------|---------|-------|----------------|-----------------------|----------------|----------------|-----------------------------------|--------|----------|------------|
| 40.00-20.00 | | | B | 0.154 | 2.755 | | 0.85 | 1 | 6.908 | | | |
| T8 20.00-5.00 | 0.16 | 1.03 | C | 0.154 | 2.755 | | 0.85 | 1 | 6.908 | | | |
| | | | A | 0.166 | 2.714 | 17 | 0.85 | 1 | 5.610 | 0.43 | 28.88 | C |
| | | | B | 0.166 | 2.714 | | 0.85 | 1 | 5.610 | | | |
| T9 5.00-0.00 | 0.05 | 0.37 | C | 0.166 | 2.714 | | 0.85 | 1 | 5.610 | | | |
| | | | A | 0.344 | 2.187 | 17 | 0.85 | 1 | 2.357 | 0.15 | 29.11 | C |
| | | | B | 0.344 | 2.187 | | 0.85 | 1 | 2.357 | | | |
| Sum Weight: | 1.58 | 9.73 | C | 0.344 | 2.187 | | 0.85 | 1 | 2.357 | 5.63 | | |

Tower Forces - With Ice - Wind Normal To Face

| Section Elevation ft | Add Weight K | Self Weight K | F a c e | e | C _F | q _z psf | D _F | D _R | A _E ft ² | F K | w plf | Ctrl. Face |
|-------------------------|-----------------|------------------|---------|-------|----------------|-----------------------|----------------|----------------|-----------------------------------|--------|----------|------------|
| T1 150.00-140.00 | 0.73 | 2.15 | A | 0.722 | 1.779 | 7 | 1 | 1 | 25.666 | 0.37 | 36.75 | C |
| | | | B | 0.722 | 1.779 | | 1 | 1 | 25.666 | | | |
| | | | C | 0.722 | 1.779 | | 1 | 1 | 25.666 | | | |
| T2 140.00-120.00 | 1.81 | 3.73 TA 3.12 | A | 0.644 | 1.783 | 7 | 1 | 1 | 42.725 | 0.72 | 35.79 | C |
| | | | B | 0.644 | 1.783 | | 1 | 1 | 42.725 | | | |
| | | | C | 0.644 | 1.783 | | 1 | 1 | 42.725 | | | |
| T3 120.00-100.00 | 1.78 | 3.65 | A | 0.636 | 1.786 | 7 | 1 | 1 | 41.889 | 0.69 | 34.31 | C |
| | | | B | 0.636 | 1.786 | | 1 | 1 | 41.889 | | | |
| | | | C | 0.636 | 1.786 | | 1 | 1 | 41.889 | | | |
| T4 100.00-80.00 | 1.75 | 3.77 | A | 0.632 | 1.788 | 7 | 1 | 1 | 41.564 | 0.66 | 32.79 | C |
| | | | B | 0.632 | 1.788 | | 1 | 1 | 41.564 | | | |
| | | | C | 0.632 | 1.788 | | 1 | 1 | 41.564 | | | |
| T5 80.00-60.00 | 1.71 | 3.81 | A | 0.64 | 1.785 | 6 | 1 | 1 | 42.330 | 0.62 | 31.08 | C |
| | | | B | 0.64 | 1.785 | | 1 | 1 | 42.330 | | | |
| | | | C | 0.64 | 1.785 | | 1 | 1 | 42.330 | | | |
| T6 60.00-40.00 | 1.65 | 3.53 | A | 0.607 | 1.8 | 6 | 1 | 1 | 38.878 | 0.57 | 28.32 | C |
| | | | B | 0.607 | 1.8 | | 1 | 1 | 38.878 | | | |
| | | | C | 0.607 | 1.8 | | 1 | 1 | 38.878 | | | |
| T7 40.00-20.00 | 1.57 | 3.34 | A | 0.586 | 1.814 | 5 | 1 | 1 | 36.741 | 0.50 | 24.98 | C |
| | | | B | 0.586 | 1.814 | | 1 | 1 | 36.741 | | | |
| | | | C | 0.586 | 1.814 | | 1 | 1 | 36.741 | | | |
| T8 20.00-5.00 | 1.09 | 2.50 | A | 0.569 | 1.827 | 5 | 1 | 1 | 26.348 | 0.32 | 21.20 | C |
| | | | B | 0.569 | 1.827 | | 1 | 1 | 26.348 | | | |
| | | | C | 0.569 | 1.827 | | 1 | 1 | 26.348 | | | |
| T9 5.00-0.00 | 0.32 | 0.73 | A | 0.829 | 1.84 | 5 | 1 | 1 | 8.987 | 0.08 | 16.23 | C |
| | | | B | 0.829 | 1.84 | | 1 | 1 | 8.987 | | | |
| | | | C | 0.829 | 1.84 | | 1 | 1 | 8.987 | | | |
| Sum Weight: | 12.42 | 30.33 | | | | | | | | 4.51 | | |

Tower Forces - With Ice - Wind 45 To Face

| | | |
|--|---|----------------------------------|
| tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587 | Job 17012.45 - CT11180C | Page 19 of 44 |
| | Project 150' Guyed Tower - 130 Vernon Road Bolton, CT | Date 13:20:26 04/20/17 |
| | Client T-Mobile | Designed by TJL |

| Section Elevation ft | Add Weight K | Self Weight K | F a c e | e | C _F | q _z psf | D _F | D _R | A _E ft ² | F K | w plf | Ctrl. Face |
|-------------------------|-----------------|------------------|---------|-------|----------------|-----------------------|----------------|----------------|-----------------------------------|--------|----------|------------|
| T1 150.00-140.00 | 0.73 | 2.15 | A | 0.722 | 1.779 | 7 | 0.825 | 1 | 25.666 | 0.37 | 36.75 | C |
| | | | B | 0.722 | 1.779 | | 0.825 | 1 | 25.666 | | | |
| | | | C | 0.722 | 1.779 | | 0.825 | 1 | 25.666 | | | |
| T2 140.00-120.00 | 1.81 | 3.73 TA 3.12 | A | 0.644 | 1.783 | 7 | 0.825 | 1 | 42.725 | 0.72 | 35.79 | C |
| | | | B | 0.644 | 1.783 | | 0.825 | 1 | 42.725 | | | |
| | | | C | 0.644 | 1.783 | | 0.825 | 1 | 42.725 | | | |
| T3 120.00-100.00 | 1.78 | 3.65 | A | 0.636 | 1.786 | 7 | 0.825 | 1 | 41.889 | 0.69 | 34.31 | C |
| | | | B | 0.636 | 1.786 | | 0.825 | 1 | 41.889 | | | |
| | | | C | 0.636 | 1.786 | | 0.825 | 1 | 41.889 | | | |
| T4 100.00-80.00 | 1.75 | 3.77 | A | 0.632 | 1.788 | 7 | 0.825 | 1 | 41.564 | 0.66 | 32.79 | C |
| | | | B | 0.632 | 1.788 | | 0.825 | 1 | 41.564 | | | |
| | | | C | 0.632 | 1.788 | | 0.825 | 1 | 41.564 | | | |
| T5 80.00-60.00 | 1.71 | 3.81 | A | 0.64 | 1.785 | 6 | 0.825 | 1 | 42.330 | 0.62 | 31.08 | C |
| | | | B | 0.64 | 1.785 | | 0.825 | 1 | 42.330 | | | |
| | | | C | 0.64 | 1.785 | | 0.825 | 1 | 42.330 | | | |
| T6 60.00-40.00 | 1.65 | 3.53 | A | 0.607 | 1.8 | 6 | 0.825 | 1 | 38.878 | 0.57 | 28.32 | C |
| | | | B | 0.607 | 1.8 | | 0.825 | 1 | 38.878 | | | |
| | | | C | 0.607 | 1.8 | | 0.825 | 1 | 38.878 | | | |
| T7 40.00-20.00 | 1.57 | 3.34 | A | 0.586 | 1.814 | 5 | 0.825 | 1 | 36.741 | 0.50 | 24.98 | C |
| | | | B | 0.586 | 1.814 | | 0.825 | 1 | 36.741 | | | |
| | | | C | 0.586 | 1.814 | | 0.825 | 1 | 36.741 | | | |
| T8 20.00-5.00 | 1.09 | 2.50 | A | 0.569 | 1.827 | 5 | 0.825 | 1 | 26.348 | 0.32 | 21.20 | C |
| | | | B | 0.569 | 1.827 | | 0.825 | 1 | 26.348 | | | |
| | | | C | 0.569 | 1.827 | | 0.825 | 1 | 26.348 | | | |
| T9 5.00-0.00 | 0.32 | 0.73 | A | 0.829 | 1.84 | 5 | 0.825 | 1 | 8.879 | 0.08 | 16.07 | C |
| | | | B | 0.829 | 1.84 | | 0.825 | 1 | 8.879 | | | |
| | | | C | 0.829 | 1.84 | | 0.825 | 1 | 8.879 | | | |
| Sum Weight: | 12.42 | 30.33 | | | | | | | | 4.51 | | |

Tower Forces - With Ice - Wind 60 To Face

| Section Elevation ft | Add Weight K | Self Weight K | F a c e | e | C _F | q _z psf | D _F | D _R | A _E ft ² | F K | w plf | Ctrl. Face |
|-------------------------|-----------------|------------------|---------|-------|----------------|-----------------------|----------------|----------------|-----------------------------------|--------|----------|------------|
| T1 150.00-140.00 | 0.73 | 2.15 | A | 0.722 | 1.779 | 7 | 0.8 | 1 | 25.666 | 0.37 | 36.75 | C |
| | | | B | 0.722 | 1.779 | | 0.8 | 1 | 25.666 | | | |
| | | | C | 0.722 | 1.779 | | 0.8 | 1 | 25.666 | | | |
| T2 140.00-120.00 | 1.81 | 3.73 TA 3.12 | A | 0.644 | 1.783 | 7 | 0.8 | 1 | 42.725 | 0.72 | 35.79 | C |
| | | | B | 0.644 | 1.783 | | 0.8 | 1 | 42.725 | | | |
| | | | C | 0.644 | 1.783 | | 0.8 | 1 | 42.725 | | | |
| T3 120.00-100.00 | 1.78 | 3.65 | A | 0.636 | 1.786 | 7 | 0.8 | 1 | 41.889 | 0.69 | 34.31 | C |
| | | | B | 0.636 | 1.786 | | 0.8 | 1 | 41.889 | | | |
| | | | C | 0.636 | 1.786 | | 0.8 | 1 | 41.889 | | | |
| T4 100.00-80.00 | 1.75 | 3.77 | A | 0.632 | 1.788 | 7 | 0.8 | 1 | 41.564 | 0.66 | 32.79 | C |
| | | | B | 0.632 | 1.788 | | 0.8 | 1 | 41.564 | | | |
| | | | C | 0.632 | 1.788 | | 0.8 | 1 | 41.564 | | | |
| T5 80.00-60.00 | 1.71 | 3.81 | A | 0.64 | 1.785 | 6 | 0.8 | 1 | 42.330 | 0.62 | 31.08 | C |
| | | | B | 0.64 | 1.785 | | 0.8 | 1 | 42.330 | | | |
| | | | C | 0.64 | 1.785 | | 0.8 | 1 | 42.330 | | | |
| T6 60.00-40.00 | 1.65 | 3.53 | A | 0.607 | 1.8 | 6 | 0.8 | 1 | 38.878 | 0.57 | 28.32 | C |
| | | | B | 0.607 | 1.8 | | 0.8 | 1 | 38.878 | | | |
| | | | C | 0.607 | 1.8 | | 0.8 | 1 | 38.878 | | | |
| T7 | 1.57 | 3.34 | A | 0.586 | 1.814 | 5 | 0.8 | 1 | 36.741 | 0.50 | 24.98 | C |

| | | |
|--|---|----------------------------------|
| tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587 | Job 17012.45 - CT11180C | Page 20 of 44 |
| | Project 150' Guyed Tower - 130 Vernon Road Bolton, CT | Date 13:20:26 04/20/17 |
| | Client T-Mobile | Designed by TJL |

| Section Elevation ft | Add Weight K | Self Weight K | F a c e | e | C _F | q _z psf | D _F | D _R | A _E ft ² | F K | w plf | Ctrl. Face |
|-------------------------|-----------------|------------------|---------|-------|----------------|-----------------------|----------------|----------------|-----------------------------------|--------|----------|------------|
| 40.00-20.00 | | | B | 0.586 | 1.814 | | 0.8 | 1 | 36.741 | | | |
| T8 20.00-5.00 | 1.09 | 2.50 | C | 0.586 | 1.814 | | 0.8 | 1 | 36.741 | | | |
| | | | A | 0.569 | 1.827 | 5 | 0.8 | 1 | 26.348 | 0.32 | 21.20 | C |
| | | | B | 0.569 | 1.827 | | 0.8 | 1 | 26.348 | | | |
| T9 5.00-0.00 | 0.32 | 0.73 | C | 0.569 | 1.827 | | 0.8 | 1 | 26.348 | | | |
| | | | A | 0.829 | 1.84 | 5 | 0.8 | 1 | 8.864 | 0.08 | 16.05 | C |
| | | | B | 0.829 | 1.84 | | 0.8 | 1 | 8.864 | | | |
| Sum Weight: | 12.42 | 30.33 | C | 0.829 | 1.84 | | 0.8 | 1 | 8.864 | 4.51 | | |

Tower Forces - With Ice - Wind 90 To Face

| Section Elevation ft | Add Weight K | Self Weight K | F a c e | e | C _F | q _z psf | D _F | D _R | A _E ft ² | F K | w plf | Ctrl. Face |
|-------------------------|-----------------|------------------|---------|-------|----------------|-----------------------|----------------|----------------|-----------------------------------|--------|----------|------------|
| T1 150.00-140.00 | 0.73 | 2.15 | A | 0.722 | 1.779 | 7 | 0.85 | 1 | 25.666 | 0.37 | 36.75 | C |
| | | | B | 0.722 | 1.779 | | 0.85 | 1 | 25.666 | | | |
| | | | C | 0.722 | 1.779 | | 0.85 | 1 | 25.666 | | | |
| T2 140.00-120.00 | 1.81 | 3.73 TA 3.12 | A | 0.644 | 1.783 | 7 | 0.85 | 1 | 42.725 | 0.72 | 35.79 | C |
| | | | B | 0.644 | 1.783 | | 0.85 | 1 | 42.725 | | | |
| | | | C | 0.644 | 1.783 | | 0.85 | 1 | 42.725 | | | |
| T3 120.00-100.00 | 1.78 | 3.65 | A | 0.636 | 1.786 | 7 | 0.85 | 1 | 41.889 | 0.69 | 34.31 | C |
| | | | B | 0.636 | 1.786 | | 0.85 | 1 | 41.889 | | | |
| | | | C | 0.636 | 1.786 | | 0.85 | 1 | 41.889 | | | |
| T4 100.00-80.00 | 1.75 | 3.77 | A | 0.632 | 1.788 | 7 | 0.85 | 1 | 41.564 | 0.66 | 32.79 | C |
| | | | B | 0.632 | 1.788 | | 0.85 | 1 | 41.564 | | | |
| | | | C | 0.632 | 1.788 | | 0.85 | 1 | 41.564 | | | |
| T5 80.00-60.00 | 1.71 | 3.81 | A | 0.64 | 1.785 | 6 | 0.85 | 1 | 42.330 | 0.62 | 31.08 | C |
| | | | B | 0.64 | 1.785 | | 0.85 | 1 | 42.330 | | | |
| | | | C | 0.64 | 1.785 | | 0.85 | 1 | 42.330 | | | |
| T6 60.00-40.00 | 1.65 | 3.53 | A | 0.607 | 1.8 | 6 | 0.85 | 1 | 38.878 | 0.57 | 28.32 | C |
| | | | B | 0.607 | 1.8 | | 0.85 | 1 | 38.878 | | | |
| | | | C | 0.607 | 1.8 | | 0.85 | 1 | 38.878 | | | |
| T7 40.00-20.00 | 1.57 | 3.34 | A | 0.586 | 1.814 | 5 | 0.85 | 1 | 36.741 | 0.50 | 24.98 | C |
| | | | B | 0.586 | 1.814 | | 0.85 | 1 | 36.741 | | | |
| | | | C | 0.586 | 1.814 | | 0.85 | 1 | 36.741 | | | |
| T8 20.00-5.00 | 1.09 | 2.50 | A | 0.569 | 1.827 | 5 | 0.85 | 1 | 26.348 | 0.32 | 21.20 | C |
| | | | B | 0.569 | 1.827 | | 0.85 | 1 | 26.348 | | | |
| | | | C | 0.569 | 1.827 | | 0.85 | 1 | 26.348 | | | |
| T9 5.00-0.00 | 0.32 | 0.73 | A | 0.829 | 1.84 | 5 | 0.85 | 1 | 8.894 | 0.08 | 16.10 | C |
| | | | B | 0.829 | 1.84 | | 0.85 | 1 | 8.894 | | | |
| | | | C | 0.829 | 1.84 | | 0.85 | 1 | 8.894 | | | |
| Sum Weight: | 12.42 | 30.33 | | | | | | | | 4.51 | | |

Tower Forces - Service - Wind Normal To Face

| | | |
|--|---|----------------------------------|
| tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587 | Job 17012.45 - CT11180C | Page 21 of 44 |
| | Project 150' Guyed Tower - 130 Vernon Road Bolton, CT | Date 13:20:26 04/20/17 |
| | Client T-Mobile | Designed by TJL |

| Section Elevation ft | Add Weight K | Self Weight K | F a c e | e | C _F | q _z psf | D _F | D _R | A _E ft ² | F K | w plf | Ctrl. Face |
|-------------------------|-----------------|------------------|---------|-------|----------------|-----------------------|----------------|----------------|-----------------------------------|--------|----------|------------|
| T1 150.00-140.00 | 0.09 | 0.56 | A | 0.159 | 2.737 | 11 | 1 | 1 | 3.550 | 0.16 | 15.69 | C |
| | | | B | 0.159 | 2.737 | | 1 | 1 | 3.550 | | | |
| | | | C | 0.159 | 2.737 | | 1 | 1 | 3.550 | | | |
| T2 140.00-120.00 | 0.21 | 1.00 TA 1.07 | A | 0.145 | 2.79 | 10 | 1 | 1 | 6.439 | 0.33 | 16.35 | C |
| | | | B | 0.145 | 2.79 | | 1 | 1 | 6.439 | | | |
| | | | C | 0.145 | 2.79 | | 1 | 1 | 6.439 | | | |
| T3 120.00-100.00 | 0.21 | 1.00 | A | 0.145 | 2.79 | 10 | 1 | 1 | 6.439 | 0.32 | 15.78 | C |
| | | | B | 0.145 | 2.79 | | 1 | 1 | 6.439 | | | |
| | | | C | 0.145 | 2.79 | | 1 | 1 | 6.439 | | | |
| T4 100.00-80.00 | 0.21 | 1.17 | A | 0.154 | 2.755 | 10 | 1 | 1 | 6.908 | 0.31 | 15.57 | C |
| | | | B | 0.154 | 2.755 | | 1 | 1 | 6.908 | | | |
| | | | C | 0.154 | 2.755 | | 1 | 1 | 6.908 | | | |
| T5 80.00-60.00 | 0.21 | 1.21 | A | 0.159 | 2.738 | 9 | 1 | 1 | 7.126 | 0.30 | 14.95 | C |
| | | | B | 0.159 | 2.738 | | 1 | 1 | 7.126 | | | |
| | | | C | 0.159 | 2.738 | | 1 | 1 | 7.126 | | | |
| T6 60.00-40.00 | 0.21 | 1.17 | A | 0.154 | 2.755 | 9 | 1 | 1 | 6.908 | 0.28 | 13.76 | C |
| | | | B | 0.154 | 2.755 | | 1 | 1 | 6.908 | | | |
| | | | C | 0.154 | 2.755 | | 1 | 1 | 6.908 | | | |
| T7 40.00-20.00 | 0.21 | 1.17 | A | 0.154 | 2.755 | 8 | 1 | 1 | 6.908 | 0.25 | 12.35 | C |
| | | | B | 0.154 | 2.755 | | 1 | 1 | 6.908 | | | |
| | | | C | 0.154 | 2.755 | | 1 | 1 | 6.908 | | | |
| T8 20.00-5.00 | 0.16 | 1.03 | A | 0.166 | 2.714 | 7 | 1 | 1 | 5.610 | 0.17 | 11.05 | C |
| | | | B | 0.166 | 2.714 | | 1 | 1 | 5.610 | | | |
| | | | C | 0.166 | 2.714 | | 1 | 1 | 5.610 | | | |
| T9 5.00-0.00 | 0.05 | 0.37 | A | 0.344 | 2.187 | 7 | 1 | 1 | 2.450 | 0.06 | 11.37 | C |
| | | | B | 0.344 | 2.187 | | 1 | 1 | 2.450 | | | |
| | | | C | 0.344 | 2.187 | | 1 | 1 | 2.450 | | | |
| Sum Weight: | 1.58 | 9.73 | | | | | | | | 2.15 | | |

Tower Forces - Service - Wind 45 To Face

| Section Elevation ft | Add Weight K | Self Weight K | F a c e | e | C _F | q _z psf | D _F | D _R | A _E ft ² | F K | w plf | Ctrl. Face |
|-------------------------|-----------------|------------------|---------|-------|----------------|-----------------------|----------------|----------------|-----------------------------------|--------|----------|------------|
| T1 150.00-140.00 | 0.09 | 0.56 | A | 0.159 | 2.737 | 11 | 0.825 | 1 | 3.550 | 0.16 | 15.69 | C |
| | | | B | 0.159 | 2.737 | | 0.825 | 1 | 3.550 | | | |
| | | | C | 0.159 | 2.737 | | 0.825 | 1 | 3.550 | | | |
| T2 140.00-120.00 | 0.21 | 1.00 TA 1.07 | A | 0.145 | 2.79 | 10 | 0.825 | 1 | 6.439 | 0.33 | 16.35 | C |
| | | | B | 0.145 | 2.79 | | 0.825 | 1 | 6.439 | | | |
| | | | C | 0.145 | 2.79 | | 0.825 | 1 | 6.439 | | | |
| T3 120.00-100.00 | 0.21 | 1.00 | A | 0.145 | 2.79 | 10 | 0.825 | 1 | 6.439 | 0.32 | 15.78 | C |
| | | | B | 0.145 | 2.79 | | 0.825 | 1 | 6.439 | | | |
| | | | C | 0.145 | 2.79 | | 0.825 | 1 | 6.439 | | | |
| T4 100.00-80.00 | 0.21 | 1.17 | A | 0.154 | 2.755 | 10 | 0.825 | 1 | 6.908 | 0.31 | 15.57 | C |
| | | | B | 0.154 | 2.755 | | 0.825 | 1 | 6.908 | | | |
| | | | C | 0.154 | 2.755 | | 0.825 | 1 | 6.908 | | | |
| T5 80.00-60.00 | 0.21 | 1.21 | A | 0.159 | 2.738 | 9 | 0.825 | 1 | 7.126 | 0.30 | 14.95 | C |
| | | | B | 0.159 | 2.738 | | 0.825 | 1 | 7.126 | | | |
| | | | C | 0.159 | 2.738 | | 0.825 | 1 | 7.126 | | | |
| T6 60.00-40.00 | 0.21 | 1.17 | A | 0.154 | 2.755 | 9 | 0.825 | 1 | 6.908 | 0.28 | 13.76 | C |
| | | | B | 0.154 | 2.755 | | 0.825 | 1 | 6.908 | | | |
| | | | C | 0.154 | 2.755 | | 0.825 | 1 | 6.908 | | | |
| T7 40.00-20.00 | 0.21 | 1.17 | A | 0.154 | 2.755 | 8 | 0.825 | 1 | 6.908 | 0.25 | 12.35 | C |

| | | |
|--|---|----------------------------------|
| tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587 | Job 17012.45 - CT11180C | Page 22 of 44 |
| | Project 150' Guyed Tower - 130 Vernon Road Bolton, CT | Date 13:20:26 04/20/17 |
| | Client T-Mobile | Designed by TJL |

| Section Elevation ft | Add Weight K | Self Weight K | F a c e | e | C _F | q _z psf | D _F | D _R | A _E ft ² | F K | w plf | Ctrl. Face |
|-------------------------|-----------------|------------------|---------|-------|----------------|-----------------------|----------------|----------------|-----------------------------------|--------|----------|------------|
| 40.00-20.00 | | | B | 0.154 | 2.755 | | 0.825 | 1 | 6.908 | | | |
| T8 20.00-5.00 | 0.16 | 1.03 | C | 0.154 | 2.755 | | 0.825 | 1 | 6.908 | | | |
| | | | A | 0.166 | 2.714 | 7 | 0.825 | 1 | 5.610 | 0.17 | 11.05 | C |
| T9 5.00-0.00 | 0.05 | 0.37 | B | 0.166 | 2.714 | | 0.825 | 1 | 5.610 | | | |
| | | | C | 0.166 | 2.714 | | 0.825 | 1 | 5.610 | | | |
| T9 5.00-0.00 | 0.05 | 0.37 | A | 0.344 | 2.187 | 7 | 0.825 | 1 | 2.342 | 0.06 | 11.10 | C |
| | | | B | 0.344 | 2.187 | | 0.825 | 1 | 2.342 | | | |
| T9 5.00-0.00 | 0.05 | 0.37 | C | 0.344 | 2.187 | | 0.825 | 1 | 2.342 | | | |
| | | | | | | | | | | | | |
| Sum Weight: | 1.58 | 9.73 | | | | | | | | 2.15 | | |

Tower Forces - Service - Wind 60 To Face

| Section Elevation ft | Add Weight K | Self Weight K | F a c e | e | C _F | q _z psf | D _F | D _R | A _E ft ² | F K | w plf | Ctrl. Face |
|-------------------------|-----------------|------------------|---------|-------|----------------|-----------------------|----------------|----------------|-----------------------------------|--------|----------|------------|
| T1 150.00-140.00 | 0.09 | 0.56 | A | 0.159 | 2.737 | 11 | 0.8 | 1 | 3.550 | 0.16 | 15.69 | C |
| T1 150.00-140.00 | 0.09 | 0.56 | B | 0.159 | 2.737 | | 0.8 | 1 | 3.550 | | | |
| | | | C | 0.159 | 2.737 | | 0.8 | 1 | 3.550 | | | |
| | | | A | 0.145 | 2.79 | 10 | 0.8 | 1 | 6.439 | 0.33 | 16.35 | C |
| T2 140.00-120.00 | 0.21 | 1.00 | B | 0.145 | 2.79 | | 0.8 | 1 | 6.439 | | | |
| | | | C | 0.145 | 2.79 | | 0.8 | 1 | 6.439 | | | |
| T3 120.00-100.00 | 0.21 | 1.00 | A | 0.145 | 2.79 | 10 | 0.8 | 1 | 6.439 | 0.32 | 15.78 | C |
| | | | B | 0.145 | 2.79 | | 0.8 | 1 | 6.439 | | | |
| T4 100.00-80.00 | 0.21 | 1.17 | C | 0.145 | 2.79 | | 0.8 | 1 | 6.439 | | | |
| | | | A | 0.154 | 2.755 | 10 | 0.8 | 1 | 6.908 | 0.31 | 15.57 | C |
| T4 100.00-80.00 | 0.21 | 1.17 | B | 0.154 | 2.755 | | 0.8 | 1 | 6.908 | | | |
| | | | C | 0.154 | 2.755 | | 0.8 | 1 | 6.908 | | | |
| | | | A | 0.159 | 2.738 | 9 | 0.8 | 1 | 7.126 | 0.30 | 14.95 | C |
| T5 80.00-60.00 | 0.21 | 1.21 | B | 0.159 | 2.738 | | 0.8 | 1 | 7.126 | | | |
| | | | C | 0.159 | 2.738 | | 0.8 | 1 | 7.126 | | | |
| T6 60.00-40.00 | 0.21 | 1.17 | A | 0.154 | 2.755 | 9 | 0.8 | 1 | 6.908 | 0.28 | 13.76 | C |
| | | | B | 0.154 | 2.755 | | 0.8 | 1 | 6.908 | | | |
| T7 40.00-20.00 | 0.21 | 1.17 | C | 0.154 | 2.755 | | 0.8 | 1 | 6.908 | | | |
| | | | A | 0.154 | 2.755 | 8 | 0.8 | 1 | 6.908 | 0.25 | 12.35 | C |
| T8 20.00-5.00 | 0.16 | 1.03 | B | 0.154 | 2.755 | | 0.8 | 1 | 6.908 | | | |
| | | | C | 0.154 | 2.755 | | 0.8 | 1 | 6.908 | | | |
| | | | A | 0.166 | 2.714 | 7 | 0.8 | 1 | 5.610 | 0.17 | 11.05 | C |
| T9 5.00-0.00 | 0.05 | 0.37 | B | 0.166 | 2.714 | | 0.8 | 1 | 5.610 | | | |
| | | | C | 0.166 | 2.714 | | 0.8 | 1 | 5.610 | | | |
| T9 5.00-0.00 | 0.05 | 0.37 | A | 0.344 | 2.187 | 7 | 0.8 | 1 | 2.326 | 0.06 | 11.06 | C |
| | | | B | 0.344 | 2.187 | | 0.8 | 1 | 2.326 | | | |
| T9 5.00-0.00 | 0.05 | 0.37 | C | 0.344 | 2.187 | | 0.8 | 1 | 2.326 | | | |
| | | | | | | | | | | | | |
| Sum Weight: | 1.58 | 9.73 | | | | | | | | 2.15 | | |

Tower Forces - Service - Wind 90 To Face

| | | |
|--|---|----------------------------------|
| tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587 | Job 17012.45 - CT11180C | Page 23 of 44 |
| | Project 150' Guyed Tower - 130 Vernon Road Bolton, CT | Date 13:20:26 04/20/17 |
| | Client T-Mobile | Designed by TJJ |

| Section Elevation ft | Add Weight K | Self Weight K | F a c e | e | C _F | q _z psf | D _F | D _R | A _E ft ² | F K | w plf | Ctrl. Face |
|-------------------------|-----------------|------------------|---------|-------|----------------|-----------------------|----------------|----------------|-----------------------------------|--------|----------|------------|
| T1 150.00-140.00 | 0.09 | 0.56 | A | 0.159 | 2.737 | 11 | 0.85 | 1 | 3.550 | 0.16 | 15.69 | C |
| | | | B | 0.159 | 2.737 | | 0.85 | 1 | 3.550 | | | |
| | | | C | 0.159 | 2.737 | | 0.85 | 1 | 3.550 | | | |
| T2 140.00-120.00 | 0.21 | 1.00 | A | 0.145 | 2.79 | 10 | 0.85 | 1 | 6.439 | 0.33 | 16.35 | C |
| | | TA 1.07 | B | 0.145 | 2.79 | | 0.85 | 1 | 6.439 | | | |
| | | | C | 0.145 | 2.79 | | 0.85 | 1 | 6.439 | | | |
| T3 120.00-100.00 | 0.21 | 1.00 | A | 0.145 | 2.79 | 10 | 0.85 | 1 | 6.439 | 0.32 | 15.78 | C |
| | | | B | 0.145 | 2.79 | | 0.85 | 1 | 6.439 | | | |
| | | | C | 0.145 | 2.79 | | 0.85 | 1 | 6.439 | | | |
| T4 100.00-80.00 | 0.21 | 1.17 | A | 0.154 | 2.755 | 10 | 0.85 | 1 | 6.908 | 0.31 | 15.57 | C |
| | | | B | 0.154 | 2.755 | | 0.85 | 1 | 6.908 | | | |
| | | | C | 0.154 | 2.755 | | 0.85 | 1 | 6.908 | | | |
| T5 80.00-60.00 | 0.21 | 1.21 | A | 0.159 | 2.738 | 9 | 0.85 | 1 | 7.126 | 0.30 | 14.95 | C |
| | | | B | 0.159 | 2.738 | | 0.85 | 1 | 7.126 | | | |
| | | | C | 0.159 | 2.738 | | 0.85 | 1 | 7.126 | | | |
| T6 60.00-40.00 | 0.21 | 1.17 | A | 0.154 | 2.755 | 9 | 0.85 | 1 | 6.908 | 0.28 | 13.76 | C |
| | | | B | 0.154 | 2.755 | | 0.85 | 1 | 6.908 | | | |
| | | | C | 0.154 | 2.755 | | 0.85 | 1 | 6.908 | | | |
| T7 40.00-20.00 | 0.21 | 1.17 | A | 0.154 | 2.755 | 8 | 0.85 | 1 | 6.908 | 0.25 | 12.35 | C |
| | | | B | 0.154 | 2.755 | | 0.85 | 1 | 6.908 | | | |
| | | | C | 0.154 | 2.755 | | 0.85 | 1 | 6.908 | | | |
| T8 20.00-5.00 | 0.16 | 1.03 | A | 0.166 | 2.714 | 7 | 0.85 | 1 | 5.610 | 0.17 | 11.05 | C |
| | | | B | 0.166 | 2.714 | | 0.85 | 1 | 5.610 | | | |
| | | | C | 0.166 | 2.714 | | 0.85 | 1 | 5.610 | | | |
| T9 5.00-0.00 | 0.05 | 0.37 | A | 0.344 | 2.187 | 7 | 0.85 | 1 | 2.357 | 0.06 | 11.14 | C |
| | | | B | 0.344 | 2.187 | | 0.85 | 1 | 2.357 | | | |
| | | | C | 0.344 | 2.187 | | 0.85 | 1 | 2.357 | | | |
| Sum Weight: | 1.58 | 9.73 | | | | | | | | 2.15 | | |

Force Totals (Does not include forces on guys)

| Load Case | Vertical Forces K | Sum of Forces X K | Sum of Forces Z K | Sum of Torques kip-ft |
|--------------------------|----------------------|-------------------------|-------------------------|--------------------------|
| Leg Weight | 5.88 | | | |
| Bracing Weight | 3.85 | | | |
| Total Member Self-Weight | 9.73 | | | |
| Guy Weight | 1.76 | | | |
| Total Weight | 16.19 | | | |
| Wind 0 deg - No Ice | | 0.06 | -9.24 | -0.79 |
| Wind 30 deg - No Ice | | 4.64 | -8.03 | -0.66 |
| Wind 45 deg - No Ice | | 6.53 | -6.57 | -0.53 |
| Wind 60 deg - No Ice | | 7.97 | -4.67 | -0.36 |
| Wind 90 deg - No Ice | | 9.17 | -0.06 | 0.05 |
| Wind 120 deg - No Ice | | 7.92 | 4.57 | 0.44 |
| Wind 135 deg - No Ice | | 6.45 | 6.49 | 0.59 |
| Wind 150 deg - No Ice | | 4.54 | 7.97 | 0.71 |
| Wind 180 deg - No Ice | | -0.06 | 9.24 | 0.79 |
| Wind 210 deg - No Ice | | -4.64 | 8.03 | 0.66 |
| Wind 225 deg - No Ice | | -6.53 | 6.57 | 0.53 |
| Wind 240 deg - No Ice | | -7.98 | 4.67 | 0.36 |
| Wind 270 deg - No Ice | | -9.17 | 0.06 | -0.05 |
| Wind 300 deg - No Ice | | -7.91 | -4.57 | -0.44 |

| | | |
|--|---|----------------------------------|
| tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587 | Job 17012.45 - CT11180C | Page 24 of 44 |
| | Project 150' Guyed Tower - 130 Vernon Road Bolton, CT | Date 13:20:26 04/20/17 |
| | Client T-Mobile | Designed by TJL |

| Load Case | Vertical Forces K | Sum of Forces X K | Sum of Forces Z K | Sum of Torques kip-ft |
|------------------------|----------------------|-------------------------|-------------------------|--------------------------|
| Wind 315 deg - No Ice | | -6.45 | -6.49 | -0.59 |
| Wind 330 deg - No Ice | | -4.54 | -7.97 | -0.71 |
| Member Ice | 20.60 | | | |
| Guy Ice | 15.05 | | | |
| Total Weight Ice | 70.15 | | | |
| Wind 0 deg - Ice | | 0.02 | -6.37 | -0.34 |
| Wind 30 deg - Ice | | 3.19 | -5.52 | -0.31 |
| Wind 45 deg - Ice | | 4.50 | -4.51 | -0.26 |
| Wind 60 deg - Ice | | 5.50 | -3.20 | -0.19 |
| Wind 90 deg - Ice | | 6.35 | -0.02 | -0.02 |
| Wind 120 deg - Ice | | 5.49 | 3.17 | 0.15 |
| Wind 135 deg - Ice | | 4.48 | 4.49 | 0.22 |
| Wind 150 deg - Ice | | 3.16 | 5.50 | 0.28 |
| Wind 180 deg - Ice | | -0.02 | 6.36 | 0.34 |
| Wind 210 deg - Ice | | -3.19 | 5.52 | 0.31 |
| Wind 225 deg - Ice | | -4.50 | 4.51 | 0.26 |
| Wind 240 deg - Ice | | -5.50 | 3.20 | 0.19 |
| Wind 270 deg - Ice | | -6.35 | 0.02 | 0.02 |
| Wind 300 deg - Ice | | -5.49 | -3.17 | -0.15 |
| Wind 315 deg - Ice | | -4.48 | -4.49 | -0.22 |
| Wind 330 deg - Ice | | -3.16 | -5.50 | -0.28 |
| Total Weight | 16.19 | | | |
| Wind 0 deg - Service | | 0.02 | -3.54 | -0.30 |
| Wind 30 deg - Service | | 1.77 | -3.07 | -0.25 |
| Wind 45 deg - Service | | 2.50 | -2.52 | -0.20 |
| Wind 60 deg - Service | | 3.05 | -1.79 | -0.14 |
| Wind 90 deg - Service | | 3.51 | -0.02 | 0.02 |
| Wind 120 deg - Service | | 3.03 | 1.75 | 0.17 |
| Wind 135 deg - Service | | 2.47 | 2.48 | 0.23 |
| Wind 150 deg - Service | | 1.74 | 3.05 | 0.27 |
| Wind 180 deg - Service | | -0.02 | 3.53 | 0.30 |
| Wind 210 deg - Service | | -1.77 | 3.07 | 0.25 |
| Wind 225 deg - Service | | -2.50 | 2.52 | 0.20 |
| Wind 240 deg - Service | | -3.05 | 1.79 | 0.14 |
| Wind 270 deg - Service | | -3.51 | 0.02 | -0.02 |
| Wind 300 deg - Service | | -3.03 | -1.75 | -0.17 |
| Wind 315 deg - Service | | -2.47 | -2.48 | -0.23 |
| Wind 330 deg - Service | | -1.74 | -3.05 | -0.27 |

Load Combinations

| Comb. No. | Description |
|-----------|--|
| 1 | Dead Only |
| 2 | 1.2 Dead+1.6 Wind 0 deg - No Ice+1.0 Guy |
| 3 | 1.2 Dead+1.6 Wind 30 deg - No Ice+1.0 Guy |
| 4 | 1.2 Dead+1.6 Wind 45 deg - No Ice+1.0 Guy |
| 5 | 1.2 Dead+1.6 Wind 60 deg - No Ice+1.0 Guy |
| 6 | 1.2 Dead+1.6 Wind 90 deg - No Ice+1.0 Guy |
| 7 | 1.2 Dead+1.6 Wind 120 deg - No Ice+1.0 Guy |
| 8 | 1.2 Dead+1.6 Wind 135 deg - No Ice+1.0 Guy |
| 9 | 1.2 Dead+1.6 Wind 150 deg - No Ice+1.0 Guy |
| 10 | 1.2 Dead+1.6 Wind 180 deg - No Ice+1.0 Guy |
| 11 | 1.2 Dead+1.6 Wind 210 deg - No Ice+1.0 Guy |

| | | |
|--|---|----------------------------------|
| tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587 | Job 17012.45 - CT11180C | Page 25 of 44 |
| | Project 150' Guyed Tower - 130 Vernon Road Bolton, CT | Date 13:20:26 04/20/17 |
| | Client T-Mobile | Designed by TJL |

| Comb. No. | Description |
|-----------|--|
| 12 | 1.2 Dead+1.6 Wind 225 deg - No Ice+1.0 Guy |
| 13 | 1.2 Dead+1.6 Wind 240 deg - No Ice+1.0 Guy |
| 14 | 1.2 Dead+1.6 Wind 270 deg - No Ice+1.0 Guy |
| 15 | 1.2 Dead+1.6 Wind 300 deg - No Ice+1.0 Guy |
| 16 | 1.2 Dead+1.6 Wind 315 deg - No Ice+1.0 Guy |
| 17 | 1.2 Dead+1.6 Wind 330 deg - No Ice+1.0 Guy |
| 18 | 1.2 Dead+1.0 Ice+1.0 Temp+Guy |
| 19 | 1.2 Dead+1.0 Wind 0 deg+1.0 Ice+1.0 Temp+1.0 Guy |
| 20 | 1.2 Dead+1.0 Wind 30 deg+1.0 Ice+1.0 Temp+1.0 Guy |
| 21 | 1.2 Dead+1.0 Wind 45 deg+1.0 Ice+1.0 Temp+1.0 Guy |
| 22 | 1.2 Dead+1.0 Wind 60 deg+1.0 Ice+1.0 Temp+1.0 Guy |
| 23 | 1.2 Dead+1.0 Wind 90 deg+1.0 Ice+1.0 Temp+1.0 Guy |
| 24 | 1.2 Dead+1.0 Wind 120 deg+1.0 Ice+1.0 Temp+1.0 Guy |
| 25 | 1.2 Dead+1.0 Wind 135 deg+1.0 Ice+1.0 Temp+1.0 Guy |
| 26 | 1.2 Dead+1.0 Wind 150 deg+1.0 Ice+1.0 Temp+1.0 Guy |
| 27 | 1.2 Dead+1.0 Wind 180 deg+1.0 Ice+1.0 Temp+1.0 Guy |
| 28 | 1.2 Dead+1.0 Wind 210 deg+1.0 Ice+1.0 Temp+1.0 Guy |
| 29 | 1.2 Dead+1.0 Wind 225 deg+1.0 Ice+1.0 Temp+1.0 Guy |
| 30 | 1.2 Dead+1.0 Wind 240 deg+1.0 Ice+1.0 Temp+1.0 Guy |
| 31 | 1.2 Dead+1.0 Wind 270 deg+1.0 Ice+1.0 Temp+1.0 Guy |
| 32 | 1.2 Dead+1.0 Wind 300 deg+1.0 Ice+1.0 Temp+1.0 Guy |
| 33 | 1.2 Dead+1.0 Wind 315 deg+1.0 Ice+1.0 Temp+1.0 Guy |
| 34 | 1.2 Dead+1.0 Wind 330 deg+1.0 Ice+1.0 Temp+1.0 Guy |
| 35 | Dead+Wind 0 deg - Service+Guy |
| 36 | Dead+Wind 30 deg - Service+Guy |
| 37 | Dead+Wind 45 deg - Service+Guy |
| 38 | Dead+Wind 60 deg - Service+Guy |
| 39 | Dead+Wind 90 deg - Service+Guy |
| 40 | Dead+Wind 120 deg - Service+Guy |
| 41 | Dead+Wind 135 deg - Service+Guy |
| 42 | Dead+Wind 150 deg - Service+Guy |
| 43 | Dead+Wind 180 deg - Service+Guy |
| 44 | Dead+Wind 210 deg - Service+Guy |
| 45 | Dead+Wind 225 deg - Service+Guy |
| 46 | Dead+Wind 240 deg - Service+Guy |
| 47 | Dead+Wind 270 deg - Service+Guy |
| 48 | Dead+Wind 300 deg - Service+Guy |
| 49 | Dead+Wind 315 deg - Service+Guy |
| 50 | Dead+Wind 330 deg - Service+Guy |

Maximum Member Forces

| Section No. | Elevation ft | Component Type | Condition | Gov. Load Comb. | Axial K | Major Axis Moment kip-ft | Minor Axis Moment kip-ft |
|-------------|--------------|----------------|------------------|-----------------|---------|--------------------------|--------------------------|
| T1 | 150 - 140 | Leg | Max Tension | 5 | 3.17 | 0.02 | -0.01 |
| | | | Max. Compression | 24 | -16.63 | -0.24 | -0.10 |
| | | | Max. Mx | 6 | -0.62 | -0.51 | 0.11 |
| | | | Max. My | 2 | -10.87 | -0.01 | 0.58 |
| | | | Max. Vy | 5 | -0.98 | -0.49 | 0.30 |
| | | Diagonal | Max. Vx | 2 | 1.09 | -0.01 | 0.58 |
| | | | Max Tension | 8 | 1.33 | 0.00 | 0.00 |
| | | | Max. Compression | 8 | -1.35 | 0.00 | 0.00 |
| | | | Max. Mx | 22 | -0.04 | -0.01 | 0.00 |
| | | | Max. My | 4 | -1.33 | -0.00 | 0.00 |
| | | Top Girt | Max. Vy | 27 | 0.01 | -0.01 | 0.00 |
| | | | Max. Vx | 4 | 0.00 | 0.00 | 0.00 |
| | | | Max Tension | 15 | 0.04 | 0.00 | 0.00 |
| | | | Max. Compression | 7 | -0.08 | 0.00 | 0.00 |

| | | |
|--|---|----------------------------------|
| tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587 | Job 17012.45 - CT11180C | Page 26 of 44 |
| | Project 150' Guyed Tower - 130 Vernon Road Bolton, CT | Date 13:20:26 04/20/17 |
| | Client T-Mobile | Designed by TJL |

| Section No. | Elevation ft | Component Type | Condition | Gov. Load Comb. | Axial K | Major Axis Moment kip-ft | Minor Axis Moment kip-ft | |
|------------------|----------------|------------------|------------------|------------------|---------|--------------------------|--------------------------|-------|
| T2 | 140 - 120 | Bottom Girt | Max. Mx | 29 | -0.07 | 0.02 | 0.00 | |
| | | | Max. Vy | 29 | 0.02 | 0.00 | 0.00 | |
| | | | Max Tension | 2 | 0.43 | 0.00 | 0.00 | |
| | | | Max. Compression | 5 | -0.30 | 0.00 | 0.00 | |
| | | | Max. Mx | 29 | 0.31 | 0.02 | 0.00 | |
| | | | Max. Vy | 29 | 0.02 | 0.00 | 0.00 | |
| | | Top Guy Pull-Off | Max Tension | 10 | 4.48 | 0.00 | 0.00 | |
| | | | Max. Compression | 2 | -2.82 | 0.00 | 0.00 | |
| | | | Max. Mx | 29 | 0.32 | 0.03 | 0.00 | |
| | | | Max. My | 17 | 0.79 | 0.00 | -0.00 | |
| | | | Max. Vy | 29 | -0.03 | 0.00 | 0.00 | |
| | | | Max. Vx | 17 | 0.00 | 0.00 | 0.00 | |
| | | Leg | Max Tension | 2 | 1.00 | 0.06 | 0.11 | |
| | | | Max. Compression | 22 | -28.88 | 0.03 | -0.02 | |
| | | | Max. Mx | 5 | -2.87 | 0.48 | -0.29 | |
| | | | Max. My | 10 | -1.72 | 0.00 | 0.51 | |
| | | | Max. Vy | 5 | -0.97 | -0.01 | 0.01 | |
| | | | Max. Vx | 2 | 1.09 | -0.00 | 0.04 | |
| | | | Diagonal | Max Tension | 17 | 2.14 | 0.00 | 0.00 |
| | | | | Max. Compression | 9 | -2.48 | 0.00 | 0.00 |
| | | | | Max. Mx | 19 | -1.28 | -0.01 | 0.00 |
| | | | | Max. My | 2 | -1.74 | 0.00 | 0.02 |
| | | | | Max. Vy | 19 | 0.01 | -0.01 | -0.00 |
| | | | | Max. Vx | 2 | 0.01 | 0.00 | 0.00 |
| | | | Top Girt | Max Tension | 5 | 0.90 | 0.00 | 0.00 |
| | | | | Max. Compression | 2 | -1.06 | 0.00 | 0.00 |
| | | | | Max. Mx | 29 | -0.63 | 0.02 | 0.00 |
| | | | Bottom Girt | Max. Vy | 29 | -0.02 | 0.00 | 0.00 |
| | | | | Max Tension | 24 | 0.22 | 0.00 | 0.00 |
| | | | | Max. Compression | 10 | -0.10 | 0.00 | 0.00 |
| | | Guy A | Max. Mx | 29 | 0.21 | 0.02 | 0.00 | |
| | | | Max. Vy | 29 | -0.02 | 0.00 | 0.00 | |
| | | | Bottom Tension | 27 | 10.16 | | | |
| | | | Top Tension | 27 | 11.33 | | | |
| | | | Top Cable Vert | 27 | 7.43 | | | |
| | | | Top Cable Norm | 27 | 8.55 | | | |
| | | | Top Cable Tan | 27 | 0.01 | | | |
| | | | Bot Cable Vert | 27 | -5.28 | | | |
| | | | Bot Cable Norm | 27 | 8.69 | | | |
| | | | Bot Cable Tan | 27 | 0.01 | | | |
| | | | Guy B | Bottom Tension | 32 | 10.59 | | |
| | | | | Top Tension | 32 | 11.87 | | |
| Top Cable Vert | 32 | | | 8.27 | | | | |
| Top Cable Norm | 32 | | | 8.51 | | | | |
| Top Cable Tan | 32 | | | 0.01 | | | | |
| Bot Cable Vert | 32 | -6.06 | | | | | | |
| Bot Cable Norm | 32 | 8.68 | | | | | | |
| Bot Cable Tan | 32 | 0.00 | | | | | | |
| Guy C | Bottom Tension | 22 | | 10.69 | | | | |
| | Top Tension | 22 | 11.99 | | | | | |
| | Top Cable Vert | 22 | 8.45 | | | | | |
| | Top Cable Norm | 22 | 8.51 | | | | | |
| | Top Cable Tan | 22 | 0.01 | | | | | |
| | Bot Cable Vert | 22 | -6.23 | | | | | |
| | Bot Cable Norm | 22 | 8.69 | | | | | |
| | Bot Cable Tan | 22 | 0.00 | | | | | |
| | Torque Arm Top | Max Tension | 27 | 10.46 | 0.00 | 0.00 | | |
| Max. Compression | | 7 | -0.13 | 0.00 | 0.00 | | | |
| Max. Mx | | 23 | 7.69 | 0.22 | 0.00 | | | |
| Max. My | | 17 | 0.86 | 0.00 | -0.00 | | | |
| Max. Vy | | 23 | -0.12 | 0.00 | 0.00 | | | |

| | | |
|--|---|----------------------------------|
| tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587 | Job 17012.45 - CT11180C | Page 27 of 44 |
| | Project 150' Guyed Tower - 130 Vernon Road Bolton, CT | Date 13:20:26 04/20/17 |
| | Client T-Mobile | Designed by TJJ |

| Section No. | Elevation ft | Component Type | Condition | Gov. Load Comb. | Axial K | Major Axis Moment kip-ft | Minor Axis Moment kip-ft | |
|-------------|------------------|-------------------|------------------|------------------|---------|--------------------------|--------------------------|-------|
| T3 | 120 - 100 | Torque Arm Bottom | Max. Vx | 17 | 0.00 | 0.00 | 0.00 | |
| | | | Max Tension | 3 | 4.07 | 0.00 | 0.00 | |
| | | | Max. Compression | 4 | -7.30 | 0.00 | 0.00 | |
| | | | Max. Mx | 24 | -4.52 | 0.20 | 0.00 | |
| | | | Max. My | 26 | -5.81 | 0.00 | -0.00 | |
| | | | Max. Vy | 24 | 0.12 | 0.00 | 0.00 | |
| | | Leg | Max. Vx | 26 | 0.00 | 0.00 | 0.00 | |
| | | | Max Tension | 2 | 1.61 | -0.00 | -0.01 | |
| | | | Max. Compression | 22 | -30.80 | -0.05 | 0.03 | |
| | | | Max. Mx | 6 | -15.12 | 0.15 | -0.04 | |
| | | | Max. My | 3 | -15.18 | 0.08 | -0.17 | |
| | | | Max. Vy | 6 | 0.33 | -0.04 | -0.01 | |
| | | | Diagonal | Max. Vx | 3 | -0.39 | 0.00 | 0.03 |
| | | | | Max Tension | 3 | 0.55 | 0.00 | 0.00 |
| | | | | Max. Compression | 3 | -0.65 | 0.00 | 0.00 |
| | | | | Max. Mx | 20 | -0.15 | -0.01 | 0.00 |
| | | | | Max. My | 3 | -0.65 | -0.00 | -0.00 |
| | | | | Max. Vy | 20 | 0.01 | -0.01 | 0.00 |
| | | | Top Girt | Max. Vx | 3 | -0.00 | 0.00 | 0.00 |
| | | | | Max Tension | 27 | 0.16 | 0.00 | 0.00 |
| | | | | Max. Compression | 2 | -0.04 | 0.00 | 0.00 |
| Max. Mx | 29 | 0.01 | | 0.02 | 0.00 | | | |
| Max. Vy | 29 | -0.02 | | 0.00 | 0.00 | | | |
| Bottom Girt | Max Tension | 5 | | 0.18 | 0.00 | 0.00 | | |
| | Max. Compression | 12 | -0.07 | 0.00 | 0.00 | | | |
| | Max. Mx | 25 | 0.13 | 0.02 | 0.00 | | | |
| | Max. Vy | 25 | -0.02 | 0.00 | 0.00 | | | |
| | T4 | 100 - 80 | Leg | Max Tension | 1 | 0.00 | 0.00 | 0.00 |
| | | | | Max. Compression | 22 | -30.67 | -0.03 | 0.03 |
| Max. Mx | | | | 6 | -7.02 | 0.42 | -0.07 | |
| Max. My | | | | 10 | -7.79 | -0.03 | 0.44 | |
| Max. Vy | | | | 6 | 0.83 | 0.01 | -0.00 | |
| Max. Vx | | | | 10 | 0.86 | -0.00 | 0.01 | |
| Diagonal | | | Max Tension | 3 | 1.19 | 0.00 | 0.00 | |
| | | | Max. Compression | 3 | -1.30 | 0.00 | 0.00 | |
| | | | Max. Mx | 19 | -0.10 | -0.01 | 0.00 | |
| | | | Max. My | 3 | -1.29 | -0.00 | -0.00 | |
| | | | Max. Vy | 19 | 0.01 | -0.01 | 0.00 | |
| | | | Max. Vx | 3 | -0.00 | 0.00 | 0.00 | |
| Top Girt | | | Max Tension | 12 | 0.23 | 0.00 | 0.00 | |
| | | | Max. Compression | 5 | -0.16 | 0.00 | 0.00 | |
| | | | Max. Mx | 25 | 0.17 | 0.02 | 0.00 | |
| | Max. Vy | 25 | -0.02 | 0.00 | 0.00 | | | |
| | Bottom Girt | Max Tension | 5 | 0.43 | 0.00 | 0.00 | | |
| | | Max. Compression | 13 | -0.29 | 0.00 | 0.00 | | |
| Max. Mx | | 31 | 0.29 | 0.02 | 0.00 | | | |
| Max. My | | 34 | 0.14 | 0.00 | -0.00 | | | |
| Max. Vy | | 31 | -0.02 | 0.00 | 0.00 | | | |
| Max. Vx | | 34 | 0.00 | 0.00 | 0.00 | | | |
| T5 | | 80 - 60 | Leg | Max Tension | 1 | 0.00 | 0.00 | 0.00 |
| | | | | Max. Compression | 20 | -35.62 | 0.04 | -0.03 |
| | | | | Max. Mx | 6 | -13.04 | -0.42 | -0.07 |
| | Max. My | | | 10 | -5.82 | 0.03 | -0.42 | |
| | Max. Vy | | | 6 | 0.83 | -0.41 | 0.06 | |
| | Max. Vx | | | 10 | 0.86 | 0.03 | -0.42 | |
| | Diagonal | | Max Tension | 3 | 1.28 | 0.00 | 0.00 | |
| | | | Max. Compression | 3 | -1.38 | 0.00 | 0.00 | |
| | | | Max. Mx | 25 | 0.09 | -0.01 | -0.00 | |
| | | | Max. My | 3 | -1.38 | -0.00 | -0.00 | |
| | | | Max. Vy | 25 | 0.01 | -0.01 | -0.00 | |
| | | | Max. Vx | 3 | -0.00 | 0.00 | 0.00 | |

| | | | | |
|--|----------------|---|--------------------|-------------------|
| tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587 | Job | 17012.45 - CT11180C | Page | 28 of 44 |
| | Project | 150' Guyed Tower - 130 Vernon Road Bolton, CT | Date | 13:20:26 04/20/17 |
| | Client | T-Mobile | Designed by | TJL |

| Section No. | Elevation ft | Component Type | Condition | Gov. Load Comb. | Axial K | Major Axis Moment kip-ft | Minor Axis Moment kip-ft | |
|------------------|------------------|------------------|------------------|------------------|----------------|--------------------------|--------------------------|-------|
| T6 | 60 - 40 | Top Girt | Max Tension | 13 | 0.40 | 0.00 | 0.00 | |
| | | | Max. Compression | 5 | -0.30 | 0.00 | 0.00 | |
| | | | Max. Mx | 31 | -0.02 | 0.02 | 0.00 | |
| | | | Max. My | 34 | 0.13 | 0.00 | -0.00 | |
| | | | Max. Vy | 31 | -0.02 | 0.00 | 0.00 | |
| | | | Max. Vx | 34 | 0.00 | 0.00 | 0.00 | |
| | | | Bottom Girt | Max Tension | 13 | 0.36 | 0.00 | 0.00 |
| | | | | Max. Compression | 10 | -0.21 | 0.00 | 0.00 |
| | | | | Max. Mx | 31 | 0.09 | 0.02 | 0.00 |
| | | | | Max. My | 34 | 0.20 | 0.00 | -0.00 |
| | | | | Max. Vy | 31 | -0.02 | 0.00 | 0.00 |
| | | | | Max. Vx | 34 | 0.00 | 0.00 | 0.00 |
| | | | | Guy A | Bottom Tension | 27 | 11.88 | |
| | | | Top Tension | | 27 | 12.50 | | |
| | | | Top Cable Vert | | 27 | 5.42 | | |
| | | Top Cable Norm | 27 | | 11.26 | | | |
| | | Top Cable Tan | 27 | | 0.00 | | | |
| | | Bot Cable Vert | 27 | | -3.70 | | | |
| | | Bot Cable Norm | 27 | | 11.29 | | | |
| | | Bot Cable Tan | 27 | | 0.00 | | | |
| | | Guy B | Bottom Tension | | 32 | 12.27 | | |
| | | | Top Tension | | 32 | 12.99 | | |
| | | | Top Cable Vert | 32 | 6.48 | | | |
| | | | Top Cable Norm | 32 | 11.25 | | | |
| | | | Top Cable Tan | 32 | 0.00 | | | |
| | | | Bot Cable Vert | 32 | -4.80 | | | |
| | | | Bot Cable Norm | 32 | 11.29 | | | |
| | | Guy C | Bottom Tension | 22 | 12.44 | | | |
| | | | Top Tension | 22 | 13.18 | | | |
| | | | Top Cable Vert | 22 | 6.73 | | | |
| | | | Top Cable Norm | 22 | 11.33 | | | |
| | | | Top Cable Tan | 22 | 0.00 | | | |
| | | | Bot Cable Vert | 22 | -5.06 | | | |
| | | | Bot Cable Norm | 22 | 11.37 | | | |
| | | Top Guy Pull-Off | Max Tension | 19 | 5.91 | 0.00 | 0.00 | |
| | | | Max. Compression | 1 | 0.00 | 0.00 | 0.00 | |
| | | | Max. Mx | 31 | 4.73 | 0.02 | 0.00 | |
| | | | Max. My | 3 | 2.75 | 0.00 | -0.00 | |
| | | | Max. Vy | 31 | 0.03 | 0.00 | 0.00 | |
| | | | Max. Vx | 3 | 0.00 | 0.00 | 0.00 | |
| | | | Leg | Max Tension | 1 | 0.00 | 0.00 | 0.00 |
| | | Max. Compression | | 22 | -39.71 | 0.05 | -0.03 | |
| Max. Mx | 6 | -11.48 | | 0.36 | -0.03 | | | |
| Max. My | 10 | -10.19 | | 0.02 | 0.37 | | | |
| Max. Vy | 6 | -0.69 | | 0.01 | -0.01 | | | |
| Max. Vx | 10 | -0.73 | | -0.00 | 0.01 | | | |
| Diagonal | Max Tension | 6 | | 0.85 | 0.00 | 0.00 | | |
| | Max. Compression | 6 | | -0.99 | 0.00 | 0.00 | | |
| | Max. Mx | 20 | | -0.09 | -0.01 | 0.00 | | |
| | Max. My | 6 | | -0.99 | -0.00 | -0.00 | | |
| | Max. Vy | 20 | | 0.01 | -0.01 | 0.00 | | |
| | Max. Vx | 6 | | 0.00 | 0.00 | 0.00 | | |
| | Top Girt | Max Tension | | 10 | 0.36 | 0.00 | 0.00 | |
| Max. Compression | | 12 | | -0.22 | 0.00 | 0.00 | | |
| Max. Mx | | 31 | | 0.24 | 0.02 | 0.00 | | |
| Max. My | | 20 | 0.13 | 0.00 | -0.00 | | | |
| Max. Vy | | 31 | 0.02 | 0.00 | 0.00 | | | |
| Max. Vx | | 20 | -0.00 | 0.00 | 0.00 | | | |
| Bottom Girt | | Max Tension | 24 | 0.23 | 0.00 | 0.00 | | |

| | | |
|--|---|----------------------------------|
| tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587 | Job 17012.45 - CT11180C | Page 29 of 44 |
| | Project 150' Guyed Tower - 130 Vernon Road Bolton, CT | Date 13:20:26 04/20/17 |
| | Client T-Mobile | Designed by TJL |

| Section No. | Elevation ft | Component Type | Condition | Gov. Load Comb. | Axial K | Major Axis Moment kip-ft | Minor Axis Moment kip-ft | |
|-------------|------------------|----------------|------------------|------------------|---------|--------------------------|--------------------------|-------|
| T7 | 40 - 20 | Leg | Max. Compression | 10 | -0.05 | 0.00 | 0.00 | |
| | | | Max. Mx | 29 | 0.22 | 0.02 | 0.00 | |
| | | | Max. My | 20 | 0.21 | 0.00 | -0.00 | |
| | | | Max. Vy | 29 | 0.02 | 0.00 | 0.00 | |
| | | | Max. Vx | 20 | -0.00 | 0.00 | 0.00 | |
| | | | Max Tension | 1 | 0.00 | 0.00 | 0.00 | |
| | | | Max. Compression | 22 | -40.56 | -0.07 | 0.04 | |
| | | | Max. Mx | 6 | -17.95 | 0.15 | -0.01 | |
| | | | Max. My | 10 | -18.27 | 0.01 | 0.15 | |
| | | | Max. Vy | 14 | 0.25 | 0.01 | -0.01 | |
| | | | Max. Vx | 10 | -0.25 | -0.00 | 0.03 | |
| | | | Max Tension | 34 | 0.31 | 0.00 | 0.00 | |
| | | Diagonal | Max. Compression | 34 | -0.47 | 0.00 | 0.00 | |
| | | | Max. Mx | 20 | -0.24 | -0.01 | 0.00 | |
| | | | Max. My | 6 | -0.39 | -0.00 | -0.00 | |
| | | | Max. Vy | 19 | 0.01 | -0.01 | 0.00 | |
| | | | Max. Vx | 10 | -0.00 | 0.00 | 0.00 | |
| | | | Max Tension | 19 | 0.20 | 0.00 | 0.00 | |
| | | | Top Girt | Max. Compression | 14 | -0.01 | 0.00 | 0.00 |
| | | | | Max. Mx | 29 | 0.17 | 0.01 | 0.00 |
| | | | | Max. My | 20 | 0.14 | 0.00 | -0.00 |
| | | | | Max. Vy | 29 | -0.02 | 0.00 | 0.00 |
| | | | | Max. Vx | 20 | 0.00 | 0.00 | 0.00 |
| | | | | Max Tension | 32 | 0.26 | 0.00 | 0.00 |
| Bottom Girt | Max. Compression | 1 | | 0.00 | 0.00 | 0.00 | | |
| | Max. Mx | 25 | | 0.16 | 0.01 | 0.00 | | |
| | Max. My | 20 | | 0.22 | 0.00 | -0.00 | | |
| | Max. Vy | 25 | | -0.02 | 0.00 | 0.00 | | |
| | Max. Vx | 20 | | 0.00 | 0.00 | 0.00 | | |
| | Max Tension | 32 | | 0.26 | 0.00 | 0.00 | | |
| | T8 | 20 - 5 | Leg | Max. Compression | 1 | 0.00 | 0.00 | 0.00 |
| | | | | Max. Mx | 22 | -40.24 | -0.04 | 0.04 |
| | | | | Max. My | 20 | -39.91 | -0.46 | 0.27 |
| | | | | Max. Vy | 26 | -39.36 | 0.00 | -0.53 |
| | | | | Max. Vx | 20 | 0.35 | -0.46 | 0.27 |
| | | | | Max Tension | 26 | 0.40 | 0.00 | -0.53 |
| Diagonal | | | | Max Tension | 34 | 1.42 | 0.00 | 0.00 |
| | | | | Max. Compression | 34 | -0.97 | 0.00 | 0.00 |
| | | | | Max. Mx | 20 | -0.72 | -0.01 | 0.00 |
| | | | | Max. My | 21 | -0.47 | -0.01 | 0.00 |
| | | | | Max. Vy | 19 | 0.01 | -0.01 | -0.00 |
| | | | | Max. Vx | 21 | 0.00 | 0.00 | 0.00 |
| | | | Max Tension | 19 | 0.29 | 0.00 | 0.00 | |
| | | | Top Girt | Max. Compression | 15 | -0.02 | 0.00 | 0.00 |
| | | | | Max. Mx | 25 | 0.26 | 0.01 | 0.00 |
| | | | | Max. My | 20 | 0.16 | 0.00 | -0.00 |
| | | | | Max. Vy | 25 | -0.01 | 0.00 | 0.00 |
| | | | | Max. Vx | 20 | 0.00 | 0.00 | 0.00 |
| Max Tension | | | | 19 | 7.97 | 0.00 | 0.00 | |
| Bottom Girt | | | | Max. Compression | 1 | 0.00 | 0.00 | 0.00 |
| | | | | Max. Mx | 25 | 7.87 | 0.01 | 0.00 |
| | | | | Max. My | 20 | 7.75 | 0.00 | -0.00 |
| | | | | Max. Vy | 25 | -0.01 | 0.00 | 0.00 |
| | | | | Max. Vx | 20 | 0.00 | 0.00 | 0.00 |
| | Max Tension | 19 | | 7.97 | 0.00 | 0.00 | | |
| | T9 | 5 - 0 | Leg | Max. Compression | 1 | 0.00 | 0.00 | 0.00 |
| | | | | Max. Mx | 34 | -42.80 | -0.34 | 0.00 |
| | | | | Max. My | 20 | -42.75 | 0.53 | 0.00 |
| | | | | Max. Vy | 17 | -13.90 | 0.07 | 0.03 |
| | | | | Max. Vx | 19 | 1.23 | -0.45 | -0.00 |
| | | | | Max Tension | 3 | -0.08 | -0.17 | 0.01 |
| Diagonal | | | | Max Tension | 20 | 0.61 | 0.00 | 0.00 |
| | | | | Max. Compression | 19 | -2.88 | -0.00 | 0.00 |

| | | |
|--|---|----------------------------------|
| tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587 | Job 17012.45 - CT11180C | Page 30 of 44 |
| | Project 150' Guyed Tower - 130 Vernon Road Bolton, CT | Date 13:20:26 04/20/17 |
| | Client T-Mobile | Designed by TJL |

| Section No. | Elevation ft | Component Type | Condition | Gov. Load Comb. | Axial K | Major Axis Moment kip-ft | Minor Axis Moment kip-ft |
|-------------|--------------|----------------|------------------|-----------------|---------|--------------------------|--------------------------|
| | | | Max. Mx | 20 | 0.60 | -0.01 | -0.00 |
| | | | Max. My | 19 | 0.57 | -0.01 | 0.00 |
| | | | Max. Vy | 23 | 0.01 | 0.00 | 0.00 |
| | | | Max. Vx | 23 | -0.00 | 0.00 | 0.00 |
| | | Horizontal | Max Tension | 19 | 0.25 | 0.00 | 0.00 |
| | | | Max. Compression | 1 | 0.00 | 0.00 | 0.00 |
| | | | Max. Mx | 25 | 0.23 | 0.01 | 0.00 |
| | | | Max. My | 20 | 0.21 | 0.00 | 0.00 |
| | | | Max. Vy | 25 | -0.02 | 0.00 | 0.00 |
| | | | Max. Vx | 20 | -0.00 | 0.00 | 0.00 |
| | | Bottom Girt | Max Tension | 19 | 1.36 | 0.00 | 0.00 |
| | | | Max. Compression | 1 | 0.00 | 0.00 | 0.00 |
| | | | Max. Mx | 25 | 1.33 | 0.00 | 0.00 |
| | | | Max. Vy | 25 | -0.00 | 0.00 | 0.00 |

Maximum Reactions

| Location | Condition | Gov. Load Comb. | Vertical K | Horizontal, X K | Horizontal, Z K | |
|--|--|---------------------|------------|-----------------|-----------------|--------|
| Mast | Max. Vert | 19 | 114.07 | 0.05 | 0.68 | |
| | Max. H _x | 14 | 43.55 | 1.18 | 0.06 | |
| | Max. H _z | 2 | 42.33 | 0.01 | 1.38 | |
| | Max. M _x | 1 | 0.00 | 0.00 | 0.02 | |
| | Max. M _z | 1 | 0.00 | 0.00 | 0.02 | |
| | Max. Torsion | 1 | 0.00 | 0.00 | 0.02 | |
| | Min. Vert | 1 | 35.17 | 0.00 | 0.02 | |
| | Min. H _x | 6 | 43.68 | -1.18 | 0.04 | |
| | Min. H _z | 10 | 43.84 | -0.01 | -1.20 | |
| | Min. M _x | 1 | 0.00 | 0.00 | 0.02 | |
| | Min. M _z | 1 | 0.00 | 0.00 | 0.02 | |
| | Min. Torsion | 1 | 0.00 | 0.00 | 0.02 | |
| | Guy C @ 210 ft Elev -38 ft Azimuth 240 deg | Max. Vert | 13 | -1.43 | -1.94 | 1.12 |
| | | Max. H _x | 13 | -1.43 | -1.94 | 1.12 |
| Max. H _z | | 21 | -17.42 | -24.70 | 14.43 | |
| Min. Vert | | 22 | -17.51 | -24.87 | 14.37 | |
| Min. H _x | | 22 | -17.51 | -24.87 | 14.37 | |
| Min. H _z | | 13 | -1.43 | -1.94 | 1.12 | |
| Max. Vert | | 7 | -1.35 | 1.91 | 1.11 | |
| Guy B @ 210 ft Elev -34 ft Azimuth 120 deg | Max. H _x | 32 | -16.92 | 24.80 | 14.33 | |
| | Max. H _z | 33 | -16.83 | 24.62 | 14.39 | |
| | Min. Vert | 32 | -16.92 | 24.80 | 14.33 | |
| | Min. H _x | 7 | -1.35 | 1.91 | 1.11 | |
| | Min. H _z | 7 | -1.35 | 1.91 | 1.11 | |
| | Max. Vert | 2 | -0.78 | -0.00 | -1.81 | |
| | Guy A @ 210 ft Elev -14 ft Azimuth 0 deg | Max. H _x | 31 | -11.63 | 0.89 | -23.82 |
| Max. H _z | | 2 | -0.78 | -0.00 | -1.81 | |
| Min. Vert | | 27 | -14.25 | -0.00 | -28.64 | |
| Min. H _x | | 23 | -11.61 | -0.89 | -23.79 | |
| Min. H _z | | 27 | -14.25 | -0.00 | -28.64 | |
| | | | | | | |

| | | |
|--|---|----------------------------------|
| tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587 | Job 17012.45 - CT11180C | Page 31 of 44 |
| | Project 150' Guyed Tower - 130 Vernon Road Bolton, CT | Date 13:20:26 04/20/17 |
| | Client T-Mobile | Designed by TJL |

Tower Mast Reaction Summary

| Load Combination | Vertical | Shear _x | Shear _z | Overtuning Moment, M _x | Overtuning Moment, M _z | Torque |
|--|----------|--------------------|--------------------|-----------------------------------|-----------------------------------|--------|
| | K | K | K | kip-ft | kip-ft | kip-ft |
| Dead Only | 35.17 | -0.00 | -0.02 | 0.00 | 0.00 | 0.00 |
| 1.2 Dead+1.6 Wind 0 deg - No Ice+1.0 Guy | 42.33 | -0.01 | -1.38 | 0.00 | 0.00 | 0.00 |
| 1.2 Dead+1.6 Wind 30 deg - No Ice+1.0 Guy | 44.12 | 0.60 | -1.03 | 0.00 | 0.00 | 0.00 |
| 1.2 Dead+1.6 Wind 45 deg - No Ice+1.0 Guy | 44.67 | 0.84 | -0.83 | 0.00 | 0.00 | 0.00 |
| 1.2 Dead+1.6 Wind 60 deg - No Ice+1.0 Guy | 44.81 | 1.02 | -0.61 | 0.00 | 0.00 | 0.00 |
| 1.2 Dead+1.6 Wind 90 deg - No Ice+1.0 Guy | 43.68 | 1.18 | -0.04 | 0.00 | 0.00 | 0.00 |
| 1.2 Dead+1.6 Wind 120 deg - No Ice+1.0 Guy | 41.80 | 1.14 | 0.65 | 0.00 | 0.00 | 0.00 |
| 1.2 Dead+1.6 Wind 135 deg - No Ice+1.0 Guy | 42.31 | 0.89 | 0.87 | 0.00 | 0.00 | 0.00 |
| 1.2 Dead+1.6 Wind 150 deg - No Ice+1.0 Guy | 43.04 | 0.59 | 1.04 | 0.00 | 0.00 | 0.00 |
| 1.2 Dead+1.6 Wind 180 deg - No Ice+1.0 Guy | 43.84 | 0.01 | 1.20 | 0.00 | 0.00 | 0.00 |
| 1.2 Dead+1.6 Wind 210 deg - No Ice+1.0 Guy | 43.09 | -0.57 | 1.03 | 0.00 | 0.00 | 0.00 |
| 1.2 Dead+1.6 Wind 225 deg - No Ice+1.0 Guy | 42.35 | -0.87 | 0.86 | 0.00 | 0.00 | 0.00 |
| 1.2 Dead+1.6 Wind 240 deg - No Ice+1.0 Guy | 41.85 | -1.12 | 0.62 | 0.00 | 0.00 | 0.00 |
| 1.2 Dead+1.6 Wind 270 deg - No Ice+1.0 Guy | 43.55 | -1.18 | -0.06 | 0.00 | 0.00 | 0.00 |
| 1.2 Dead+1.6 Wind 300 deg - No Ice+1.0 Guy | 44.59 | -1.04 | -0.63 | 0.00 | 0.00 | 0.00 |
| 1.2 Dead+1.6 Wind 315 deg - No Ice+1.0 Guy | 44.44 | -0.86 | -0.86 | 0.00 | 0.00 | 0.00 |
| 1.2 Dead+1.6 Wind 330 deg - No Ice+1.0 Guy | 43.93 | -0.62 | -1.05 | 0.00 | 0.00 | 0.00 |
| 1.2 Dead+1.0 Ice+1.0 Temp+Guy | 112.04 | -0.04 | -0.02 | 0.00 | 0.00 | 0.00 |
| 1.2 Dead+1.0 Wind 0 deg+1.0 Ice+1.0 Temp+1.0 Guy | 114.07 | -0.05 | -0.68 | 0.00 | 0.00 | 0.00 |
| 1.2 Dead+1.0 Wind 30 deg+1.0 Ice+1.0 Temp+1.0 Guy | 113.43 | 0.21 | -0.58 | 0.00 | 0.00 | 0.00 |
| 1.2 Dead+1.0 Wind 45 deg+1.0 Ice+1.0 Temp+1.0 Guy | 112.98 | 0.33 | -0.46 | 0.00 | 0.00 | 0.00 |
| 1.2 Dead+1.0 Wind 60 deg+1.0 Ice+1.0 Temp+1.0 Guy | 112.74 | 0.44 | -0.30 | 0.00 | 0.00 | 0.00 |
| 1.2 Dead+1.0 Wind 90 deg+1.0 Ice+1.0 Temp+1.0 Guy | 113.00 | 0.57 | 0.04 | 0.00 | 0.00 | 0.00 |
| 1.2 Dead+1.0 Wind 120 deg+1.0 Ice+1.0 Temp+1.0 Guy | 113.27 | 0.53 | 0.31 | 0.00 | 0.00 | 0.00 |
| 1.2 Dead+1.0 Wind 135 deg+1.0 Ice+1.0 Temp+1.0 Guy | 112.97 | 0.45 | 0.41 | 0.00 | 0.00 | 0.00 |
| 1.2 Dead+1.0 Wind 150 deg+1.0 Ice+1.0 Temp+1.0 Guy | 112.48 | 0.32 | 0.48 | 0.00 | 0.00 | 0.00 |
| 1.2 Dead+1.0 Wind 180 deg+1.0 Ice+1.0 Temp+1.0 Guy | 111.86 | -0.04 | 0.54 | 0.00 | 0.00 | 0.00 |
| 1.2 Dead+1.0 Wind 210 deg+1.0 Ice+1.0 Temp+1.0 Guy | 112.40 | -0.41 | 0.48 | 0.00 | 0.00 | 0.00 |

| | | |
|--|---|----------------------------------|
| tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587 | Job 17012.45 - CT11180C | Page 32 of 44 |
| | Project 150' Guyed Tower - 130 Vernon Road Bolton, CT | Date 13:20:26 04/20/17 |
| | Client T-Mobile | Designed by TJL |

| Load Combination | Vertical K | Shear _x K | Shear _z K | Overturning Moment, M _x kip-ft | Overturning Moment, M _z kip-ft | Torque kip-ft |
|--|---------------|-------------------------|-------------------------|---|---|------------------|
| 1.2 Dead+1.0 Wind 225 deg+1.0 Ice+1.0 Temp+1.0 Guy | 112.85 | -0.53 | 0.41 | 0.00 | 0.00 | 0.00 |
| 1.2 Dead+1.0 Wind 240 deg+1.0 Ice+1.0 Temp+1.0 Guy | 113.11 | -0.62 | 0.31 | 0.00 | 0.00 | 0.00 |
| 1.2 Dead+1.0 Wind 270 deg+1.0 Ice+1.0 Temp+1.0 Guy | 112.83 | -0.66 | 0.03 | 0.00 | 0.00 | 0.00 |
| 1.2 Dead+1.0 Wind 300 deg+1.0 Ice+1.0 Temp+1.0 Guy | 112.59 | -0.53 | -0.31 | 0.00 | 0.00 | 0.00 |
| 1.2 Dead+1.0 Wind 315 deg+1.0 Ice+1.0 Temp+1.0 Guy | 112.86 | -0.42 | -0.47 | 0.00 | 0.00 | 0.00 |
| 1.2 Dead+1.0 Wind 330 deg+1.0 Ice+1.0 Temp+1.0 Guy | 113.34 | -0.30 | -0.59 | 0.00 | 0.00 | 0.00 |
| Dead+Wind 0 deg - Service+Guy | 35.59 | -0.01 | -0.36 | 0.00 | 0.00 | 0.00 |
| Dead+Wind 30 deg - Service+Guy | 35.50 | 0.15 | -0.31 | 0.00 | 0.00 | 0.00 |
| Dead+Wind 45 deg - Service+Guy | 35.45 | 0.22 | -0.25 | 0.00 | 0.00 | 0.00 |
| Dead+Wind 60 deg - Service+Guy | 35.42 | 0.28 | -0.17 | 0.00 | 0.00 | 0.00 |
| Dead+Wind 90 deg - Service+Guy | 35.43 | 0.33 | -0.00 | 0.00 | 0.00 | 0.00 |
| Dead+Wind 120 deg - Service+Guy | 35.45 | 0.29 | 0.16 | 0.00 | 0.00 | 0.00 |
| Dead+Wind 135 deg - Service+Guy | 35.41 | 0.24 | 0.22 | 0.00 | 0.00 | 0.00 |
| Dead+Wind 150 deg - Service+Guy | 35.34 | 0.17 | 0.27 | 0.00 | 0.00 | 0.00 |
| Dead+Wind 180 deg - Service+Guy | 35.28 | -0.00 | 0.31 | 0.00 | 0.00 | 0.00 |
| Dead+Wind 210 deg - Service+Guy | 35.33 | -0.18 | 0.27 | 0.00 | 0.00 | 0.00 |
| Dead+Wind 225 deg - Service+Guy | 35.39 | -0.25 | 0.22 | 0.00 | 0.00 | 0.00 |
| Dead+Wind 240 deg - Service+Guy | 35.43 | -0.30 | 0.15 | 0.00 | 0.00 | 0.00 |
| Dead+Wind 270 deg - Service+Guy | 35.40 | -0.34 | -0.01 | 0.00 | 0.00 | 0.00 |
| Dead+Wind 300 deg - Service+Guy | 35.40 | -0.28 | -0.18 | 0.00 | 0.00 | 0.00 |
| Dead+Wind 315 deg - Service+Guy | 35.43 | -0.23 | -0.25 | 0.00 | 0.00 | 0.00 |
| Dead+Wind 330 deg - Service+Guy | 35.49 | -0.16 | -0.31 | 0.00 | 0.00 | 0.00 |

Solution Summary

| Load Comb. | Sum of Applied Forces | | | Sum of Reactions | | | % Error |
|------------|-----------------------|---------|---------|------------------|---------|---------|---------|
| | PX K | PY K | PZ K | PX K | PY K | PZ K | |
| 1 | 0.00 | -16.19 | 0.00 | -0.00 | 16.19 | -0.00 | 0.004% |
| 2 | 0.10 | -19.33 | -17.02 | -0.10 | 19.33 | 17.00 | 0.074% |
| 3 | 8.55 | -19.12 | -14.78 | -8.56 | 19.12 | 14.77 | 0.065% |
| 4 | 12.07 | -18.97 | -12.09 | -12.08 | 18.97 | 12.08 | 0.076% |
| 5 | 14.76 | -18.91 | -8.59 | -14.77 | 18.91 | 8.58 | 0.063% |
| 6 | 16.99 | -19.09 | -0.10 | -16.98 | 19.09 | 0.11 | 0.081% |
| 7 | 14.67 | -19.27 | 8.42 | -14.65 | 19.27 | -8.41 | 0.084% |
| 8 | 11.93 | -19.20 | 11.95 | -11.92 | 19.20 | -11.94 | 0.043% |

| | | | | |
|--|----------------|---|--------------------|-------------------|
| tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587 | Job | 17012.45 - CT11180C | Page | 33 of 44 |
| | Project | 150' Guyed Tower - 130 Vernon Road Bolton, CT | Date | 13:20:26 04/20/17 |
| | Client | T-Mobile | Designed by | TJL |

| Load Comb. | Sum of Applied Forces | | | Sum of Reactions | | | % Error |
|------------|-----------------------|---------|---------|------------------|---------|---------|---------|
| | PX K | PY K | PZ K | PX K | PY K | PZ K | |
| 9 | 8.38 | -19.05 | 14.68 | -8.36 | 19.05 | -14.67 | 0.075% |
| 10 | -0.10 | -18.83 | 17.02 | 0.10 | 18.83 | -17.03 | 0.040% |
| 11 | -8.55 | -19.04 | 14.78 | 8.54 | 19.04 | -14.78 | 0.075% |
| 12 | -12.07 | -19.19 | 12.09 | 12.05 | 19.19 | -12.09 | 0.088% |
| 13 | -14.76 | -19.26 | 8.59 | 14.74 | 19.26 | -8.58 | 0.084% |
| 14 | -16.99 | -19.08 | 0.10 | 16.98 | 19.08 | -0.08 | 0.076% |
| 15 | -14.66 | -18.90 | -8.42 | 14.68 | 18.90 | 8.41 | 0.061% |
| 16 | -11.93 | -18.97 | -11.95 | 11.94 | 18.96 | 11.93 | 0.071% |
| 17 | -8.38 | -19.12 | -14.68 | 8.39 | 19.12 | 14.66 | 0.061% |
| 18 | 0.00 | -73.03 | 0.00 | 0.00 | 73.03 | -0.00 | 0.005% |
| 19 | 0.03 | -73.34 | -9.31 | -0.03 | 73.34 | 9.29 | 0.019% |
| 20 | 4.70 | -73.07 | -8.07 | -4.70 | 73.07 | 8.06 | 0.014% |
| 21 | 6.66 | -72.88 | -6.59 | -6.66 | 72.88 | 6.58 | 0.020% |
| 22 | 8.17 | -72.80 | -4.67 | -8.16 | 72.80 | 4.66 | 0.025% |
| 23 | 9.42 | -73.04 | -0.02 | -9.41 | 73.04 | 0.02 | 0.018% |
| 24 | 8.14 | -73.28 | 4.63 | -8.13 | 73.28 | -4.62 | 0.009% |
| 25 | 6.62 | -73.19 | 6.55 | -6.62 | 73.19 | -6.54 | 0.009% |
| 26 | 4.65 | -73.00 | 8.03 | -4.64 | 73.00 | -8.03 | 0.014% |
| 27 | -0.03 | -72.72 | 9.31 | 0.03 | 72.72 | -9.30 | 0.010% |
| 28 | -4.70 | -72.99 | 8.07 | 4.69 | 72.99 | -8.07 | 0.010% |
| 29 | -6.66 | -73.18 | 6.59 | 6.65 | 73.18 | -6.59 | 0.014% |
| 30 | -8.17 | -73.27 | 4.67 | 8.16 | 73.27 | -4.67 | 0.015% |
| 31 | -9.42 | -73.03 | 0.02 | 9.41 | 73.03 | -0.02 | 0.014% |
| 32 | -8.14 | -72.79 | -4.63 | 8.14 | 72.79 | 4.62 | 0.014% |
| 33 | -6.62 | -72.88 | -6.55 | 6.63 | 72.88 | 6.53 | 0.021% |
| 34 | -4.65 | -73.07 | -8.03 | 4.65 | 73.07 | 8.02 | 0.015% |
| 35 | 0.02 | -16.25 | -4.07 | -0.02 | 16.25 | 4.06 | 0.045% |
| 36 | 2.05 | -16.20 | -3.53 | -2.05 | 16.20 | 3.53 | 0.033% |
| 37 | 2.89 | -16.17 | -2.89 | -2.89 | 16.17 | 2.88 | 0.047% |
| 38 | 3.53 | -16.15 | -2.05 | -3.54 | 16.15 | 2.05 | 0.062% |
| 39 | 4.06 | -16.20 | -0.02 | -4.06 | 16.20 | 0.03 | 0.034% |
| 40 | 3.51 | -16.24 | 2.01 | -3.50 | 16.24 | -2.01 | 0.029% |
| 41 | 2.85 | -16.22 | 2.86 | -2.85 | 16.22 | -2.86 | 0.027% |
| 42 | 2.00 | -16.19 | 3.51 | -2.00 | 16.19 | -3.51 | 0.022% |
| 43 | -0.02 | -16.13 | 4.07 | 0.03 | 16.13 | -4.07 | 0.027% |
| 44 | -2.05 | -16.18 | 3.53 | 2.04 | 16.18 | -3.53 | 0.040% |
| 45 | -2.89 | -16.22 | 2.89 | 2.88 | 16.22 | -2.89 | 0.025% |
| 46 | -3.53 | -16.24 | 2.05 | 3.53 | 16.24 | -2.05 | 0.026% |
| 47 | -4.06 | -16.19 | 0.02 | 4.06 | 16.19 | -0.01 | 0.057% |
| 48 | -3.51 | -16.15 | -2.01 | 3.51 | 16.15 | 2.00 | 0.069% |
| 49 | -2.85 | -16.17 | -2.86 | 2.86 | 16.17 | 2.85 | 0.049% |
| 50 | -2.00 | -16.20 | -3.51 | 2.01 | 16.20 | 3.50 | 0.034% |

Non-Linear Convergence Results

| Load Combination | Converged? | Number of Cycles | Displacement Tolerance | Force Tolerance |
|------------------|------------|------------------|------------------------|-----------------|
| 1 | Yes | 6 | 0.00000001 | 0.00008194 |
| 2 | Yes | 14 | 0.00141443 | 0.00084363 |
| 3 | Yes | 14 | 0.00099155 | 0.00088402 |
| 4 | Yes | 13 | 0.00105882 | 0.00099220 |
| 5 | Yes | 11 | 0.00074525 | 0.00089925 |
| 6 | Yes | 13 | 0.00116782 | 0.00112495 |
| 7 | Yes | 13 | 0.00146554 | 0.00115152 |
| 8 | Yes | 14 | 0.00075206 | 0.00065583 |
| 9 | Yes | 13 | 0.00121587 | 0.00107471 |

| | | | | |
|--|----------------|---|--------------------|-------------------|
| tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587 | Job | 17012.45 - CT11180C | Page | 34 of 44 |
| | Project | 150' Guyed Tower - 130 Vernon Road Bolton, CT | Date | 13:20:26 04/20/17 |
| | Client | T-Mobile | Designed by | TJL |

| | | | | |
|----|-----|----|------------|------------|
| 10 | Yes | 11 | 0.00041267 | 0.00088770 |
| 11 | Yes | 13 | 0.00119043 | 0.00107182 |
| 12 | Yes | 13 | 0.00146869 | 0.00125059 |
| 13 | Yes | 13 | 0.00144068 | 0.00116620 |
| 14 | Yes | 13 | 0.00111243 | 0.00108167 |
| 15 | Yes | 11 | 0.00072376 | 0.00093045 |
| 16 | Yes | 13 | 0.00101302 | 0.00094715 |
| 17 | Yes | 14 | 0.00095427 | 0.00084131 |
| 18 | Yes | 12 | 0.00077891 | 0.00012132 |
| 19 | Yes | 13 | 0.00118438 | 0.00046265 |
| 20 | Yes | 13 | 0.00084048 | 0.00034202 |
| 21 | Yes | 12 | 0.00113213 | 0.00044331 |
| 22 | Yes | 11 | 0.00135268 | 0.00048946 |
| 23 | Yes | 11 | 0.00105627 | 0.00038917 |
| 24 | Yes | 13 | 0.00078775 | 0.00023091 |
| 25 | Yes | 13 | 0.00084788 | 0.00022180 |
| 26 | Yes | 12 | 0.00133222 | 0.00031781 |
| 27 | Yes | 11 | 0.00086087 | 0.00022920 |
| 28 | Yes | 12 | 0.00105257 | 0.00023334 |
| 29 | Yes | 12 | 0.00147929 | 0.00031918 |
| 30 | Yes | 12 | 0.00142559 | 0.00033927 |
| 31 | Yes | 11 | 0.00093423 | 0.00031204 |
| 32 | Yes | 12 | 0.00087557 | 0.00031932 |
| 33 | Yes | 12 | 0.00129748 | 0.00047347 |
| 34 | Yes | 13 | 0.00091724 | 0.00035361 |
| 35 | Yes | 9 | 0.00132280 | 0.00068038 |
| 36 | Yes | 9 | 0.00091803 | 0.00048599 |
| 37 | Yes | 8 | 0.00117217 | 0.00049475 |
| 38 | Yes | 6 | 0.00125698 | 0.00044932 |
| 39 | Yes | 8 | 0.00090340 | 0.00039935 |
| 40 | Yes | 9 | 0.00097786 | 0.00042104 |
| 41 | Yes | 9 | 0.00100097 | 0.00041089 |
| 42 | Yes | 9 | 0.00000001 | 0.00031700 |
| 43 | Yes | 6 | 0.00000001 | 0.00031904 |
| 44 | Yes | 8 | 0.00138700 | 0.00041983 |
| 45 | Yes | 9 | 0.00093130 | 0.00036754 |
| 46 | Yes | 9 | 0.00093841 | 0.00039675 |
| 47 | Yes | 7 | 0.00146982 | 0.00047278 |
| 48 | Yes | 6 | 0.00145747 | 0.00043866 |
| 49 | Yes | 8 | 0.00129932 | 0.00051668 |
| 50 | Yes | 9 | 0.00098726 | 0.00049588 |

Maximum Tower Deflections - Service Wind

| Section No. | Elevation ft | Horz. Deflection in | Gov. Load Comb. | Tilt ° | Twist ° |
|-------------|-----------------|---------------------------|-----------------------|-----------|------------|
| T1 | 150 - 140 | 1.132 | 38 | 0.0201 | 0.0129 |
| T2 | 140 - 120 | 1.102 | 38 | 0.0181 | 0.0129 |
| T3 | 120 - 100 | 1.045 | 38 | 0.0226 | 0.0141 |
| T4 | 100 - 80 | 0.921 | 38 | 0.0363 | 0.0119 |
| T5 | 80 - 60 | 0.745 | 38 | 0.0416 | 0.0156 |
| T6 | 60 - 40 | 0.578 | 38 | 0.0379 | 0.0205 |
| T7 | 40 - 20 | 0.418 | 38 | 0.0425 | 0.0234 |
| T8 | 20 - 5 | 0.224 | 38 | 0.0504 | 0.0250 |
| T9 | 5 - 0 | 0.057 | 38 | 0.0534 | 0.0255 |

| | | |
|--|---|----------------------------------|
| tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587 | Job 17012.45 - CT11180C | Page 35 of 44 |
| | Project 150' Guyed Tower - 130 Vernon Road Bolton, CT | Date 13:20:26 04/20/17 |
| | Client T-Mobile | Designed by TJL |

Critical Deflections and Radius of Curvature - Service Wind

| Elevation | Appurtenance | Gov. Load Comb. | Deflection in | Tilt ° | Twist ° | Radius of Curvature ft |
|-----------|-----------------|-----------------|---------------|--------|---------|------------------------|
| 148.00 | APXVSPP18-C-A20 | 38 | 1.125 | 0.0196 | 0.0129 | 170312 |
| 138.00 | Guy | 38 | 1.096 | 0.0179 | 0.0130 | 114750 |
| 130.00 | AIR21 B4A/B2P | 38 | 1.077 | 0.0188 | 0.0137 | 160650 |
| 70.00 | Guy | 38 | 0.659 | 0.0397 | 0.0183 | 178709 |

Maximum Tower Deflections - Design Wind

| Section No. | Elevation ft | Horz. Deflection in | Gov. Load Comb. | Tilt ° | Twist ° |
|-------------|--------------|---------------------|-----------------|--------|---------|
| T1 | 150 - 140 | 6.094 | 5 | 0.1454 | 0.1054 |
| T2 | 140 - 120 | 5.811 | 5 | 0.1367 | 0.1056 |
| T3 | 120 - 100 | 5.273 | 5 | 0.1579 | 0.1094 |
| T4 | 100 - 80 | 4.498 | 5 | 0.2074 | 0.0986 |
| T5 | 80 - 60 | 3.547 | 5 | 0.2197 | 0.0915 |
| T6 | 60 - 40 | 2.681 | 5 | 0.1921 | 0.0992 |
| T7 | 40 - 20 | 1.900 | 5 | 0.2013 | 0.1114 |
| T8 | 20 - 5 | 1.003 | 5 | 0.2285 | 0.1182 |
| T9 | 5 - 0 | 0.254 | 5 | 0.2398 | 0.1202 |

Critical Deflections and Radius of Curvature - Design Wind

| Elevation | Appurtenance | Gov. Load Comb. | Deflection in | Tilt ° | Twist ° | Radius of Curvature ft |
|-----------|-----------------|-----------------|---------------|--------|---------|------------------------|
| 148.00 | APXVSPP18-C-A20 | 5 | 6.036 | 0.1432 | 0.1053 | 47809 |
| 138.00 | Guy | 5 | 5.758 | 0.1362 | 0.1060 | 33659 |
| 130.00 | AIR21 B4A/B2P | 5 | 5.553 | 0.1408 | 0.1083 | 45484 |
| 70.00 | Guy | 5 | 3.097 | 0.2057 | 0.0900 | 30872 |

Bolt Design Data

| Section No. | Elevation ft | Component Type | Bolt Grade | Bolt Size in | Number Of Bolts | Maximum Load per Bolt K | Allowable Load K | Ratio Load / Allowable | Allowable Ratio | Criteria |
|-------------|--------------|----------------|------------|--------------|-----------------|-------------------------|------------------|------------------------|-----------------|-----------|
| T2 | 140 | Leg | A325N | 0.6250 | 5 | 3.29 | 24.85 | 0.133 | ✓ | 1 Bolt DS |
| T3 | 120 | Leg | A325N | 0.6250 | 5 | 5.78 | 24.85 | 0.233 | ✓ | 1 Bolt DS |
| T4 | 100 | Leg | A325N | 0.7500 | 5 | 6.13 | 35.78 | 0.171 | ✓ | 1 Bolt DS |
| T5 | 80 | Leg | A325N | 0.7500 | 5 | 5.63 | 35.78 | 0.157 | ✓ | 1 Bolt DS |
| T6 | 60 | Leg | A325N | 0.7500 | 5 | 7.13 | 35.78 | 0.199 | ✓ | 1 Bolt DS |
| T7 | 40 | Leg | A325N | 0.7500 | 5 | 7.94 | 35.78 | 0.222 | ✓ | 1 Bolt DS |

| | | |
|--|---|----------------------------------|
| tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587 | Job 17012.45 - CT11180C | Page 36 of 44 |
| | Project 150' Guyed Tower - 130 Vernon Road Bolton, CT | Date 13:20:26 04/20/17 |
| | Client T-Mobile | Designed by TJL |

| Section No. | Elevation ft | Component Type | Bolt Grade | Bolt Size in | Number Of Bolts | Maximum Load per Bolt K | Allowable Load K | Ratio Load/Allowable | Allowable Ratio | Criteria |
|-------------|-----------------|----------------|------------|-----------------|-----------------|----------------------------|---------------------|----------------------|-----------------|----------|
| T8 | 20 | Leg | A325N | 0.7500 | 5 | 8.05 | 35.78 | 0.225 ✓ | 1 | Bolt DS |

Guy Design Data

| Section No. | Elevation ft | Size | Initial Tension K | Breaking Load K | Actual T_u K | Allowable ϕT_n K | Required S.F. | Actual S.F. |
|-------------|---------------------|------------|----------------------|--------------------|-------------------|---------------------------|---------------|-------------|
| T2 | 138.00 (A) (457) | 9/16 EHS | 3.50 | 35.00 | 11.31 | 21.00 | 1.000 | 1.856 ✓ |
| | 138.00 (A) (458) | 9/16 EHS | 3.50 | 35.00 | 11.33 | 21.00 | 1.000 | 1.854 ✓ |
| | 138.00 (B) (451) | 9/16 EHS | 3.50 | 35.00 | 11.86 | 21.00 | 1.000 | 1.771 ✓ |
| | 138.00 (B) (452) | 9/16 EHS | 3.50 | 35.00 | 11.87 | 21.00 | 1.000 | 1.770 ✓ |
| | 138.00 (C) (442) | 9/16 EHS | 3.50 | 35.00 | 11.99 | 21.00 | 1.000 | 1.751 ✓ |
| | 138.00 (C) (443) | 9/16 EHS | 3.50 | 35.00 | 11.97 | 21.00 | 1.000 | 1.754 ✓ |
| T5 | 70.00 (A) (468) | 11/16" EHS | 5.00 | 50.00 | 12.50 | 30.00 | 1.000 | 2.400 ✓ |
| | 70.00 (B) (467) | 11/16" EHS | 5.00 | 50.00 | 12.99 | 30.00 | 1.000 | 2.310 ✓ |
| | 70.00 (C) (463) | 11/16" EHS | 5.00 | 50.00 | 13.18 | 30.00 | 1.000 | 2.277 ✓ |

Compression Checks

Leg Design Data (Compression)

| Section No. | Elevation ft | Size | L ft | L_u ft | Kl/r | A in ² | Mast Stability Index | P_u K | ϕP_n K | Ratio $\frac{P_u}{\phi P_n}$ |
|-------------|-----------------|-------|---------|-------------|----------------|----------------------|----------------------|------------|-----------------|------------------------------|
| T1 | 150 - 140 | 2 | 10.00 | 2.25 | 54.0 K=1.00 | 3.1416 | 1.00 | -16.63 | 114.23 | 0.146 ¹ ✓ |
| T2 | 140 - 120 | 2 | 20.00 | 2.38 | 57.0 K=1.00 | 3.1416 | 1.00 | -28.88 | 111.48 | 0.259 ¹ ✓ |
| T3 | 120 - 100 | 2 | 20.00 | 2.38 | 57.0 K=1.00 | 3.1416 | 1.00 | -30.80 | 111.48 | 0.276 ¹ ✓ |
| T4 | 100 - 80 | 2 1/4 | 20.00 | 2.38 | 50.7 K=1.00 | 3.9761 | 1.00 | -30.67 | 148.30 | 0.207 ¹ ✓ |
| T5 | 80 - 60 | 2 1/4 | 20.00 | 2.38 | 50.7 K=1.00 | 3.9761 | 1.00 | -35.62 | 148.30 | 0.240 ¹ ✓ |
| T6 | 60 - 40 | 2 1/4 | 20.00 | 2.38 | 50.7 K=1.00 | 3.9761 | 1.00 | -39.71 | 148.30 | 0.268 ¹ ✓ |

| | | |
|--|---|----------------------------------|
| tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587 | Job 17012.45 - CT11180C | Page 37 of 44 |
| | Project 150' Guyed Tower - 130 Vernon Road Bolton, CT | Date 13:20:26 04/20/17 |
| | Client T-Mobile | Designed by TJL |

| Section No. | Elevation ft | Size | L ft | L _u ft | Kl/r | A in ² | Mast Stability Index | P _u K | φP _n K | Ratio $\frac{P_u}{\phi P_n}$ |
|-------------|-----------------|-------|---------|----------------------|----------------|----------------------|----------------------|---------------------|----------------------|---------------------------------|
| T7 | 40 - 20 | 2 1/4 | 20.00 | 2.38 | 50.7 K=1.00 | 3.9761 | 1.00 | -40.56 | 148.30 | 0.274 ¹ ✓ |
| T8 | 20 - 5 | 2 1/2 | 15.00 | 2.42 | 46.4 K=1.00 | 4.9087 | 1.00 | -40.24 | 188.16 | 0.214 ¹ ✓ |
| T9 | 5 - 0 | 2 1/2 | 5.45 | 2.45 | 47.1 K=1.00 | 4.9087 | 1.00 | -42.80 | 187.85 | 0.228 ¹ ✓ |

¹ P_u / φP_n controls

Diagonal Design Data (Compression)

| Section No. | Elevation ft | Size | L ft | L _u ft | Kl/r | A in ² | P _u K | φP _n K | Ratio $\frac{P_u}{\phi P_n}$ |
|-------------|-----------------|------|---------|----------------------|-----------------|----------------------|---------------------|----------------------|---------------------------------|
| T1 | 150 - 140 | 3/4 | 4.37 | 2.09 | 120.4 K=0.90 | 0.4418 | -1.35 | 6.89 | 0.196 ¹ ✓ |
| T2 | 140 - 120 | 3/4 | 4.44 | 2.12 | 122.2 K=0.90 | 0.4418 | -2.48 | 6.69 | 0.371 ¹ ✓ |
| T3 | 120 - 100 | 3/4 | 4.44 | 2.12 | 122.2 K=0.90 | 0.4418 | -0.65 | 6.69 | 0.098 ¹ ✓ |
| T4 | 100 - 80 | 3/4 | 4.44 | 2.11 | 121.4 K=0.90 | 0.4418 | -1.30 | 6.77 | 0.192 ¹ ✓ |
| T5 | 80 - 60 | 3/4 | 4.44 | 2.11 | 121.4 K=0.90 | 0.4418 | -1.38 | 6.77 | 0.205 ¹ ✓ |
| T6 | 60 - 40 | 3/4 | 4.44 | 2.11 | 121.4 K=0.90 | 0.4418 | -0.99 | 6.77 | 0.147 ¹ ✓ |
| T7 | 40 - 20 | 3/4 | 4.44 | 2.11 | 121.4 K=0.90 | 0.4418 | -0.47 | 6.77 | 0.069 ¹ ✓ |
| T8 | 20 - 5 | 3/4 | 4.46 | 2.11 | 121.3 K=0.90 | 0.4418 | -0.97 | 6.78 | 0.143 ¹ ✓ |
| T9 | 5 - 0 | 3/4 | 2.60 | 2.00 | 115.0 K=0.90 | 0.4418 | -2.88 | 7.54 | 0.381 ¹ ✓ |

¹ P_u / φP_n controls

Top Girt Design Data (Compression)

| Section No. | Elevation ft | Size | L ft | L _u ft | Kl/r | A in ² | P _u K | φP _n K | Ratio $\frac{P_u}{\phi P_n}$ |
|-------------|-----------------|------|---------|----------------------|-----------------|----------------------|---------------------|----------------------|---------------------------------|
| T1 | 150 - 140 | 3/4 | 3.75 | 3.58 | 160.5 K=0.70 | 0.4418 | -0.08 | 3.87 | 0.022 ¹ ✓ |
| T2 | 140 - 120 | 3/4 | 3.75 | 3.58 | 160.5 K=0.70 | 0.4418 | -1.06 | 3.87 | 0.272 ¹ ✓ |
| T3 | 120 - 100 | 3/4 | 3.75 | 3.58 | 160.5 K=0.70 | 0.4418 | -0.04 | 3.87 | 0.009 ¹ ✓ |
| T4 | 100 - 80 | 3/4 | 3.75 | 3.56 | 159.6 | 0.4418 | -0.16 | 3.92 | 0.040 ¹ ✓ |

| | | | | |
|--|----------------|---|--------------------|-------------------|
| tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587 | Job | 17012.45 - CT11180C | Page | 38 of 44 |
| | Project | 150' Guyed Tower - 130 Vernon Road Bolton, CT | Date | 13:20:26 04/20/17 |
| | Client | T-Mobile | Designed by | TJL |

| Section No. | Elevation ft | Size | L ft | L _u ft | Kl/r | A in ² | P _u K | φP _n K | Ratio $\frac{P_u}{\phi P_n}$ |
|-------------|-----------------|------|---------|----------------------|-----------------|----------------------|---------------------|----------------------|---------------------------------|
| T5 | 80 - 60 | 3/4 | 3.75 | 3.56 | K=0.70 159.6 | 0.4418 | -0.30 | 3.92 | 0.076 ¹ ✓ |
| T6 | 60 - 40 | 3/4 | 3.75 | 3.56 | K=0.70 159.6 | 0.4418 | -0.22 | 3.92 | 0.055 ¹ ✓ |
| T7 | 40 - 20 | 3/4 | 3.75 | 3.56 | K=0.70 159.6 | 0.4418 | -0.01 | 3.92 | 0.003 ¹ ✓ |
| T8 | 20 - 5 | 3/4 | 3.75 | 3.54 | K=0.70 158.7 | 0.4418 | -0.02 | 3.96 | 0.005 ¹ ✓ |

¹ P_u / φP_n controls

Bottom Girt Design Data (Compression)

| Section No. | Elevation ft | Size | L ft | L _u ft | Kl/r | A in ² | P _u K | φP _n K | Ratio $\frac{P_u}{\phi P_n}$ |
|-------------|-----------------|------|---------|----------------------|-----------------|----------------------|---------------------|----------------------|---------------------------------|
| T1 | 150 - 140 | 3/4 | 3.75 | 3.58 | K=0.70 160.5 | 0.4418 | -0.30 | 3.87 | 0.077 ¹ ✓ |
| T2 | 140 - 120 | 3/4 | 3.75 | 3.58 | K=0.70 160.5 | 0.4418 | -0.10 | 3.87 | 0.025 ¹ ✓ |
| T3 | 120 - 100 | 3/4 | 3.75 | 3.58 | K=0.70 160.5 | 0.4418 | -0.07 | 3.87 | 0.017 ¹ ✓ |
| T4 | 100 - 80 | 3/4 | 3.75 | 3.56 | K=0.70 159.6 | 0.4418 | -0.29 | 3.92 | 0.074 ¹ ✓ |
| T5 | 80 - 60 | 3/4 | 3.75 | 3.56 | K=0.70 159.6 | 0.4418 | -0.21 | 3.92 | 0.053 ¹ ✓ |
| T6 | 60 - 40 | 3/4 | 3.75 | 3.56 | K=0.70 159.6 | 0.4418 | -0.05 | 3.92 | 0.014 ¹ ✓ |

¹ P_u / φP_n controls

Top Guy Pull-Off Design Data (Compression)

| Section No. | Elevation ft | Size | L ft | L _u ft | Kl/r | A in ² | P _u K | φP _n K | Ratio $\frac{P_u}{\phi P_n}$ |
|-------------|-----------------|-------|---------|----------------------|-----------------|----------------------|---------------------|----------------------|---------------------------------|
| T1 | 150 - 140 | 1 1/4 | 3.75 | 3.58 | K=1.00 137.6 | 1.2272 | -2.82 | 14.64 | 0.192 ¹ ✓ |

¹ P_u / φP_n controls

Torque-Arm Top Design Data

| | | |
|--|---|----------------------------------|
| tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587 | Job 17012.45 - CT11180C | Page 39 of 44 |
| | Project 150' Guyed Tower - 130 Vernon Road Bolton, CT | Date 13:20:26 04/20/17 |
| | Client T-Mobile | Designed by TJL |

| Section No. | Elevation ft | Size | L ft | L _u ft | Kl/r | A in ² | P _u K | φP _n K | Ratio $\frac{P_u}{\phi P_n}$ |
|-------------|-----------------|------------|---------|----------------------|----------------|----------------------|---------------------|----------------------|---------------------------------|
| T2 | 140 - 120 (445) | 2L3x3x5/16 | 7.76 | 7.66 | 99.7 K=1.00 | 3.5500 | -0.05 | 68.19 | 0.001 ¹ ✓ |
| T2 | 140 - 120 (460) | 2L3x3x5/16 | 7.76 | 7.66 | 99.7 K=1.00 | 3.5500 | -0.13 | 68.19 | 0.002 ¹ ✓ |

¹ P_u / φP_n controls

Torque-Arm Bottom Design Data

| Section No. | Elevation ft | Size | L ft | L _u ft | Kl/r | A in ² | P _u K | φP _n K | Ratio $\frac{P_u}{\phi P_n}$ |
|-------------|-----------------|------------|---------|----------------------|----------------|----------------------|---------------------|----------------------|---------------------------------|
| T2 | 140 - 120 (449) | 2L3x3x5/16 | 6.95 | 6.85 | 89.2 K=1.00 | 3.5500 | -7.30 | 75.67 | 0.096 ¹ ✓ |
| T2 | 140 - 120 (450) | 2L3x3x5/16 | 6.95 | 6.85 | 89.2 K=1.00 | 3.5500 | -6.68 | 75.67 | 0.088 ¹ ✓ |
| T2 | 140 - 120 (455) | 2L3x3x5/16 | 6.95 | 6.85 | 89.2 K=1.00 | 3.5500 | -6.97 | 75.67 | 0.092 ¹ ✓ |
| T2 | 140 - 120 (456) | 2L3x3x5/16 | 6.95 | 6.85 | 89.2 K=1.00 | 3.5500 | -7.06 | 75.67 | 0.093 ¹ ✓ |
| T2 | 140 - 120 (461) | 2L3x3x5/16 | 6.95 | 6.85 | 89.2 K=1.00 | 3.5500 | -6.90 | 75.67 | 0.091 ¹ ✓ |
| T2 | 140 - 120 (462) | 2L3x3x5/16 | 6.95 | 6.85 | 89.2 K=1.00 | 3.5500 | -6.36 | 75.67 | 0.084 ¹ ✓ |

¹ P_u / φP_n controls

Tension Checks

Leg Design Data (Tension)

| Section No. | Elevation ft | Size | L ft | L _u ft | Kl/r | A in ² | P _u K | φP _n K | Ratio $\frac{P_u}{\phi P_n}$ |
|-------------|-----------------|------|---------|----------------------|------|----------------------|---------------------|----------------------|---------------------------------|
| T1 | 150 - 140 | 2 | 10.00 | 2.25 | 54.0 | 3.1416 | 3.17 | 141.37 | 0.022 ¹ ✓ |
| T2 | 140 - 120 | 2 | 20.00 | 2.38 | 57.0 | 3.1416 | 1.00 | 141.37 | 0.007 ¹ ✓ |
| T3 | 120 - 100 | 2 | 20.00 | 2.38 | 57.0 | 1.7942 | 1.00 | 87.47 | 0.011 ¹ ✓ |

¹ P_u / φP_n controls

| | | |
|--|---|----------------------------------|
| tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587 | Job 17012.45 - CT11180C | Page 40 of 44 |
| | Project 150' Guyed Tower - 130 Vernon Road Bolton, CT | Date 13:20:26 04/20/17 |
| | Client T-Mobile | Designed by TJL |

Diagonal Design Data (Tension)

| Section No. | Elevation ft | Size | L ft | L _u ft | Kl/r | A in ² | P _u K | φP _n K | Ratio $\frac{P_u}{\phi P_n}$ |
|-------------|-----------------|------|---------|----------------------|-------|----------------------|---------------------|----------------------|---------------------------------|
| T1 | 150 - 140 | 3/4 | 4.37 | 2.09 | 133.7 | 0.4418 | 1.33 | 19.88 | 0.067 ¹ |
| T2 | 140 - 120 | 3/4 | 4.44 | 2.12 | 135.7 | 0.4418 | 2.14 | 19.88 | 0.108 ¹ |
| T3 | 120 - 100 | 3/4 | 4.44 | 2.12 | 135.7 | 0.4418 | 0.55 | 19.88 | 0.028 ¹ |
| T4 | 100 - 80 | 3/4 | 4.44 | 2.11 | 134.9 | 0.4418 | 1.19 | 19.88 | 0.060 ¹ |
| T5 | 80 - 60 | 3/4 | 4.44 | 2.11 | 134.9 | 0.4418 | 1.28 | 19.88 | 0.064 ¹ |
| T6 | 60 - 40 | 3/4 | 4.44 | 2.11 | 134.9 | 0.4418 | 0.85 | 19.88 | 0.043 ¹ |
| T7 | 40 - 20 | 3/4 | 4.44 | 2.11 | 134.9 | 0.4418 | 0.31 | 19.88 | 0.016 ¹ |
| T8 | 20 - 5 | 3/4 | 4.46 | 2.11 | 134.8 | 0.4418 | 1.42 | 19.88 | 0.072 ¹ |
| T9 | 5 - 0 | 3/4 | 3.71 | 2.19 | 139.9 | 0.4418 | 0.61 | 19.88 | 0.031 ¹ |

¹ P_u / φP_n controls

Horizontal Design Data (Tension)

| Section No. | Elevation ft | Size | L ft | L _u ft | Kl/r | A in ² | P _u K | φP _n K | Ratio $\frac{P_u}{\phi P_n}$ |
|-------------|-----------------|-------|---------|----------------------|-------|----------------------|---------------------|----------------------|---------------------------------|
| T9 | 5 - 0 | 4x1/2 | 2.06 | 1.85 | 154.2 | 2.0000 | 0.25 | 64.80 | 0.004 ¹ |

¹ P_u / φP_n controls

Top Girt Design Data (Tension)

| Section No. | Elevation ft | Size | L ft | L _u ft | Kl/r | A in ² | P _u K | φP _n K | Ratio $\frac{P_u}{\phi P_n}$ |
|-------------|-----------------|------|---------|----------------------|-------|----------------------|---------------------|----------------------|---------------------------------|
| T1 | 150 - 140 | 3/4 | 3.75 | 3.58 | 229.3 | 0.4418 | 0.04 | 19.88 | 0.002 ¹ |
| T2 | 140 - 120 | 3/4 | 3.75 | 3.58 | 229.3 | 0.4418 | 0.90 | 19.88 | 0.045 ¹ |
| T3 | 120 - 100 | 3/4 | 3.75 | 3.58 | 229.3 | 0.4418 | 0.16 | 19.88 | 0.008 ¹ |
| T4 | 100 - 80 | 3/4 | 3.75 | 3.56 | 228.0 | 0.4418 | 0.23 | 19.88 | 0.011 ¹ |

| | | | | |
|--|----------------|---|--------------------|-------------------|
| tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587 | Job | 17012.45 - CT11180C | Page | 41 of 44 |
| | Project | 150' Guyed Tower - 130 Vernon Road Bolton, CT | Date | 13:20:26 04/20/17 |
| | Client | T-Mobile | Designed by | TJL |

| Section No. | Elevation ft | Size | L ft | L _u ft | Kl/r | A in ² | P _u K | φP _n K | Ratio $\frac{P_u}{\phi P_n}$ |
|-------------|-----------------|------|---------|----------------------|-------|----------------------|---------------------|----------------------|---------------------------------|
| T5 | 80 - 60 | 3/4 | 3.75 | 3.56 | 228.0 | 0.4418 | 0.40 | 19.88 | 0.020 ¹ ✓ |
| T6 | 60 - 40 | 3/4 | 3.75 | 3.56 | 228.0 | 0.4418 | 0.36 | 19.88 | 0.018 ¹ ✓ |
| T7 | 40 - 20 | 3/4 | 3.75 | 3.56 | 228.0 | 0.4418 | 0.20 | 19.88 | 0.010 ¹ ✓ |
| T8 | 20 - 5 | 3/4 | 3.75 | 3.54 | 226.7 | 0.4418 | 0.29 | 19.88 | 0.015 ¹ ✓ |

¹ P_u / φP_n controls

Bottom Girt Design Data (Tension)

| Section No. | Elevation ft | Size | L ft | L _u ft | Kl/r | A in ² | P _u K | φP _n K | Ratio $\frac{P_u}{\phi P_n}$ |
|-------------|-----------------|------|---------|----------------------|-------|----------------------|---------------------|----------------------|---------------------------------|
| T1 | 150 - 140 | 3/4 | 3.75 | 3.58 | 229.3 | 0.4418 | 0.43 | 19.88 | 0.022 ¹ ✓ |
| T2 | 140 - 120 | 3/4 | 3.75 | 3.58 | 229.3 | 0.4418 | 0.22 | 19.88 | 0.011 ¹ ✓ |
| T3 | 120 - 100 | 3/4 | 3.75 | 3.58 | 229.3 | 0.4418 | 0.18 | 19.88 | 0.009 ¹ ✓ |
| T4 | 100 - 80 | 3/4 | 3.75 | 3.56 | 228.0 | 0.4418 | 0.43 | 19.88 | 0.021 ¹ ✓ |
| T5 | 80 - 60 | 3/4 | 3.75 | 3.56 | 228.0 | 0.4418 | 0.36 | 19.88 | 0.018 ¹ ✓ |
| T6 | 60 - 40 | 3/4 | 3.75 | 3.56 | 228.0 | 0.4418 | 0.23 | 19.88 | 0.012 ¹ ✓ |
| T7 | 40 - 20 | 3/4 | 3.75 | 3.56 | 228.0 | 0.4418 | 0.26 | 19.88 | 0.013 ¹ ✓ |
| T8 | 20 - 5 | 3/4 | 3.75 | 3.54 | 226.7 | 0.4418 | 7.97 | 19.88 | 0.401 ¹ ✓ |
| T9 | 5 - 0 | 3/4 | 0.38 | 0.17 | 10.7 | 0.4418 | 1.36 | 19.88 | 0.068 ¹ ✓ |

¹ P_u / φP_n controls

Top Guy Pull-Off Design Data (Tension)

| Section No. | Elevation ft | Size | L ft | L _u ft | Kl/r | A in ² | P _u K | φP _n K | Ratio $\frac{P_u}{\phi P_n}$ |
|-------------|-----------------|-------|---------|----------------------|-------|----------------------|---------------------|----------------------|---------------------------------|
| T1 | 150 - 140 | 1 1/4 | 3.75 | 3.58 | 137.6 | 1.2272 | 4.48 | 55.22 | 0.081 ¹ ✓ |
| T5 | 80 - 60 | 1 1/4 | 3.75 | 3.56 | 136.8 | 1.2272 | 5.91 | 55.22 | 0.107 ¹ ✓ |

| | | |
|--|---|----------------------------------|
| tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587 | Job 17012.45 - CT11180C | Page 42 of 44 |
| | Project 150' Guyed Tower - 130 Vernon Road Bolton, CT | Date 13:20:26 04/20/17 |
| | Client T-Mobile | Designed by TJL |

| Section No. | Elevation ft | Size | L ft | L _u ft | Kl/r | A in ² | P _u K | φP _n K | Ratio $\frac{P_u}{\phi P_n}$ |
|-------------|-----------------|------|---------|----------------------|------|----------------------|---------------------|----------------------|---------------------------------|
| | | | | | | | | | ✓ |

¹ P_u / φP_n controls

Torque-Arm Top Design Data

| Section No. | Elevation ft | Size | L ft | L _u ft | Kl/r | A in ² | P _u K | φP _n K | Ratio $\frac{P_u}{\phi P_n}$ |
|-------------|-----------------|------------|---------|----------------------|------|----------------------|---------------------|----------------------|---------------------------------|
| T2 | 140 - 120 (444) | 2L3x3x5/16 | 7.76 | 7.66 | 99.7 | 3.5500 | 10.46 | 115.02 | 0.091 ¹ ✓ |
| T2 | 140 - 120 (445) | 2L3x3x5/16 | 7.76 | 7.66 | 99.7 | 3.5500 | 9.67 | 115.02 | 0.084 ¹ ✓ |
| T2 | 140 - 120 (453) | 2L3x3x5/16 | 7.76 | 7.66 | 99.7 | 3.5500 | 10.27 | 115.02 | 0.089 ¹ ✓ |
| T2 | 140 - 120 (454) | 2L3x3x5/16 | 7.76 | 7.66 | 99.7 | 3.5500 | 10.39 | 115.02 | 0.090 ¹ ✓ |
| T2 | 140 - 120 (459) | 2L3x3x5/16 | 7.76 | 7.66 | 99.7 | 3.5500 | 10.35 | 115.02 | 0.090 ¹ ✓ |
| T2 | 140 - 120 (460) | 2L3x3x5/16 | 7.76 | 7.66 | 99.7 | 3.5500 | 9.67 | 115.02 | 0.084 ¹ ✓ |

¹ P_u / φP_n controls

Torque-Arm Bottom Design Data

| Section No. | Elevation ft | Size | L ft | L _u ft | Kl/r | A in ² | P _u K | φP _n K | Ratio $\frac{P_u}{\phi P_n}$ |
|-------------|-----------------|------------|---------|----------------------|------|----------------------|---------------------|----------------------|---------------------------------|
| T2 | 140 - 120 (449) | 2L3x3x5/16 | 6.95 | 6.85 | 89.2 | 3.5500 | 3.98 | 115.02 | 0.035 ¹ ✓ |
| T2 | 140 - 120 (450) | 2L3x3x5/16 | 6.95 | 6.85 | 89.2 | 3.5500 | 4.07 | 115.02 | 0.035 ¹ ✓ |
| T2 | 140 - 120 (455) | 2L3x3x5/16 | 6.95 | 6.85 | 89.2 | 3.5500 | 3.74 | 115.02 | 0.033 ¹ ✓ |
| T2 | 140 - 120 (456) | 2L3x3x5/16 | 6.95 | 6.85 | 89.2 | 3.5500 | 3.72 | 115.02 | 0.032 ¹ ✓ |
| T2 | 140 - 120 (461) | 2L3x3x5/16 | 6.95 | 6.85 | 89.2 | 3.5500 | 3.75 | 115.02 | 0.033 ¹ ✓ |
| T2 | 140 - 120 (462) | 2L3x3x5/16 | 6.95 | 6.85 | 89.2 | 3.5500 | 3.79 | 115.02 | 0.033 ¹ ✓ |

¹ P_u / φP_n controls

| | | |
|--|---|----------------------------------|
| tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587 | Job 17012.45 - CT11180C | Page 43 of 44 |
| | Project 150' Guyed Tower - 130 Vernon Road Bolton, CT | Date 13:20:26 04/20/17 |
| | Client T-Mobile | Designed by TJL |

Section Capacity Table

| Section No. | Elevation ft | Component Type | Size | Critical Element | P K | ϕP_{allow} K | % Capacity | Pass Fail | |
|-------------|--------------|-----------------------|------------|------------------|--------|--------------------|-----------------|-----------|------|
| T1 | 150 - 140 | Leg | 2 | 2 | -16.63 | 114.23 | 14.6 | Pass | |
| T2 | 140 - 120 | Leg | 2 | 34 | -28.88 | 111.48 | 25.9 | Pass | |
| T3 | 120 - 100 | Leg | 2 | 91 | -30.80 | 111.48 | 27.6 | Pass | |
| T4 | 100 - 80 | Leg | 2 1/4 | 148 | -30.67 | 148.30 | 20.7 | Pass | |
| T5 | 80 - 60 | Leg | 2 1/4 | 205 | -35.62 | 148.30 | 24.0 | Pass | |
| T6 | 60 - 40 | Leg | 2 1/4 | 262 | -39.71 | 148.30 | 26.8 | Pass | |
| T7 | 40 - 20 | Leg | 2 1/4 | 319 | -40.56 | 148.30 | 27.4 | Pass | |
| T8 | 20 - 5 | Leg | 2 1/2 | 376 | -40.24 | 188.16 | 21.4 | Pass | |
| T9 | 5 - 0 | Leg | 2 1/2 | 422 | -42.80 | 187.85 | 22.8 | Pass | |
| T1 | 150 - 140 | Diagonal | 3/4 | 24 | -1.35 | 6.89 | 19.6 | Pass | |
| T2 | 140 - 120 | Diagonal | 3/4 | 77 | -2.48 | 6.69 | 37.1 | Pass | |
| T3 | 120 - 100 | Diagonal | 3/4 | 104 | -0.65 | 6.69 | 9.8 | Pass | |
| T4 | 100 - 80 | Diagonal | 3/4 | 161 | -1.30 | 6.77 | 19.2 | Pass | |
| T5 | 80 - 60 | Diagonal | 3/4 | 260 | -1.38 | 6.77 | 20.5 | Pass | |
| T6 | 60 - 40 | Diagonal | 3/4 | 313 | -0.99 | 6.77 | 14.7 | Pass | |
| T7 | 40 - 20 | Diagonal | 3/4 | 331 | -0.47 | 6.77 | 6.9 | Pass | |
| T8 | 20 - 5 | Diagonal | 3/4 | 394 | -0.97 | 6.78 | 14.3 | Pass | |
| T9 | 5 - 0 | Diagonal | 3/4 | 427 | -2.88 | 7.54 | 38.1 | Pass | |
| T9 | 5 - 0 | Horizontal | 4x1/2 | 433 | 0.25 | 64.80 | 0.4 | Pass | |
| T1 | 150 - 140 | Top Girt | 3/4 | 6 | -0.08 | 3.87 | 2.2 | Pass | |
| T2 | 140 - 120 | Top Girt | 3/4 | 37 | -1.06 | 3.87 | 27.2 | Pass | |
| T3 | 120 - 100 | Top Girt | 3/4 | 94 | -0.04 | 3.87 | 0.9 | Pass | |
| T4 | 100 - 80 | Top Girt | 3/4 | 152 | -0.16 | 3.92 | 4.0 | Pass | |
| T5 | 80 - 60 | Top Girt | 3/4 | 209 | -0.30 | 3.92 | 7.6 | Pass | |
| T6 | 60 - 40 | Top Girt | 3/4 | 266 | -0.22 | 3.92 | 5.5 | Pass | |
| T7 | 40 - 20 | Top Girt | 3/4 | 322 | 0.20 | 19.88 | 1.0 | Pass | |
| T8 | 20 - 5 | Top Girt | 3/4 | 379 | 0.29 | 19.88 | 1.5 | Pass | |
| T1 | 150 - 140 | Bottom Girt | 3/4 | 8 | -0.30 | 3.87 | 7.7 | Pass | |
| T2 | 140 - 120 | Bottom Girt | 3/4 | 40 | -0.10 | 3.87 | 2.5 | Pass | |
| T3 | 120 - 100 | Bottom Girt | 3/4 | 98 | -0.07 | 3.87 | 1.7 | Pass | |
| T4 | 100 - 80 | Bottom Girt | 3/4 | 155 | -0.29 | 3.92 | 7.4 | Pass | |
| T5 | 80 - 60 | Bottom Girt | 3/4 | 211 | -0.21 | 3.92 | 5.3 | Pass | |
| T6 | 60 - 40 | Bottom Girt | 3/4 | 268 | -0.05 | 3.92 | 1.4 | Pass | |
| T7 | 40 - 20 | Bottom Girt | 3/4 | 327 | 0.26 | 19.88 | 1.3 | Pass | |
| T8 | 20 - 5 | Bottom Girt | 3/4 | 382 | 7.97 | 19.88 | 40.1 | Pass | |
| T9 | 5 - 0 | Bottom Girt | 3/4 | 424 | 1.36 | 19.88 | 6.8 | Pass | |
| T2 | 140 - 120 | Guy A@138 | 9/16 | 458 | 11.33 | 21.00 | 53.9 | Pass | |
| T5 | 80 - 60 | Guy A@70 | 11/16" | 468 | 12.50 | 30.00 | 41.7 | Pass | |
| T2 | 140 - 120 | Guy B@138 | 9/16 | 452 | 11.87 | 21.00 | 56.5 | Pass | |
| T5 | 80 - 60 | Guy B@70 | 11/16" | 467 | 12.99 | 30.00 | 43.3 | Pass | |
| T2 | 140 - 120 | Guy C@138 | 9/16 | 442 | 11.99 | 21.00 | 57.1 | Pass | |
| T5 | 80 - 60 | Guy C@70 | 11/16" | 463 | 13.18 | 30.00 | 43.9 | Pass | |
| T1 | 150 - 140 | Top Guy | 1 1/4 | 446 | -2.82 | 14.64 | 19.2 | Pass | |
| T5 | 80 - 60 | Pull-Off@138 | 1 1/4 | 464 | 5.91 | 55.22 | 10.7 | Pass | |
| T2 | 140 - 120 | Torque Arm Top@138 | 2L3x3x5/16 | 444 | 10.46 | 115.02 | 9.1 | Pass | |
| T2 | 140 - 120 | Torque Arm Bottom@138 | 2L3x3x5/16 | 449 | -7.30 | 75.67 | 9.6 | Pass | |
| | | | | | | | Summary | | |
| | | | | | | | Leg (T3) | 27.6 | Pass |
| | | | | | | | Diagonal (T9) | 38.1 | Pass |
| | | | | | | | Horizontal (T9) | 0.4 | Pass |
| | | | | | | | Top Girt | 27.2 | Pass |

| | | |
|--|---|----------------------------------|
| tnxTower Centek Engineering Inc. 63-2 North Branford Rd. Branford, CT 06405 Phone: (203) 488-0580 FAX: (203) 488-8587 | Job 17012.45 - CT11180C | Page 44 of 44 |
| | Project 150' Guyed Tower - 130 Vernon Road Bolton, CT | Date 13:20:26 04/20/17 |
| | Client T-Mobile | Designed by TJL |

| Section No. | Elevation ft | Component Type | Size | Critical Element | P K | σP_{allow} K | % Capacity | Pass Fail |
|-------------|--------------|----------------|------|------------------|-----|------------------------|-------------|-------------|
| | | | | | | (T2) | | |
| | | | | | | Bottom Girt (T8) | 40.1 | Pass |
| | | | | | | Guy A (T2) | 53.9 | Pass |
| | | | | | | Guy B (T2) | 56.5 | Pass |
| | | | | | | Guy C (T2) | 57.1 | Pass |
| | | | | | | Top Guy Pull-Off (T1) | 19.2 | Pass |
| | | | | | | Torque Arm Top (T2) | 9.1 | Pass |
| | | | | | | Torque Arm Bottom (T2) | 9.6 | Pass |
| | | | | | | Bolt Checks | 23.3 | Pass |
| | | | | | | RATING = | 57.1 | Pass |

Guyed Tower Base Foundation:

Input Data:

Tower Data

Shear Force = Shear := 1-kip (User Input from tnxTower)
 Axial Force = Axial := 114-kip (User Input from tnxTower)
 Tower Height = $H_t := 150\text{-ft}$ (User Input)

Footing Data:

Overall Depth of Footing = $D_f := 3.0\text{-ft}$ (User Input)
 Length of Pier = $L_p := 2.25\text{-ft}$ (User Input)
 Extension of Pier Above Grade = $L_{pag} := 0.5\text{-ft}$ (User Input)
 Diameter of Pier = $D_p := 2.5\text{-ft}$ (User Input)
 Width of Pad = $W_{pad} := 7\text{-ft}$ (User Input)
 Thickness of Pad = $t_{pad} := 1.25\text{-ft}$ (User Input)

Material Properties:

Concrete Compressive Strength = $f_c := 3000\text{-psi}$ (User Input)
 Steel Reinforcement Yield Strength = $f_y := 60000\text{-psi}$ (User Input)
 Internal Friction Angle of Soil = $\Phi_s := 30\text{-deg}$ (User Input)
 Ultimate Soil Bearing Capacity = $q_s := 8000\text{-psf}$ (User Input)
 Unit Weight of Soil = $\gamma_{soil} := 120\text{-pcf}$ (User Input)
 Unit Weight of Concrete = $\gamma_{conc} := 150\text{-pcf}$ (User Input)
 Foundation Bouyancy = Bouyancy := 0 (User Input) (Yes=1 / No=0)
 Depth to Neglect = $n := 0\text{-ft}$ (User Input)
 Cohesion of Clay Type Soil = $c := 0\text{-ksf}$ (User Input) (Use 0 for Sandy Soil)
 Seismic Zone Factor = $Z := 2$ (User Input)
 Coefficient of Friction Between Concrete = $\mu := 0.45$ (User Input)

Calculated Factors:

Coefficient of Lateral Soil Pressure = $K_p := \frac{1 + \sin(\Phi_s)}{1 - \sin(\Phi_s)} = 3$

Load Factor = $LF := \begin{cases} 1.333 & \text{if } H_t \leq 700\text{-ft} \\ 1.7 & \text{if } H_t \geq 1200\text{-ft} \\ 1.333 + \left(\frac{H_t - 700\text{ft}}{1200\text{ft} - 700\text{ft}} \right) \cdot 0.4 & \text{otherwise} \end{cases} = 1.333$

Stability of Footing:

Adjusted Concrete Unit Weight = $\gamma_c := \text{if}(\text{Bouyancy} = 1, \gamma_{\text{conc}} - 62.4\text{pcf}, \gamma_{\text{conc}}) = 150\text{-pcf}$

Adjusted Soil Unit Weight = $\gamma_s := \text{if}(\text{Bouyancy} = 1, \gamma_{\text{soil}} - 62.4\text{pcf}, \gamma_{\text{soil}}) = 120\text{-pcf}$

Passive Pressure = $P_{\text{top}} := 0$

$$P_{\text{bot}} := K_p \cdot \gamma_s \cdot D_f + c \cdot 2 \cdot \sqrt{K_p} = 1.08\text{-ksf}$$

$$P_{\text{ave}} := \frac{P_{\text{top}} + P_{\text{bot}}}{2} = 0.54\text{-ksf}$$

$$A_p := D_p \cdot L_p = 5.625$$

Soil Shear Resistance = $Sl_1 := P_{\text{ave}} \cdot A_p = 3.04\text{-kip}$

Weight of Concrete = $WT_c := \left(\frac{1}{4} \cdot \pi \cdot D_p^2 \cdot L_p + W_{\text{pad}}^2 \cdot t_{\text{pad}} \right) \cdot \gamma_c = 10.84\text{-kip}$

Total Weight = $WT_{\text{tot}} := WT_c + \text{Axial} = 124.84\text{-kip}$

Soil/Concrete Friction Resistance = $Sl_2 := \mu \cdot WT_{\text{tot}} = 56.18\text{-kips}$

Total Sliding Resistance = $Sl_{\text{tot}} := Sl_1 + Sl_2 = 59.22\text{-kips}$

Sliding Resistance Ratio = $\text{Sliding_Resistance_ratio} := \frac{0.75Sl_{\text{tot}}}{\text{Shear}} = 44.41$

$$\text{Sliding_Resistance_Check} := \text{if} \left(\left(\frac{\text{Shear}}{0.75Sl_{\text{tot}}} < 1.0 \right), \text{"Okay"}, \text{"No Good"} \right)$$

Sliding_Resistance_Check = "Okay"

Bearing Pressure Caused by Footing:

Maximum Pressure in Mat = $P_{\text{max}} := \frac{WT_{\text{tot}}}{W_{\text{pad}}} = 2.55\text{-ksf}$

Max_Pressure_Check := $\text{if}(P_{\text{max}} < 0.6q_s, \text{"Okay"}, \text{"No Good"})$

Max_Pressure_Check = "Okay"

Rock Anchor Foundation Analysis:

Input Data:

Max Pier Reactions:

Uplift = Uplift := 18-kips *user input*
Shear = Shear := 29-kips *user input*

Rock Anchor Properties:

Number of Anchors = $N_{\text{anchor}} := 2$ *user input*
Hole Diameter = $\text{hole}_d := 3.00\text{in}$ *user input*
Ultimate Bond Stress Between
Rock and Grout = $\sigma_{\text{bond}} := 60\text{-psi}$ *user input*
Rock Anchor Ultimate Strength = $F_u := 150.0\text{ksi}$ *user input*
Rock Anchor Yield Strength = $F_y := 127.7\text{ksi}$ *user input*
Rock Anchor Diameter = $d_{\text{ra}} := 1.375\text{in}$ *user input*
Threads per Inch = $n := 6$ *user input*
 $\eta := 0.55$ *user input*

Rock Anchor Tension/Shear Check:

Net Area of Bolt = $A_n := \frac{\pi}{4} \cdot \left(d_{ra} - \frac{0.9743 \cdot \text{in}}{n} \right)^2 = 1.155 \cdot \text{in}^2$

Maximum Tensile Force = $T_{Max} := \frac{\text{Uplift}}{N_{\text{anchor}}} = 9 \cdot \text{kips}$

Maximum Shear Force = $V_{Max} := \frac{\text{Shear}}{N_{\text{anchor}}} = 14.5 \cdot \text{kips}$

Design Tensile Strength = $\Phi R_{nt} := 0.8 \cdot F_u \cdot A_n = 138.586 \cdot \text{k}$

Bolt Steel FS = $\frac{1}{\frac{T_{Max} + \frac{V_{Max}}{\eta}}{\Phi R_{nt}}} = 3.9$

Condition1 = $\text{Condition1} := \text{if} \left[\frac{\left(T_{Max} + \frac{V_{Max}}{\eta} \right)}{\Phi R_{nt}} \leq 1.00, \text{"OK"}, \text{"Overstressed"} \right]$

Condition1 = "OK"

Rock Anchor Req'd Development Length in Rock:

Rock/Grout Bond Length Provided = $L_{bprov} := 29 \cdot \text{ft}$

Required Rock/Grout Bond Length = $L_{breq} := \frac{T_{Max}}{0.5 \pi \cdot \text{hole}_d \cdot \sigma_{\text{bond}}} = 2.65 \cdot \text{ft}$

Anchor Bond FS = $\frac{L_{bprov}}{L_{breq}} = 10.9$

Bond_Length_Check := $\text{if} \left(\frac{L_{breq}}{L_{bprov}} \leq 1.00, \text{"OK"}, \text{"Increase Length"} \right)$

Bond_Length_Check = "OK"

| | |
|-----------------------------------|---|
| RAN Template: 701D_WU21 | A&L Template: 701D_WU21_2QP |
|-----------------------------------|---|

CT11180C_0.1_L700

Section 1 - Site Information

| | | |
|--|---|--------------------------------|
| Site ID: CT11180C | Site Name: Bolton Ct._1 | Latitude: 41.80264800 |
| Status: Final | Site Class: Self Support Tower | Longitude: -72.44121300 |
| Version: 0.1 | Site Type: Structure Non Building | Address: 130 Vernon Rd. |
| Project Type: L700 | Solution Type: | City, State: Bolton, CT |
| Approved: 3/23/2017 6:45:03 AM | Plan Year: | Region: NORTHEAST |
| Approved By: GSM1900\BAIter | Market: CONNECTICUT | |
| Last Modified: 3/23/2017 6:45:03 AM | Vendor: Ericsson | |
| Last Modified By: GSM1900\BAIter | Landlord: Mountaintop Enterprises Inc. | |

| | | | | |
|--------------------------------|-------------------------|-----------------------------------|---------------------|---------------------|
| RAN Template: 701D_WU21 | | AL Template: 701D_WU21_2QP | | |
| Sector Count: 2 | Antenna Count: 4 | Coax Line Count: 4 | TMA Count: 2 | RRU Count: 2 |

Section 2 - Existing Template Images

----- This section is intentionally blank. -----

Section 3 - Proposed Template Images

---- This section is intentionally blank. ----

Section 4 - Siteplan Images

---- This section is intentionally blank. ----

| | |
|-----------------------------------|---|
| RAN Template: 701D_WU21 | A&L Template: 701D_WU21_2QP |
|-----------------------------------|---|

CT11180C_0.1_L700

Section 5 - RAN Equipment

Existing RAN Equipment

----- This section is intentionally blank. -----

Proposed RAN Equipment

Template: 701D_WU21

| Enclosure | 1 | 2 |
|----------------------------|---|-----------------------------------|
| Enclosure Type | RBS 6131 | Ancillary Equipment |
| Baseband | <div style="display: flex; gap: 5px;"> <div style="border: 1px solid gray; padding: 2px;">DUW30 U2100</div> <div style="border: 1px solid gray; padding: 2px;">DUS41 L2100 L700</div> <div style="border: 1px solid gray; padding: 2px;">DUW30 U1900</div> </div> | |
| Hybrid Cable System | | Ericsson 9x18 HCS *Select Length* |
| Multiplexer | XMU | |
| Radio | <div style="border: 1px solid gray; padding: 2px;">RU22 (x3) U2100</div> | |

RAN Scope of Work:

Replace existing S8000 GSM cabinet with 3106 cabinet. Upgrade 3106 to 6131. Swap existing Dual with AIR21 B4A/B2P and add 8ft B12 passive antenna. Add DUW30, DUS41. Add RRU B2 and B12. Add fibers. Remove GSM TMA.

RAN Template: 701D_WU21
 A&L Template: 701D_WU21_2QP

CT11180C_0.1_L700



Section 6 - A&L Equipment

Existing Template: Custom
 Proposed Template: 701D_WU21_2QP

| Sector 1 (Proposed) view from behind | | | | |
|--|---|----|--|--|
| Coverage Type | A - Outdoor Macro | | | |
| Antenna | 1 | | 2 | |
| Antenna Model | Ericsson - AIR21 KRC118023-1_B2P_B4A (Quad) | | CommScope - SBNH-1D65C (Quad) | |
| Azimuth | 30 | | 30 | |
| M. Tilt | 0 | | 0 | |
| Height | 180 | | 180 | |
| Ports | P1 | P2 | P3 | P4 |
| Active Tech. | U2100 L2100 | | U2100 | L700 |
| Dark Tech. | | | | |
| Restricted Tech. | | | | |
| Decomm. Tech. | | | | |
| E. Tilt | 2 | | 2 | 2 |
| Cables | Fiber Jumper - 15 ft. | | 1-5/8" Coax - 200 ft. 1-5/8" Coax - 200 ft. | Fiber Jumper - 15 ft. Fiber Jumper - 15 ft. |
| TMA's | | | Generic Style 1B - Twin AWS | |
| Diplexers / Combiners | | | | |
| Radio | | | | RRUS11 B12 |
| Sector Equipment | | | | |
| Unconnected Equipment: Scope of Work: Interim integrate U2100/L2100 in mixed mode until full entitlement | | | | |

RAN Template: 701D_WU21
 A&L Template: 701D_WU21_2QP

CT11180C_0.1_L700

| Sector 2 (Proposed) view from behind | | | | |
|--|---|----|--|--|
| Coverage Type | A - Outdoor Macro | | | |
| Antenna | 1 | | 2 | |
| Antenna Model | Ericsson - AIR21 KRC118023-1_B2P_B4A (Quad) | | CommScope - SBNH-1D65C (Quad) | |
| Azimuth | 150 | | 150 | |
| M. Tilt | 0 | | 0 | |
| Height | 180  | | 180  | |
| Ports | P1 | P2 | P3 | P4 |
| Active Tech. | U2100 L2100 | | U2100 | L700 |
| Dark Tech. | | | | |
| Restricted Tech. | | | | |
| Decomm. Tech. | | | | |
| E. Tilt | 2 | | 2 | 2 |
| Cables | Fiber Jumper - 15 ft. | | 1-5/8" Coax - 200 ft. 1-5/8" Coax - 200 ft. | Fiber Jumper - 15 ft. Fiber Jumper - 15 ft. |
| TMA's | | | Generic Style 1B - Twin AWS | |
| Diplexers / Combiners | | | | |
| Radio | | | | RRUS11 B12 |
| Sector Equipment | | | | |
| Unconnected Equipment: | | | | |
| Scope of Work: | | | | |
| Interim integrate U2100/L2100 in mixed mode until full entitlement | | | | |



WIRELESS COMMUNICATIONS FACILITY

BOLTON CT.._1

SITE ID: CT1180C - U1900

130 VERNON RD

BOLTON, CT 06043

GENERAL NOTES


- ALL WORK SHALL BE IN ACCORDANCE WITH THE 2012 INTERNATIONAL BUILDING CODE AS MODIFIED BY THE 2016 CONNECTICUT SUPPLEMENT, INCLUDING THE TIA/EIA-222 REVISION "G" "STRUCTURAL STANDARDS FOR STEEL ANTENNA TOWERS AND SUPPORTING STRUCTURES." 2016 CONNECTICUT FIRE SAFETY CODE, NATIONAL ELECTRICAL CODE AND LOCAL CODES.
- CONTRACTOR SHALL REVIEW ALL DRAWINGS AND SPECIFICATIONS IN THE CONTRACT DOCUMENT SET. CONTRACTOR SHALL COORDINATE ALL WORK SHOWN IN THE SET OF DRAWINGS. THE CONTRACTOR SHALL PROVIDE A COMPLETE SET OF DRAWINGS TO ALL SUBCONTRACTORS AND ALL RELATED PARTIES. THE SUBCONTRACTORS SHALL EXAMINE ALL THE DRAWINGS AND SPECIFICATIONS FOR THE INFORMATION THAT AFFECTS THEIR WORK.
- CONTRACTOR SHALL PROVIDE A COMPLETE BUILD-OUT WITH ALL FINISHES, STRUCTURAL, MECHANICAL, AND ELECTRICAL COMPONENTS AND PROVIDE ALL ITEMS AS SHOWN OR INDICATED ON THE DRAWINGS OR IN THE WRITTEN SPECIFICATIONS.
- CONTRACTOR SHALL FURNISH ALL MATERIAL, LABOR AND EQUIPMENT TO COMPLETE THE WORK AND FURNISH A COMPLETED JOB ALL IN ACCORDANCE WITH LOCAL AND STATE GOVERNING AUTHORITIES AND OTHER AUTHORITIES HAVING LAWFUL JURISDICTION OVER THE WORK.
- CONTRACTOR SHALL SECURE AND PAY FOR ALL PERMITS AND ALL INSPECTIONS REQUIRED AND SHALL ALSO PAY FEES REQUIRED FOR THE GENERAL CONSTRUCTION, PLUMBING, ELECTRICAL AND HVAC. PERMITS SHALL BE PAID FOR BY THE RESPECTIVE SUBCONTRACTORS.
- CONTRACTOR SHALL MAINTAIN A CURRENT SET OF DRAWINGS AND SPECIFICATIONS ON SITE AT ALL TIMES AND INSURE DISTRIBUTION OF NEW DRAWINGS TO SUBCONTRACTORS AND OTHER RELEVANT PARTIES AS SOON AS THEY ARE MADE AVAILABLE. ALL OLD DRAWINGS SHALL BE MARKED VOID AND REMOVED FROM THE CONTRACT AREA. THE CONTRACTOR SHALL FURNISH AN "AS-BUILT" SET OF DRAWINGS TO OWNER UPON COMPLETION OF PROJECT.
- LOCATION OF EQUIPMENT, AND WORK SUPPLIED BY OTHERS THAT IS DIAGRAMMATICALLY INDICATED ON THE DRAWINGS SHALL BE DETERMINED BY THE CONTRACTOR. THE CONTRACTOR SHALL DETERMINE LOCATIONS AND DIMENSIONS SUBJECT TO STRUCTURAL CONDITIONS AND WORK OF THE SUBCONTRACTORS.
- THE CONTRACTOR IS SOLELY RESPONSIBLE TO DETERMINE CONSTRUCTION PROCEDURE AND SEQUENCE, AND TO ENSURE THE SAFETY OF THE EXISTING STRUCTURES AND ITS COMPONENT PARTS DURING CONSTRUCTION. THIS INCLUDES THE ADDITION OF WHATEVER SHORING, BRACING, UNDERPINNING, ETC. THAT MAY BE NECESSARY.
- DRAWINGS INDICATE THE MINIMUM STANDARDS, BUT IF ANY WORK SHOULD BE INDICATED TO BE SUBSTANDARD TO ANY ORDINANCES, LAWS, CODES, RULES, OR REGULATIONS BEARING ON THE WORK, THE CONTRACTOR SHALL INCLUDE IN HIS WORK AND SHALL EXECUTE THE WORK CORRECTLY IN ACCORDANCE WITH SUCH ORDINANCES, LAWS, CODES, RULES OR REGULATIONS WITH NO INCREASE IN COSTS.
- ALL UTILITY WORK SHALL BE IN ACCORDANCE WITH LOCAL UTILITY COMPANY REQUIREMENTS AND SPECIFICATIONS.
- ALL EQUIPMENT AND PRODUCTS PURCHASED ARE TO BE REVIEWED BY CONTRACTOR AND ALL APPLICABLE SUBCONTRACTORS FOR ANY CONDITION PER MFR.'S RECOMMENDATIONS. CONTRACTOR TO SUPPLY THESE ITEMS AT NO COST TO OWNER OR CONSTRUCTION MANAGER.
- ANY AND ALL ERRORS, DISCREPANCIES, AND "MISSED" ITEMS ARE TO BE BROUGHT TO THE ATTENTION OF THE T-MOBILE CONSTRUCTION MANAGER DURING THE BIDDING PROCESS BY THE CONTRACTOR. ALL THESE ITEMS ARE TO BE INCLUDED IN THE BID. NO "EXTRA" WILL BE ALLOWED FOR MISSED ITEMS.
- CONTRACTOR SHALL BE RESPONSIBLE FOR ALL ON-SITE SAFETY FROM THE TIME THE JOB IS AWARDED UNTIL ALL WORK IS COMPLETE AND ACCEPTED BY THE OWNER.
- CONTRACTOR TO REVIEW ALL SHOP DRAWINGS AND SUBMIT COPY TO ENGINEER FOR APPROVAL. DRAWINGS MUST BEAR THE CHECKER'S INITIALS BEFORE SUBMITTING TO THE CONSTRUCTION MANAGER FOR REVIEW.
- THE CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS, ELEVATIONS, ANGLES, AND EXISTING CONDITIONS AT THE SITE, PRIOR TO FABRICATION AND/OR INSTALLATION OF ANY WORK IN THE CONTRACT AREA.
- COORDINATION, LAYOUT, FURNISHING AND INSTALLATION OF CONDUIT AND ALL APPURTENANCES REQUIRED FOR PROPER INSTALLATION OF ELECTRICAL AND TELECOMMUNICATION SERVICE SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR.
- ALL DAMAGE CAUSED TO ANY EXISTING STRUCTURE SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR. THE CONTRACTOR WILL BE HELD LIABLE FOR ALL REPAIRS REQUIRED FOR EXISTING STRUCTURES IF DAMAGED DURING CONSTRUCTION ACTIVITIES.
- THE CONTRACTOR SHALL CONTACT "CALL BEFORE YOU DIG" AT LEAST 48 HOURS PRIOR TO ANY EXCAVATIONS AT 1-800-922-4455. ALL UTILITIES SHALL BE IDENTIFIED AND CLEARLY MARKED. CONTRACTOR SHALL MAINTAIN AND PROTECT MARKED UTILITIES THROUGHOUT PROJECT COMPLETION.
- CONTRACTOR SHALL COMPLY WITH OWNERS ENVIRONMENTAL ENGINEER ON ALL METHODS AND PROVISIONS FOR ALL EXCAVATION ACTIVITIES INCLUDING SOIL DISPOSAL. ALL BACKFILL MATERIALS TO BE PROVIDED BY THE CONTRACTOR.

SITE DIRECTIONS

| FROM: | TO: |
|---|-----------------------------------|
| 35 GRIFFIN ROAD SOUTH BLOOMFIELD, CT 06002 | 130 VERNON RD BOLTON, CT 06043 |
| 1. HEAD NORTH ON GRIFFIN ROAD S. TOWARD HARTMAN RD. | 0.21 MI. |
| 2. TAKE THE 2ND RIGHT ONTO DAY HILL RD. | 0.14 MI. |
| 3. TAKE THE 1ST RIGHT ONTO BLUE HILLS AVENUE EXT/CT-187 | 1.89 MI. |
| 4. TURN LEFT ONTO CT-305/OLD WINDSOR RD. | 2.32 MI. |
| 5. STAY STRAIGHT TO GO ONTO BLOOMFIELD AVE/CT-305. | 0.01 MI. |
| 6. MERGE ONTO I-91 S TOWARD HARTFORD | 2.37 MI. |
| 7. MERGE ONTO I-291 E via EXIT 35A TOWARD MANCHESTER | 6.18 MI. |
| 8. TAKE THE EXIT TOWARD I-384/I-84 W/HARTFORD | 0.35 MI. |
| 9. MERGE ONTO I-384 E via THE RAMP ON THE LEFT | 8.85 MI. |
| 10. I-384 E BECOMES US-44 E/BOSTON TURNPIKE | 0.90 MI. |
| 11. TURN LEFT ONTO VERNON RD | 0.53 MI. |
| 12. 130 VERNON RD IS ON THE LEFT | |

VICINITY MAP

SCALE: 1" = 1000'



T-MOBILE RF CONFIGURATION

701D_WU21_2QP

PROJECT SUMMARY

- THE PROPOSED SCOPE OF WORK CONSISTS OF A MODIFICATION TO THE EXISTING UNMANNED TELECOMMUNICATIONS FACILITY INCLUDING THE FOLLOWING:
 - INSTALL TWO (2) PROPOSED T-MOBILE TWIN AWS TOWER MOUNTED AMPLIFIERS (TMAS), (1) PER SECTOR, MOUNTED BEHIND POSITION 2 ANTENNAS.
 - INSTALL (4) NEW T-MOBILE 1/8"Ø COAX CABLES

PROJECT INFORMATION

| | |
|----------------------|--|
| SITE NAME: | BOLTON CT.._1 |
| SITE ID: | CT1180C - U1900 |
| SITE ADDRESS: | 130 VERNON RD BOLTON, CT 06043 |
| APPLICANT: | T-MOBILE NORTHEAST, LLC 35 GRIFFIN ROAD SOUTH BLOOMFIELD, CT 06002 |
| CONTACT PERSON: | BRIAN PAUL (PROJECT MANAGER) TRANSCEND WIRELESS, LLC (860) 550-5971 |
| ENGINEER: | CENTEK ENGINEERING, INC. 63-2 NORTH BRANFORD RD. BRANFORD, CT 06405 |
| PROJECT COORDINATES: | LATITUDE: 41°-48'-07.36" N LONGITUDE: 72°-26'-28.15" W GROUND ELEVATION: 814± AMSL |
| | SITE COORDINATES AND GROUND ELEVATION REFERENCED FROM GOOGLE EARTH. |

SHEET INDEX

| SHT. NO. | DESCRIPTION | REV. |
|----------|---|------|
| T-1 | TITLE SHEET | 0 |
| N-1 | DESIGN BASIS AND SITE NOTES | 0 |
| C-1 | SITE LOCATION PLAN | 0 |
| C-2 | COMPOUND PLAN, ELEVATION AND ANTENNA MOUNTING CONFIG. | 0 |

PROFESSIONAL ENGINEER SEAL



CENTEK engineering
Centered on Solutions™
(203) 498-0390
(203) 498-3897 Fax
632 North Branford Road
Branford, CT 06405
www.CentekEng.com

T-MOBILE NORTHEAST LLC
WIRELESS COMMUNICATIONS FACILITY
BOLTON CT.._1

SITE ID: CT1180C - U1900

130 VERNON RD
BOLTON, CT 06043


DATE: 04/03/17
SCALE: AS NOTED
JOB NO. 17012.45

TITLE SHEET

T-1


Sheet No. 1 of 4

0 06/05/17
REV. DATE
KAWIR
DRAWN BY
CAG
CHK'D BY
CONSTRUCTION DRAWINGS - ISSUED FOR CONSTRUCTION
DESCRIPTION




1 SITE LOCATION PLAN
C-1

SCALE: 1" = 80'



| REV. | DATE | BY | CHK'D BY | DESCRIPTION |
|------|----------|-------|----------|---|
| 0 | 06/05/17 | KAWIR | CAG | CONSTRUCTION DRAWINGS - ISSUED FOR CONSTRUCTION |

PROFESSIONAL ENGINEER SEAL



CEN TEK engineering
Centered on Solutions


(203) 488-0390
(203) 488-3397 Fax
652 North Branford Road
Branford, CT 06405
www.CenTekEng.com

T-MOBILE NORTHEAST LLC
WIRELESS COMMUNICATIONS FACILITY
BOLTON CT..1
SITE ID: CT1180C - U1900
130 VERNON RD
BOLTON, CT 06043


DATE: 04/03/17
SCALE: AS NOTED
JOB NO. 17012.45

SITE LOCATION PLAN


C-1




3
C-2 **EQUIPMENT PLAN**
SCALE: 1/4" = 1'
TRUE NORTH




4
C-2 **EXISTING ANTENNA MOUNTING CONFIGURATION**
SCALE: 1/2" = 1'
130' ELEVATION
TRUE NORTH



5
C-2 **PROPOSED ANTENNA MOUNTING CONFIGURATION**
SCALE: 1/2" = 1'
130' ELEVATION
TRUE NORTH




1
C-2 **COMPOUND PLAN**
SCALE: 1" = 8'
TRUE NORTH




T-MOBILE RAN TEMPLATE:
701D_WU21_2QP
T-MOBILE RF CONFIGURATION:
701D_WU21

TOWER STRUCTURAL NOTE:
1. REFER TO STRUCTURAL EVALUATION LETTER PREPARED BY CENTEK ENGINEERING, INC., PROJ. NO. 17012.45, DATED APRIL 20, 2017 FOR ADDITIONAL INFORMATION AND REQUIREMENTS.
2. ALL ANTENNAS AND COAX TO BE INSTALLED IN ACCORDANCE WITH STRUCTURAL ANALYSIS PROVIDED BY CENTEK ENGINEERING, INC. AND FINAL T-MOBILE RF DATA SHEET.



2
C-2 **TOWER ELEVATION**
SCALE: 1" = 15'



| | |
|--|---|
| PROFESSIONAL ENGINEER SEAL | CONSTRUCTION DRAWINGS - ISSUED FOR CONSTRUCTION |
| DATE: 04/03/17 | SCALE: AS NOTED |
| JOB NO. 17012.45 | COMPOUND PLAN, ELEVATION AND ANTENNA MOUNTING CONFIG. |
| | |
| CENTEK engineering <small>Centered on Solutions</small> (203) 498-0390 Fax (203) 498-3397 632 North Branford Road Branford, CT 06405 www.CentekEng.com | |
| T-MOBILE NORTHEAST LLC WIRELESS COMMUNICATIONS FACILITY BOLTON CT 01101 SITE ID: CT1180C - U1900 130 VERNON RD BOLTON, CT 06043 | |
| C-2 Sheet No. 4 of 4 | |